

The Mining And Metallurgical Journal

Vol. XXIII. No. 2 New York, N. Y. October 15, 1900 Los Angeles, Cal. Price 15 Cents

Table of Contents, page 17

Index to Advertisers, page V

Buyers' Guide, page 32

Diamond Drills



American Diamond Rock Drill Co.
120 Liberty Street
New York
P. O. Box 1442

The Edward P. Allis Company

MILWAUKEE, WISCONSIN. See page VIII

SPECIAL BOOK OFFER

THE PROSPECTOR'S HANDBOOK By J. W. ANDERSON

A Guide for the Prospector in Search of Metal-Bearing or Other Valuable Minerals
SEVENTH EDITION THOROUGHLY REVISED AND MUCH ENLARGED
CONTENTS—Prospecting—Testing Minerals by the Blowpipe—The Character of Minerals—Metals and Metallic Ores—Their Characteristics—Testing—Occurrence, etc.—Other Useful Minerals and Ores—Composition of Various Rocks—Testing by the Wet Process—Assay of Gold—Treatment of Ores—Surveying.
12mo., Cloth, 176 pages, Illustrated, Price, \$1.50

When Order is accompanied by One Year's Subscription to this Paper, Our Price for The Prospector's Handbook is 50 Cents a copy, Postage Paid.

THE MINING AND METALLURGICAL JOURNAL, NEW YORK or LOS ANGELES OFFICE

The Roessler & Hasslacher Chemical Co., 100 William St., New York

CYANIDE



Peroxide of Sodium Chloride of Lime
Hypsulphite of Soda Sulphide of Iron
And other Chemicals for Mining Purposes

Joseph Dixon Crucible Co.

Retorts, Crucibles
Graphite Lubricants
Belt Dressing
Graphite Paints
Lead Pencils and
Graphite Products
of All Kinds

MINERS, IMPORTERS AND MANUFACTURERS OF

Graphite and Plumbago

Send for Production Catalogue

JERSEY CITY, N. J.

Graphite Makes the
Best Lubricant
and Best Paint

We Manufacture and Erect in all Parts of the United States

Steel Frame Mill Buildings, Trestles, Girders

Steel Tanks and Vats of every description

Sheet and Plate Iron Work

Riveted Steel Pipe. Stacks

WM. B. SCAIFE & SONS

ESTABLISHED 1802

PITTSBURGH, PA



Used for Roofing and Siding
of Buildings

ADAMANTINE SHOES AND DIES

CHROME CAST STEEL

THE CANADA PATENT SELF-LOCKING CAM
Tappets, Bosses, Roll Shells & Crusher Plates
Also Rolled Parts for Huntington and Other Mills

These castings are extensively used in all the Mining States, and Territories throughout the world. Guaranteed to prove better and cheaper than any others. Orders solicited subject to above conditions. When ordering send sketch with exact dimensions. Send for Illustrated Circular.

CHROME STEEL WORKS

Kent Ave., Keap and Hooper Sts., BROOKLYN, N. Y.



Stamp shoes.



Canada Cam.

We Make 25 Different
Kinds of

ROCK AND COAL DRILLS

Run by Hand and Compressed Air. Get our catalogue before ordering. Established 1878.
HOWELLS MINING DRILL COMPANY, Plymouth, Pa., U. S. A.

DIAMOND DRILLS MINING MACHINERY

CHICAGO, U. S. A.

PLATINUM

HIGHEST AWARDS at the International Exhibitions of 1851, 1859, 1869, 1873, 1876, 1889, 1893, 1894, for products and manufacture of Platinum and the precious metals.

JOHNSON, MATTHEY & CO., Ltd.,
Founded 1725. Hatton Garden, London

MACHINERY

FOR SALE CHEAP
Hoisting Engines, Air Compressors, Rock Drills, Crushers, Dump Cars, Steam Shovels, Light Locomotives, Relaying Rails, etc. Send for Printed Leaflet just issued.

WILLIS SHAW, 629 N.Y. Life Bldg., CHICAGO

Fulton Engine Works

Estimates Furnished on all Classes of Mining Work

P. O. Box 296, Station "C"

Los Angeles, Cal.

Mining
Milling and
Smelting
Machinery



THE BAKER & ADAMSON
CHEMICAL CO., Manufacturers of

Strictly Chemically Pure Acids and
Chemicals and Ashless Filter Papers

EASTON, PENNSYLVANIA

ST. LOUIS, MO.

For Sale—Cheap

5000 tons 56-lb. Relaying Rails
1500 feet 10 $\frac{1}{2}$ -inch Hydraulic Casing
3 Compound Duplex Worthington Pumping Engines

Immediate Delivery

Correspondence Solicited

C. J. TALLON,

308 Market St., San Francisco, Cal.



For Making Oil and Water Wells and Testing Placer Ground

Sinks and drives 6 or 10-inch pipe through boulders; takes all the loose material out, including gold, as the hole is sunk. Does the work at a very small cost. Drills water and oil wells and mineral test wells through any kind of rock to 100 feet. Remounts. Unexcelled for test and zinc testing.

KEYSTONE DRILLER COMPANY, Beaver Falls, Pa.


If you've any Hoisting to do

6 to 150
H.P.

the Weber Gasoline or Oil Hoist is the thing to do it with. In sizes from 6 to 150 H. P. Single or Double Drum, for Gasoline, Gas or Distillate. Especially suited for mining, ship or quarry use. State size wanted and for what purpose.



Weber Gas & Gasoline Engine Co., P. O. Box 1114 J, Kansas City, Mo.
Chicago Office: 1531 Monadnock Block.



"Union" Hoist Runs on Gasoline Naphtha and Benzine

This cut shows the 10 H.P. "Union" Hoist which lifts ONE TON 125 FT. PER MINUTE. Works down 500 feet.

Double Cylinder Vertical Engine and Hoist Combined. Perfectly governed for economy and steadiness. Can be started instantly. Compact. Strong. Simple. Efficient. Economical. Many in use all over the coast. Sizes from 4 H.P. to 50 H.P. Stationary and Marine Gas and Gasoline Engines up to 100 H.P.

UNION GAS ENGINE CO.

801 HOWARD STREET,

SAN FRANCISCO, CAL.

There is only ONE



MANUFACTURERS OF

Albany Dynamo and Albany Cylinder Oils

If you are not using these Oils, give them a trial at once, and we know the result. You will want no other

ALBANY GREASE

and we are the only makers
LUBRICATES EVERYTHING
Especially Adapted to Mining and Milling Machinery.

Oils are advancing and it will pay to use
ALBANY GREASE at the present prices.

MADE ONLY BY

ADAM COOK'S SONS,
313 West St., New York.

TATUM & BOWEN,
34 & 36 Fremont Street, San Francisco, Cal.
29 & 35 First Street, Portland, Oregon.

81 South Canal Street, Chicago, Illinois.

MONTANA ORE PURCHASING CO.

F. AUG. HEINZE, Pres. and Genl. Mgr.
JOHN MACGINNIS, Vice-Pres.

ARTHUR P. HEINZE, Sec.
STANLEY GIFFORD, Treas.

Authorized Capital, \$2,500,000; Issued, \$2,000,000.

Surplus, \$1,250,000.

PURCHASERS, SMELTERS and REFINERS OF

COPPER, SILVER and GOLD ORES.

Smelting Works: BUTTE, MONT.

Offices: Butte, Mont., and 31 Nassau Street, New York.

WILLIAM H. EMANUEL,


Representing RAND DRILL COMPANY, Air Drills and Compressors,
TRENTON IRON CO., Wire Rope and Bleichert Tramways,
HENRY R. WORTHINGTON and
DEANE STEAM PUMP COMPANY, Holyoke, Mass.
BALL ELECTRIC SYSTEM, Arc Lights and Dynamos.
ROBINS CONVEYING BELT COMPANY.
ROOT IMPROVED WATER TUBE BOILER.

General Mining, Milling,
and Smelting Machinery.

1711-13 Tremont St., Denver, Colorado

FOUR and SIX FOOT FRUE VANNERS

With Brownell "Patent Lip" Flange Belts



After a Concentrator like the Frue Vanner has been on the market nearly two decades, and the sales have constantly increased, it is safe to say it is the "Standard Machine of the World." More Frue Vanners have been sold during the last twelve months than for the same period at any time during the history of the machine. Practical mining men in all parts of the world where mining is carried on will testify as to its merits. It is the "Standard" which all competitors are trying to imitate.

The results obtained by this machine are the "Acme" of concentration, and several cheap and untried machines that have lately come on the market compare by it, and the manufacturers will tell you that they are "just as good, and cheaper, etc." The facts are that no other concentrator made has an equal capacity, or will yield as clean a concentrate with as small loss in the tailings as the Frue Vanner. This amount saved from the lower first cost of an inferior machine counts little in the year's results, when compared with the increased output from a Frue. This machine not only gives better results at both ends of the belt (i. e. clean product and poor tailings), but is operated at less expense and requires less attention than any other machine on the market. At the Alaska Treadwell Mine where they have ordered over 350 Frue Vanners one man attends 48 machines for 12 hour shift.

FOR DESCRIPTIVE PAMPHLETS, ADDRESS

JAS. S. BROWNELL Frue Vanning Machine Co.


WESTERN AGENT

(Successors to Adams & Carter)

132 Market Street

SAN FRANCISCO, CAL.

Spadone's Concentrator Belts Patented



This illustration shows the edge flanging outwardly as it passes over the pulley. This relieves the strain from the top and bottom of the edge by directing the strain automatically to the inside face surface of the edges. Heretofore all belts have been so constructed that when they pass over the pulleys or rolls, a direct strain comes upon the top or at the base of the edges, causing the edges to break away from the body of the belts in a very short time.

We avoid this mechanical defect by our Spadone's Curved Edge.

Belts made to fit any machine—4, 5, and 6 feet wide. Prices and samples on application.

Send us your order for Water, Air Drill, Steam, Suction and Fire HOSE, RUBBER BELTING, RUBBER PACKING and LEATHER BELTING.

Amalgam Plate Cleaners. Our Amalgam Plate Cleaners are made of Pure Rubber in moulds, thus insuring a plate cleaner which will not scratch the plates and a perfect edge which will clean the Amalgam plates evenly. They are made 6 inches long, 3 inches wide and 1/4 inch thick, making a convenient size to handle. Price by mail to any address, each 75 cents. Correspondence solicited.

The Gutta Percha Rubber & Mfg. Co., 30 and 32 Fremont St., San Francisco, Cal.



Eugene Dietzgen Co.
181 Monroe St., Chicago
140 Fifth Ave., New York
Manufacturers and Importers of
Engineering and
Drawing Instruments of every
description.
We carry the largest stock in the West.
Send for our new 224 page ILLUSTRATED CATALOGUE.

Adolf Frese



Maker and Repairer

of Transits, Levels
and all other instru-
ments used in mining.
Fine assorted stock
of Keuffel and Esser
goods. Also Micro-
scopes, Barometers,
Field Glasses, Ther-
mometers, Hydrome-
ters, etc.

126 S. Spring Street, Los Angeles, Cal.

C. L. BERGER & SONS

Successors to

BUFF & BERGER


Mining and
Engineering Transits



Established
1871

With Patent Interchangeable
auxiliary Telescope for use on
top or side in vertical sighting.
Our friends are cautioned
against infringements, foreign
or domestic, as attempts have
been made of late to mislead
the public.
Send for Illustrated Cata-
logue and Manual.

11 Province Court, Boston, Mass.



SMITH & THOMPSON

Manufacturers of

Fine Assay Balances

Write for catalogue


2219 Stout Street, Denver, Colo.

RICHARDS & CO., Ltd.

Headquarters for Assay
Materials of every kind

New York Chicago
12 E. 18th Street 108 Lake Street

Queen No. 4 Assay Balance



Aluminum Beam, Agate Knives and Planes.
Sensibility 1-100 mg. The Best Low-Price Assay
Balance on the Market. Send for Circular.

QUEEN & CO., Optical and Scientific Instrument Works

1010 Chestnut Street
N. Y. Office, 59 Fifth Ave. PHILADELPHIA

CLEANED
WITHOUT
ALTERING
ADJUSTMENT

THE LEVER RULING PEN

SEND FOR DESCRIPTIVE CIRCULAR.
THEO. ALTENEDEK & SONS, PHILADELPHIA.



ENGINEERS' and DRAFTSMEN'S SUPPLIES

Levels and transits of superior make.
F. Weber & Co., 1125 Chestnut St., Philadelphia

L. Manasse Company

Manufacturing

Opticians

88 Madison St.
Chicago

Manufacturers and
Importers of

Architects'
Engineers' and
Surveyors'
Supplies,

Optical instruments of
every description. For
ometers, Thermometers,
Field Glasses, etc. + cata-
logues on application.

Established 1872.
F. E. BRANDIS, SONS & CO.
ENGINEERING
INSTRUMENTS
FOR ALL PURPOSES.
812-814 GATES AVE., BROOKLYN, N. Y.
Catalogues mailed on application.

MEASURING TAPES

High Grade—Steel—Linen—Metallic


Extreme accuracy, reliability and finest quality char-
acterize our goods, and the highest authorities recog-
nize them as THE BEST IN THE WORLD.

Ask Your Dealer for Lufkin Tapes

Lufkin Rule Co., Saginaw, Mich.

N. Y. City Office and Store, 291 Stewart Bldg.

Send for Tape Catalogue No. 6 and get with it a nice
1 foot steel rule gratis.



Engineers', Surveyors' and Assayers' INSTRUMENTS and SUPPLIES

A POSTAL CARD addressed to THE MINING AND
METALLURGICAL JOURNAL will bring you catalogs
and circulars from every house on this page

JUST ISSUED

Hydraulic Power Engineering

8vo, Cloth
Illustrated
360 pages
Price, \$3.50

A Practical Manual on the Concentration and
Transmission of Power by Hydraulic Machin-
ery.

By G. CROYDON MARKS

Member Inst. Mech. Eng., Assoc. M. Inst. C.E., &c.

With over Two Hundred Illustrations,
Diagrams and Tables

D. Van Nostrand Co., Publishers

Copies sent 23 Murray & 27 Warren Sts.
prepaid on receipt of price New York

MINING, Metallurgy, As- saying, Chemistry, Engi- neering and Electrical Books

Send for Catalogue

PHILADELPHIA BOOK CO.

Opposite Post Office Philadelphia, Pa.

Books for

MINERS SURVEYORS
METALLURGISTS ASSAYERS
ENGINEERS CHEMISTS

See Page XV



F.C. Knight & Co.

Successors to Edmund Draper

Manufacturers of

Engineering, Mining and
Surveying Instruments


400-402 Locust Street

Catalogue on
Application Philadelphia

ESTABLISHED IN 1840

HENRY TROEMNER

710 Market Street Philadelphia, Pa.




Assay Balances and Weights

In use in all the U. S. Assay Offices
in America

PRICE LIST ON APPLICATION

No. 045 Button Balances



Sensibility 1-50 Milligramme.

This balance was designed
with a view to furnishing an ac-
curate and reliable balance for
silver button and moderately
accurate gold button work.

It has all the latest improve-
ments and is an up-to-date bal-
ance in every particular.

If you anticipate buying and
want a good balance at a mod-
erate price, write us for particu-
lars; you will be surprised to
find how cheaply this balance
can be purchased.

For complete description of
this and other balances write
for catalogue A.

WM. AINSWORTH & SONS,

Agents for balances and the Brunton Patent Pocket Transit: F. W. Braun & Co., Los Angeles, Cal.; John Taylor & Co., San Francisco, Cal. Agents for the Brunton
Patent Pocket Transit: H. S. Crocker Co., San Francisco, Cal.; Pacific Optical Co., Los Angeles, Cal.

Brunton's Pat. Pocket Mine Transit

The engraving herewith illustrates
Brunton's Pat. Pocket Mine Transit
as it appears when folded ready for the
pocket.

The working parts are enclosed by
an aluminum case, the outside dimen-
sions of which are but 2 1/4 x 2 1/4 x 1 inches
and the total weight but 8 ounces.

There are over five hundred of the
above instruments in daily use at the
present time, and those using them
unite in pronouncing them the most
convenient, accurate and reliable
pocket instruments on the market.

Send for catalogue B.



Actual Size

DENVER, COLORADO. U. S. A.

Chas. C. Moore & Co.,

Watch this Space for Description
of Machinery Mentioned Below.

ENGINEERS AND
DEALERS IN



Send for Catalogue
and
Full Information

Babcock & Wilcox Boilers
McIntosh & Seymour Engines
Hamilton Corliss Engines
N. Y. Safety Automatic Engines
Goubert Feed Water Heaters
Stratton Steam Separators
Snow Steam Pumps
Quimby Screw Pumps

Green's Economizers
Wheeler Condensers
Barnard-Wheeler Cooling Towers
Hoppes Live Steam Purifiers
Edmiston Feed Water Filters
Bundy Steam Traps
Spencer Damper Regulators
Hyatt Roller Bearings

Los Angeles Office: 103 So. Broadway

32 First Street, San Francisco, Cal.

Sizes, 3 to 24 inches
Lengths, up to 25 ft.
Tested to any pressure



Plain Black
Asphalted or Galvanized
Steel or Refined Iron

For Pump Suction and Discharge, Water Conveying to Power Wheels,
Blowing and Ventilating, Exhaust Steam


... WRITE FOR CATALOGUE ...

ABENDROTH AND ROOT MANUFACTURING COMPANY

99 John Street, New York

Agency in London, 2 Jewry Street, Aldgate

Monadnock Block, Chicago



THE GRIFFIN THREE ROLLER ORE MILL.

The Griffin Three Roller Ore Mill is a simply constructed Mill, suitable for working all kinds of ores that require uniformly fine crushing by the wet process. This Mill is a modification of the well-known Chilian Mill, but the rollers run upon a crushing ring or die, which is inclined inwardly at an angle of about 30 degrees, the rollers themselves also being inclined to the central shaft of the Mill, thus utilizing the centrifugal force, as well as the weight of the rollers themselves as a crushing agent. The Griffin Three Roller Ore Mill is therefore a Mill of great strength, and has few wearing parts. We construct these Mills with extreme care, using only the best of raw materials, which are most carefully worked by men who are specialists as mill builders. We sell the Griffin Ore Mill on its determined merits, and will gladly supply full information regarding it to any one.

Send for free illustrated and descriptive catalogue to

Bradley Pulverizer Co., Boston, Mass.



Link-Belt Box Water Elevator
Lifts 300 to 10,000 gallons per minute

LINK-BELT Elevators and Conveyors

for handling Ores, Matte, Coal, Slag,
Cement, Gravel, Clay, Sand, Ashes, etc.

COAL WASHING MACHINERY

Designed
and
Erected


Picking Tables, Shaking Screens, Ventilating Fans, Patent Cast Iron Screw Conveyor, Patent Machine-Moulded Rope Sheaves, Malleable Iron Buckets, Shafting, Pulleys, Gearing, Clutches, etc.

CATALOGUE NO. 25 UPON APPLICATION.

The Link-Belt Machinery Co.

ENGINEERS
FOUNDERS
MACHINISTS

**CHICAGO, U. S. A.
DENVER, 1328 17TH ST.**



"Link-Belt" Breaker—Various Sizes

INDEX TO ADVERTISERS; SEE PAGE 32 FOR BUYERS' GUIDE.

Abbott, W. O.	xii	Dow, Geo. E., Pumping Engine Co.	xiv	Lidgerwood Mfg. Co.	xi	Samuel, Frank	vi
Abendroth & Root Mfg. Co.	ix	Duval Metallic Packing Co.	vi	Link-Belt Machinery Co.	iv	San Francisco Novelty & Plating Works	xiv
Agramonte, C. H. M. y.	xii	Emanuel, Wm. H.	ii	Lord, Geo. W.	ii	San Francisco Pioneer Screen Works	x
Alinsworth, Wm. & Sons	iii	Estey Wire Works Co.	xiv	Lafayette Co.	ii	Santa Fe Route	x
Aluchon Perforated Metal Co., The Robt.	xii	Fairbanks, Morse & Co.	vii	Lyon, M. H.	ii	Seafie & Sons, Wm. B.	i
Allis Co., Edward P.	xiii	Falkenau, Louis	vii	Lytle & Co.	xi	Sell Supply & Tool Co.	xiv
Altender & Sons, Theo.	iii	Fosse, Adolf	ii	McCoy, J. W.	v	Sellby Smelting & Lead Co.	xii
American Diamond Rock Drill Co.	iii	Frue Vanning Machine Co.	ii	McCoy, Percy B.	v	Sexton, J. E.	i
American Injector Co.	vi	Fulton Engine Works	i	McNamara, Geo. G.	v	Shultz Belting Co.	i
American Impulse Wheel Co.	vii	Gates Iron Works	ix	Major, A.	xii	Simonds, Ernest H.	v
Asphalt Pipe Co.	xiv	Globe Machine Works	x	Manasse, C. L.	iii	Simonds & Wainwright	xii
Atlas Pipe Wrench Co.	x	Godfrey, A. G.	xiv	Metallic Cap Mfg. Co.	v	Smith & Thompson	iii
Aubury, L. E.	v	Gold & Silver Extraction Co. of America	xiv	Michigan College of Mines	v	Southern Pacific Railway	x
Bally & Monnig	xii	Goodyear Rubber Co.	ii	Miner, J. F.	xv	Sturtevant Mill Co.	32
Baker & Adamson Chemical Co.	i	Gutta Percha Rubber & Mfg. Co.	x	Mining & Metallurgical Journal Book Dpt.	xv	Sullivan Machinery Co.	viii
Baker & Co.	iii	Haines Co., Wm. S.	xii	Montana Ore Purchasing Co.	ii	Summerville Fernoline Works	vi
Bergner & Sons, C. L.	iii	Hamlin & Morrison	xii	Morgan-Watson Mining & Construction Co.	x	Tallon, C. J.	i, vi
Bradley Pulverizer Co.	vi	Hanks, A. A.	v	Murray Iron Works Co.	xvi	Taylor & Co., John	xiii
Brandis & Son, F. E.	iii	Harlow Mining Agency	v	New Standard Co. (Inc.)	vii	Taylor Iron & Steel Co.	vi
Braun Co., F. W.	xiii	Hendy Machine Works, Joshua	xvi	Ogden Assay Office	xii	Thompson & Boyle	xiv
Bullock Mfg. Co., M. C.	v	Herrick, G. L.	v	Pacific Tank Co.	xi	Townsend Bros.	vi
Burlingame, E. E.	xii	Hersey, Clarence	xii	Paraffine Paint Co.	xiii	Trenton Iron Co., The	vi
California Anti-Calorie Co.	vi	Hopping, Roy	xi	Patterson, Frank L.	xiii	Troemner, Henry	iii
California Perforating Screen Co.	xiv	Hoskins, Wm.	i	Perez, R. A.	xiii	Union Gas Engine Co.	ii
California Victor Lighting Co.	vi	Howells Mining Drill Co.	i	Philadelphia Book Co.	iii	Van Der Naillen, A.	v
California Wire Works	vi	Ingersoll-Sergeant Drill Co.	viii	Pneumatic Cyanide Process Co.	vi	Van Nostrand Co., D.	iii
Chrome Steel Works	i	Jackson Drill & Manufacturing Co., The	xvi	Pulsometer Steam Pump Co.	xiv	Van Wagonen, Theo. F.	v
Church, John A.	v	Jeffrey Manufacturing Co.	x	Queen & Co.	iii	Volger, Wm. B.	x
Church, Edward S.	xiv	Johnson, Matthey & Co.	i	Reckhart, D. W.	xii	Wade & Wade	xii
Coggeshall Mfg. Co.	xiv	Kelley & Son, Benj. F.	vi	Reed, John T.	xii	Walsh's Sons & Co.	vi
Colorado Iron Works Co.	ix	Kempton, C. W.	v	Richards & Co., Ltd.	iii	Warren Chemical & Mfg. Co.	vi
Cook's Sons, Adam	ii	Keystone Driller Co.	iii	Richey, O. T.	iii	Weber & Co., F.	iii
Courts, W. M.	v	Knight & Co., F. C.	iii	Ricketts & Banks	xii	Weber Gas & Gasoline Engine Co.	ii
Cummins & Sons Co., F. D.	xiii	Leffel & Co., James	vii	Robins Conveying Belt Co.	x	Western Chemical Co.	xiii
Cummings & Swears	xiii	Leschen & Sons Rope Co., A.	xii	Rossler & Hasselbacher Chemical Co.	vii	Wigmore & Sons, Co., John	xvi
Cypress Tank Co.	x	Lexow, Theo.	xiii	Russell & Kinsey	x	Williams Patent Crusher & Pulverizer Co.	xii
Davis, D. Campbell & Co.	x					Wood, Henry E.	xii
Denniston, E. G.	xiv					Yawger, I. C.	xiii
Denver Fire Clay Co.	xiii						
Dietzgen & Co., Eugene	iii						
Dismow, Chas. L.	v						
Dixon Crucible Co., Jos.	i						

Crude Platinum Purchased

To Identify Crude Platinum when found, send 75c. for sample in glass, packed in a strong box. We purchase or refine anything containing Platinum.
BAKER & COMPANY, - Newark, New Jersey.
 New York Office: 120 Liberty Street.

Michigan College of Mines.

An Engineering School with unique location giving it unusual facilities. Distinctive methods of instruction. Special courses given. All work in charge of widely experienced men. Catalogue giving list of graduates and their occupations on application. Address
 F. W. McNair, Pres't, Houghton, Mich.

School of Practical Mining, Civil, Mechanical, of Electrical Engineering, Metallurgy, Cyanide Process, etc.
 Surveying, Architecture, Drawing and Assaying.
A. VAN DER NAILLER, President.
 233 Market Street, San Francisco, Cal.
 OPEN ALL YEAR.
 Assaying of Ores, \$25; Bullion and Chlorination Assay, \$25; Blowpipe Assay, \$10. Full course of Assaying, \$50. Established 1864. Send for Circular.

HEALD'S BUSINESS COLLEGE

24 POST STREET, SAN FRANCISCO, CAL.
 Mining and Civil Engineering Department
 Mathematics, Drafting, Strength of Materials, Chemistry, Assaying, Blow Pipe Analysis, Geology, Mineralogy, Surveying, etc.
 Electrical Department
 Theory and Practice, Construction.
 Business
 Bookkeeping, Shorthand, Typing, Modern Languages, etc.
 Over 1,000 graduates successfully applying their knowledge; 300 graduates annually placed in positions; 25 teachers; individual instruction; can enter at any time. Catalogue and Journal free.

Mining Engineering and Surveying

G. L. HERRICK, Ph.D., President of the University of New Mexico and Director of the University Geological Survey. Consulting Geologist. Specialty, difficult stratigraphy and petrography. Advisory superintendence and reporting in the Southwest. Office for chemical, assay and petrographic determinations for personal reports only. Albuquerque, N.M.

O. T. RICHEY

TUCSON, ARIZONA

Gold, Copper, Silver and Lead Mines and Prospects, carefully and conservatively reported upon, for sale.
 All correspondence confidential.

GEORGE GORDON McNAMARA

Consulting Mining Engineer and Metallurgist

Bedford McNeill Code FLORENCE, ARIZONA

J. F. Milner, E. M. 225 Byrne Bldg. Los Angeles, Cal.
 Consulting Mining Engineer
 Makes examinations and reports on Mining Properties. Twenty-two years experience in Mining work. Ten years in the study of Geology of Southern California, and the Oil formations.
 I can enable me to advise intelligently on Oil lands and Oil stocks. Careful attention given to Oil and Mining Investments.

J. E. Sexton

PLACERVILLE, CAL.

Mining Engineer
 I can furnish developed or undeveloped gold mining properties to responsible parties, on their own terms, and attend to the operating of the same if desired.
 Correspondence solicited

D. Campbell Davies & Co.

REPRESENTING THE LARGEST

European and American Manufacturers of

Mills, Mines and Smelting Machinery Supplies

EXPORT TRADE A SPECIALTY

Apartado No. 83, Durango, Mex.

LEW E. AUBURY

Mining Engineer

ASSAY OFFICE

115 W. First Street, Los Angeles, Cal.

John A. Church
 Mining Engineer and Metallurgist
 11 William Street, New York
 Cable, "SCOTIST"
 Morelog & Neal and Western Union Codes

EDWARD S. COBB

Designing and Consulting

Mechanical and Hydraulic Engineer
 126 Kearney Street, San Francisco, Cal.

Wm. M. Courtis, A.M.
 Assayer and Analytical Chemist

Mining and Metallurgical Engineer

Office: 412 Hammond Building, Permanent Address: 449 4th Ave., Detroit, Mich.

CHAS. L. DIGNOWITY
 Consulting Mining Engineer and Promoter of Mining Companies
 72-78 Devonshire Bldg., Boston, Mass.

State Assay Office

LOUIS FALKENAU
 Analysis of Ores, Metals, Soils, Waters, Industrial Products, Foods, Medicines, etc., etc.
 Court Expert in all branches of Chemical Technology. Working Tests of Ores and Investigation of Metallurgical and Manufacturing Processes. Consultations on all questions of applied chemistry. Instructions given in assaying and all branches of chemistry.
 538 Sacramento St., below Montgomery, S. Francisco, Cal.

Ernest H. Simonds

Late Instructor in Assaying, University of California
 Assays and Analyses
 Laboratory Tests of Ores

Special Attention Given to the Instruction of Students
 521 Sacramento St., cor. Leidesdorff, S. F., Cal.

THE HARLOW MINING AGENCY

W. P. HARLOW, Attorney-at-Law

NOGALES, - - Arizona

Examining and passing upon Mexican titles and reporting mines a specialty. Mines bought and sold. Correspondence solicited.

P. O. Box 191

ABBOT A. HANKS, Chemist and Assayer

Successor to Henry G. Hanks, est. 1869. The supervision of sampling of ores shipped to San Francisco a specialty.
 531 California St. San Francisco.

C. W. Kempton and Percy B. McCoy
 MINING ENGINEERS
 29 Broadway, New York
 Mining, Milling, Metallurgy, Exploration. Cable, Macton, New York. Western Union Code.

J. W. MCCOY
 Consulting Mining Engineer
 1202 Owings Building, Chicago, Ill.

Examinations and Reports on Mining Properties
M. H. LYON, M.E. McNeill's Code Reference, Joplin National Bank
 Joplin, Mo.

Theo. F. Van Wagenen, E.M.
 Consulting, Mining and Hydraulic Engineer...
 1508 Fillmore Street Denver, Colo.



THE HALLIDIE ROPEWAY

For Transporting Ore, Fuel, Earth, Sugar Cane, etc., by Wire Ropes.

SIMPLE, ECONOMICAL, PRACTICAL, DURABLE.

LOADS MECHANICALLY. DUMPS AUTOMATICALLY.

WIRE TRAMWAYS (Single and Double Rope Systems),

Cableways, Logging by Cables, Cable Grips,
Incline Planes, Transmission by Wire Ropes, Automatic Loaders,

PLOWING, SCRAPING AND TRANSPORTING BY WIRE ROPES,
DESIGNED, SUPPLIED AND ERECTED. Estimates Furnished.

CALIFORNIA WIRE WORKS,

19 Fremont St., San Francisco, Cal.

Improved GRIP PULLEY.

Patents Nos. 483,442; 610,353.



EFFECTIVE, SIMPLE, AUTOMATIC.
Saves Wear on Rope and Cable.

Send for Illustrated Pamphlet, No. 22.
Correspondence Solicited.

FEED WATER HEATERS

Selling Feed Water Heaters BY MAIL is our specialty.



18 years as sellers and manufacturers is the price we have paid for our experience. Our improved machinery and methods for manufacturing greatly REDUCES THE COST AND YOU GET THE BENEFIT OF IT.

THE IMPROVED BERRYMAN (KELLEY'S PATENT) WATER TUBE
Feed Water Heater and Purifier

This Heater is designed with special reference to obtaining highest results and greatest durability. All materials are of a quality and weight to successfully withstand years of usage, and workmanship is of the highest grade.

BENJ. F. KELLEY & SON


MANUFACTURERS

91 Liberty Street, New York

U.S. Automatic Injectors

Guaranteed to be the Best and Most Economical

Injectors on the Market




Can be had of

Mitchell Staver & Lewis Co., Portland, Ore.
Mitchell Staver & Lewis Co., Seattle, Wash.
Schaw-Ingram Batcher Co., Sacramento, Cal.
Henshaw, Bulkley & Co., San Francisco, Cal.
And of Jobbers and Dealers generally.

CATALOGUE FREE.

American Injector Co. Detroit, Mich. U.S.A.

Cable Hoist=Conveyors



Manufactured by

The Trenton Iron Co.
Trenton, N. J.

Engineers and Contractors and Sole Licensees in North America for the Bleichert System of Wire Rope Tramways. Also Wire Rope Equipments for Surface and Underground Haulage, etc.

New York Office
Cooper, Hewitt & Co.
17 Burling Slip

Chicago Office
1114 Monadnock Building

Denver, Colo.
W. H. Emanuel
Agent

San Francisco, Cal.
Newton M. Bell
Agent

California Vigorit Powder Co.

MANUFACTURERS OF ...

Dynamite High Explosives and
"Vigorit Low" Blasting Powder

Office: 208 California Street,
San Francisco, Cal.

Works: Point Isabel,
Contra Costa Co., Cal.

WATER PIPE FOR SALE—23,000 feet
20-in. Cast-Iron Water Pipe, made
by R. D. Wood & Co., 170 lbs. to foot, in
12-ft. lengths, in first-class condition, for
re-use. Will be sold in lots to suit.

FRANK SAMUEL,

Harrison Building, Philadelphia, Pa.

PATENTS!

Townsend Brothers Solicitors of Patents

Patents on Inventions secured in all countries. Copyrights, Trade Marks and Labels
Office, 321 Potomac Block
Telephone 847 Los Angeles, Cal.

BOOKS FOR
MINERS
ENGINEERS
CHEMISTS

See Page XV

Preserve Your Mine
Timbers by the Use of Fernoline Wood Preservative

SUMMERVILLE FERNOLINE WORKS, Summerville, S. C.

The California Anti-Caloric Company

STEAM PIPE AND BOILER COVERING

Manufactured under our own Patents and solely from
California Products. ANTI-CALORIC PLASTER; the
best and cheapest Insulating Plaster in the Market

OFFICE: 217-219 Mission Street
SAN FRANCISCO, CAL.

FACTORY, POTRERO Tel., Main 573

"PNEUMATIC" CYANIDE PROCESS

(Patented in U.S., So. African Republic, New Zealand, Victoria, New So. Wales, So. Australia.)



Will do in 7 hours what requires from 2 to 6 days by older methods.

SEND FOR PAMPHLETS.

THE PNEUMATIC CYANIDE PROCESS CO., 306 Boston Bldg., Denver, Colo.

POSSIBLY


YOU HAVE A GOLD MINE

or some other kind of a mine that you intend to equip with machinery, but do not know where to get the best machinery cheapest, or what kind of machinery is best suited to your proposition and your pocket-book. If so, write us, for it is our business to give just such information—in our reading pages usually—but cheerfully by letter if you are in a hurry.

THE MINING AND METALLURGICAL JOURNAL

Hadfield's Manganese Steel

HARD TOUGH



Best Metal known for Stamp Shoes and Dies, Roll Shells, Crusher Plates and Side Liners. Toggles and Toggle Bearings, Gyroscopic Cones and Concaves or Liners, Mine Car Wheels, Coal Crushing Rolls, etc.

TAYLOR IRON AND STEEL CO.
Highbridge, N. J., U. S. A.

Sole Licensees in America under Hadfield System and Patents
All Pacific Coast parties interested please address PARK & LACY Co., San Francisco, Cal.

The Mining And Metallurgical Journal

Entered at the Post Office at New York, N. Y., as Second-Class Mail Matter.

Vol. XXIII. Oct. 15, 1900 No. 2

F. W. EDELSTEN, Editor.
O. S. BREESE, Associate Editor.
J. A. RAWSON, JR., Business Manager.

MAIN OFFICES

32 Broadway, New York, N. Y.
120 North Main St., Los Angeles, Cal.

BRANCH OFFICES:

San Francisco, Cal. - 94-95 Merchants Exchange
Chicago, Ill. - 413, 59 Dearborn St., and
Suite 306, Times-Herald Bldg.
Denver, Colo. - 402-403 Quincy Bldg.
Salt Lake City, Utah - 15 W. Second South St.
Pittsburg, Pa. - W. L. Foulk's Son & Co.

SUBSCRIPTION PRICE:

For United States, Mexico and Canada... \$2.50 per annum
All other countries in the Postal Union... \$3.50 per annum

NOTICE TO SUBSCRIBERS.

Subscribers should notify the publishers promptly if they fail to receive their copies in a reasonable time after the dates of issue—the first and fifteenth of each month. No delay will be caused by the expiration of subscriptions, as, in accordance with the usual custom, the JOURNAL is forwarded until orders to discontinue are received.

ISSUED SEMI-MONTHLY

TABLE OF CONTENTS.

Editorials:

AMERICAN AND FOREIGN COAL EXPORTS..	17
SUSTAINED STRENGTH OF SILVER.....	17
DEADLOCK IN THE IRON TRADE.....	17
THE ANTHRACITE STRIKE.....	17

General Articles:

AMERICAN MACHINERY AT PARIS.....	18
CHARACTERISTICS OF CALIFORNIA PETROLEUM. BY A. S. COOPER.....	18
THE ROBINS BELT AWARDS.....	21
THE PROPERTIES OF BRASS MADE FROM COPPER CONTAINING SUB-OXIDE. BY ERWIN S. SPERRY.....	21
WATER POWER IN THE SNAKE RIVER DISTRICT. BY JOHN BIRKINBINE.....	22
MINE DEVELOPMENT DEFINED.....	23
DREDGING IN BRITISH COLUMBIA.....	23
THE SAN LUCAS CANYON.....	23
NORTHERN WASHINGTON'S COAL FIELDS.....	23
COAL MEASURES OF ROUTT COUNTY, COLORADO.....	24
QUALITATIVE TESTS FOR BORACIC ACID.....	24
AN EFFECTIVE PIPE WRENCH.....	24
NOVA SCOTIA IRON MINES.....	24
YELLOW ASTER'S PUMPING PLANT.....	25
THE GUIANA GOLD FIELDS.....	25
SWISS STEEL INDUSTRY.....	25
PEAT AS FUEL IN RUSSIA.....	25
THE IRON AND STEEL SUPPLEMENT.....	25

Latest Mining Decisions.....	25
Trade News.....	25
Construction and Development News.....	25
New Mining Applications.....	26
Personal.....	26
Correspondence.....	27
CALIFORNIA—MICHIGAN—MISSOURI.....	27
General News.....	27
ALASKA—ARIZONA—CALIFORNIA—COLORADO—IDAHO—MONTANA—SOUTH DAKOTA—UTAH—WASHINGTON.....	27
Iron and Steel.....	29
Coal and Coke.....	29
The Metal Markets.....	30
New Incorporations.....	30
Mining Stock Quotations.....	31

American and Foreign Coal Exports.

For the first eight months of the year England exported 30.2 million tons of coal, as compared with 28.7 last year; but she received this year \$4.05 a ton on the average as compared with only \$2.60 in 1899. Our own exports of coal are much smaller than England's, amounting to only 5.3 million tons in the first eight months of the year. This figure, however, represents an increase of about fifty per cent over last year, and all of the signs point to continued expansion. Germany also, another great coal-producing country, has increased its exports largely this year.

It is known that both England and Germany import a good deal of coal, and the question is sometimes asked how these countries can both export and import the same commodity at the same time. A part of the answer is that they do not so handle absolutely the same commodity—that is to say, the imported product is often different in kind from that exported; and another answer may be found in the fact that geographical considerations often explain the apparent absurdity. In our own country, for example, though we are the largest and cheapest producers of coal in the world, we nevertheless import considerable quantities. New England manufacturers under certain conditions find it advantageous to buy coal from the producers at Cape Breton, who can mine it as cheaply as the West Virginia operators and can ship it to New England ports by water more cheaply than the Alleghany producers. In fact, if it were not for the duty, the movement of coal from Cape Breton to the States would assume large proportions.

Sustained Strength of Silver.

While other metals have been falling in value (except copper, which has forgotten how to fall), silver has shown conspicuous strength for several months. In recent weeks the tendency to advance has been more marked than ever and prices have reached a higher range than at any time since March, 1897. Some of the causes of this improvement are temporary, while others will be lastingly effective, and American producers will be interested to learn to what extent their present comparative prosperity may be expected to continue.

One two-fold cause of the recent advance may be found in the military operations around China and the partial stoppage of the import trade in that country. The foreign fleets and armies engaged in the investment of China have required considerable quantities of silver and the various European nations involved have bought silver bars for coinage purposes. The suspension of imports as to a large part of China, while exports have continued in almost normal volume, has occasioned a dearth of exchange and has required the purchasing countries to meet their obligations by shipments of silver. The war in the Transvaal has also had a certain influence, as the English Mint is known to have bought silver freely for currency uses in South Africa.

These three causes, however, while sufficiently effective to warrant attention, are temporary in their nature and much less important than the insistent and increasing demand from India. In that country there is a genuine scarcity of rupees for circulating purposes, and both the Indian Council and the Exchange Banks have been persistent buyers of silver in the London market. Their buying is said to have begun on a large scale several months ago, and to have been so skillfully conducted that even the shrewd and experienced silver operators, who are ever on the watch for a chance like this to make speculative purchases, did not for a long time detect the movement.

While it is thought that the Indian demand has been largely supplied by the enormous quantities already purchased, it is also probable that Indian requirements will be permanently greater than they have been in the past. Next year particularly India is likely to absorb a good deal of silver, as the outlook for crops is excellent and she will probably have a favorable balance of trade to be settled in silver. It is not unlikely, indeed, that India will hereafter buy as much silver per annum on the average as she did before the closing of the mints.

Deadlock in the Iron Trade.

The recent reduction in the price of steel rails to \$26 from the fancy figure of \$35 in effect for the last twelve months is deemed insufficient by the leading railroads of the country, and they are said to have formed a combination to fight the Steel-Rail Trust—for that is what it amounts to, whatever it may be called. The presidents of the large roads are willing to pay \$22 a ton and are now holding out for that figure. Such is the situation at present, and the result is a deadlock in the entire iron trade. More than mere rails is involved in the contest, and large contracts for merchant steel, Bessemer billets, plates, and structural material are tied up pending the outcome of the struggle. Not much has been said about it publicly, but behind the scenes a battle royal is raging.

Whatever price the necessities of the railroads and the strength of the rail combination may ultimately make effective, there is no doubt that \$22 a ton would afford the manufacturers a liberal margin of profit. Bessemer pig is openly sold at \$13 and billets at \$17, and even better prices have been obtained by the favored few. Steel rails and billets should not be far apart if mere manufacturing costs are considered, and it is clear from the price of billets that rails at \$22 would give the maker a margin of profit that ought to be satisfactory.

Some of the larger companies are anxious to end the controversy, as they have enormous requirements that cannot be suppressed much longer, and the entire steel and iron trade hope for an early settlement of the difficulty. On every account this is desirable, as the struggle is holding up business in all departments of the industry just at the time when almost every other obstacle to improvement and activity has been settled.

The Anthracite Coal Strike.

As we are going to press (October 13) 857 miners are assembled in convention at Scranton, Penn., invested with the power to end or continue the big anthracite coal miners' strike. Fully 140,000 miners are out on strike, and they are practically unanimous in supporting President Mitchell's demand that the union shall be recognized in the future dealings between the operating companies and their men. Offers of ten per cent increase in wages and of a reduction in the price of powder have gone a long way towards hastening a settlement of the big contest. The concession of the employers is considered liberal in most quarters, but the men seem disposed to stand out for the formal recognition of their union as a condition to an immediate ending of the strike.

Further demands for concessions on the part of the miners are likely to be met by the operators with a declaration that they have reached the limit of their willingness to concede. Meanwhile, Senator Hanna, who is generally thought to be influential with the operators, is expressing confidence that a mutually satisfactory settlement is near at hand.

American Machinery at Paris.

An Exhibit that Won Three Prizes—The Machines that Took the Honors—Three Prize Coal-Cutters and the Work They Can Do.

It is with considerable pleasure that we present in this issue a description of one of the American exhibits at Paris which has brought to this country much of the renown it has acquired through its displays in the big Exposition. It seems that American mining men and American manufacturers of mining machinery have especial grounds for satisfaction over the Paris awards. Where prizes were won by American exhibitors in this class the competition was in most cases very keen, and the points on which the awards were made were very closely contested.




FIG. I.—ELECTRIC CHAIN COAL MINING MACHINE.

No house was more successful in carrying away honors than the Jeffrey Manufacturing Co. of Columbus, O. One gold medal, one silver medal and one bronze medal were won by this company, and it was announced that if the firm had ever before exhibited in France it would have secured a Grand Prix. It is a custom at Paris expositions that first exhibitors are not eligible for the Grand Prix. The Jeffrey company exhibited in competition with all English, German and French manufacturers of coal mining machinery. The design of the machinery, the excellence of manufacture and the method of operating were the points chiefly considered in making the awards, and it is only natural that the successful house should feel most gratified over its honors. This gratification, we are confident, will be shared by hundreds of American mining men who know of the Jeffrey products from their practical experience.

the cost of production depends, in thin veins more than in thick ones, upon the rapidity with which a machine can be moved about so that it may be kept in operation continuously. With this idea in view, this machine has been built low, compact and light, in order to insure maximum cutting.

Another Jeffrey coal-cutter is shown in Figure III—an air chain coal mining machine. It is built in three sizes to under-cut to a depth of five, six or seven feet, either thirty-nine or forty-four inches wide. To make the full cut under the coal and back out again requires from three and one-half to four minutes. It is well adapted for use in both thick and thin veins of coal and embodies most of the features of the electric machines, with the exception of the method of applying power. The engines are especially designed for heavy duty, and the machine has found a wide application in mines where the cutting is very hard. Its

carried out with this point well in mind. Although strong and rigid, it can be easily handled by two men or by a man and a boy.

The giant compressed air drill is shown in Figure V. This machine can make a six-foot hole in less than one minute. When fitted with a frame for a six-foot vein it weighs about 140 pounds.

One more feature of the Jeffrey exhibit was the electric locomotive of the Gondola style shown in Figure VI. This locomotive weighs about 14,000 pounds. It is equipped with two 25-HP. motors, which are thoroughly dust-proof and water-proof. It has a capacity for hauling a gross load of sixty-six tons at eight miles an hour, on the level; on a one per cent grade, thirty-seven tons; on a two per cent grade, twenty-four and one-half tons; on a three per cent grade, seventeen and one-half tons; and on a four per cent grade, thirteen tons. The machine exhibited has a place for the operator on the end of the locomotive and is for this

Characteristics of California Petroleum.

Physical and Chemical Features—How the Products of Various Fields Differ—Petroleum vs. Coal as a Fuel.

By A. S. Cooper, State Mineralogist of California.

Petroleum oils from different oil fields of California differ widely in physical characteristics and chemical composition. They may contain chemically combined one, two, or all three of the following elements—sulphur, oxygen and nitrogen—and in widely varying amounts, while in




FIG. II.—ELECTRIC CHAIN COAL MINING MACHINE.

Through the courtesy of the manufacturers we present herewith the illustrations of the machines that brought the coveted prizes to America. It was the coal-cutters of the Jeffrey company that seemed to possess the greatest attraction for the judges.

Figure I. shows one of these—an electric chain coal mining machine built to meet general conditions and designed especially to withstand the heavy work required in mining where the cutting is very hard and much power required. The machine is designed for under-cutting in coal to three different depths, according to the thickness of the vein—five, six or seven feet, and in width thirty-nine or forty-four inches. The motors are

use is quite general in mines formerly operating what is commonly known as the "pick" or "pincher" machines, and the adoption of the air chain machines in such mines is said to be increasing rapidly.

Sharing the attention of the coal-cutters in the Jeffrey exhibit were two mining drills, one an electric drill and the other a giant air drill. The former is shown in Figure IV. This drill is capable of making a hole six feet deep in coal in less than one minute. The drill completed weighs about 150 pounds when fitted with a frame for a six-foot vein of coal. Machinery of this kind is naturally subjected to extremely rough use and the design and construction of this drill have been

some rare instances these elements may be absent. Oils in the same stratum and a short distance apart may vary greatly. Frequently a well when it first yields will give an oil of a lighter gravity than that which it will yield when it has been pumped for some time. We may, therefore, look upon California petroleum as containing the following substances in an unknown state or states of combination: Carbon, hydrogen, sulphur, oxygen, nitrogen and other substances in minute quantities; these combinations being very great in number and extremely complex.

The boiling points and melting points of the bitumens are altered very considerably by the presence of, or even by the traces of sulphur, oxy-

gen and nitrogen. The presence of a greater or less amount of these substances during distillation has an influence on the distillate. Generally the larger the amount of carbon, sulphur, oxygen or nitrogen an oil contains the greater its specific gravity, boiling and melting points.

CHEMICAL COMPOSITION.

California petroleum is a mixture of a large number of hydro-carbons, and a large number of compounds containing hydro-carbons combined with sulphur, oxygen and nitrogen and other ele-

is tilted and broken, permitting the escape of the gases.

FORMATION OF ASPHALTUM.

When California petroleum is evaporated by atmospheric influences, the sulphur, oxygen and nitrogen compounds remain and are concentrated, and if the process is continued long enough, solid asphaltum is formed. After asphaltum is formed, evaporation proceeds with exceeding slowness. Heat accelerates evaporation. The evaporation from an oil tank built under ground and kept at a temperature of 60° Fahr. is far less than from

ture is low and fairly constant, it should at least be shaded from the sun and whitewashed to decrease absorption of heat.

When a fresh supply of oil is emptied into a tank which contains oil that has been stored for some time, it should be introduced into the bottom of the tank; the fresh oil being lighter than the oil already in the tank has a tendency to ascend, and in doing so it dissolves the heavy oil, and will not evaporate so rapidly as it would if it was placed on the surface of the heavy oil.

Advantage is taken of the fact that asphaltum




FIG. III.—AIR CHAIN COAL MINING MACHINE.

ments. The sulphur compounds usually predominate, followed by oxygen, then nitrogen, and last the other elements in smaller quantities. These sulphur, oxygen and nitrogen compounds were formed at the time that the oil was distilled from carbonaceous rocks by the heat of metamorphism, or are substitution compounds formed subsequent to such distillation by the hydro-carbons coming in contact with these substances under different conditions. Oil when exposed to the air absorbs oxygen; when heated with the peroxides, the peroxides are reduced to a lower state of oxidation. Petroleum, when exposed to sulphur vapors, absorb them; when heated with the persulphides, the persulphides are reduced to a lower state of sulphuration. From this it can be seen that California petroleum is of a highly complex character, containing a large number of hydro-carbons and hydro-carbon derivatives. When the sulphur, oxygen, nitrogen and other elements are removed a number of the remaining hydro-carbons must be unsaturated, and unless these substances be removed from the crude oil before distillation, fractional distillation does not give a true index to the composition of the oil. Ultimate analysis is worthless to show the character of the oil.

All the hydro-carbons and their compounds with other elements in California crude petroleum are volatile. Some, such as benzene, are extremely volatile, whereas asphaltum volatilizes with

a tank built above the ground and exposed to the sun's rays, which may often reach a temperature of 130° Fahr. If a petroleum oil having a specific gravity of 40° Beaume be exposed to the heat of the sun in a shallow pan, it will decrease twenty per cent in volume in a short time; the portion of oil evaporated being better for the manufacture

is nearly an unalterable gum, to make many constructions in which a plastic and unalterable cement is required. Usually, California asphaltum contains from five to nine per cent. of sulphur.

Some wells in California produce oils containing paraffin, but they are so valuable for producing illuminating oil that their use for gas-making is prohibited. At Baku, in Russia, a tract of land less than twenty acres in area has produced in twelve years 35,000,000 barrels of oil, and is still producing about 12,000 barrels a day.

SMALL TERRITORIES AS BIG PRODUCERS.

On the Laguna Extension, or Zaca rancho, in Santa Barbara county, California, there are large deposits of bituminized sand exposed upon the surface. On any one of several twenty-acre tracts at this place the dimensions of the exposures of




FIG. IV.—ELECTRIC DRILL.

great slowness. Natural gas is a volatile part of petroleum. Like coal, the bitumens, oils and asphaltum through decomposition are constantly giving off carburated hydrogen. This decomposition is probably effected by acids, alkalies and other oxidizing agents forming oxygen compounds with the bitumens, and liberating carburated hydrogen.

The composition may also be effected by sulphurizing agents forming sulphur compounds with the bitumens and liberating carburated and sulphurated hydrogen. These oxidizing and sulphurizing agents are formed by metamorphism and other chemical reaction within the earth, which came in contact with the bitumens. Carburated hydrogen may also be generated from oil by heat; this gas is often found issuing from vents in the ground in California, having a temperature higher than the surrounding ground—sometimes as high as 90° Fahr. One of the reasons that California petroleum oils have such a high gravity is the fact that the formation in which they occur

o. gas than the part remaining in the pan. This experiment is easily tried and very convincing.

Notwithstanding this evaporation caused by high atmospheric temperature, the oil producer stores his oil in dark-colored tanks, which are exposed to the blistering heat of the sun, and it is to be regretted his example in many instances is followed by the gas manufacturer. If the oil tank cannot be placed underground where the tempera-

the bituminized sand would show that it contains eight million barrels of heavy petroleum of the consistency of molasses. To make one barrel of that material, it must have taken eight barrels of ordinary petroleum before evaporation, so that on each twenty-acre tract are now the remains of 64,000,000 barrels of petroleum oil. The astonishing part of this is that it is seen upon the surface and is not hidden beneath. Therefore, in California, as well as in Russia, there are probabilities of a very small territory producing immense quantities of petroleum oils. The case cited shows at least one such place, and there may be, and doubtless are, many others of similar character, where the oils are still hidden.

Unaltered rocks of California cover an area of over forty thousand square miles. Bitumens occur in all geological formations from the plutonic, metamorphic or igneous rocks up to and including the quaternary. It is found saturating strata of sand and seamed shale, and as many as ten beds of shale can be seen on the eroded sides of some of the anticlinal ridges of the Coast Range. These sand beds are very irregular as regards their thickness and the distances between them. Some are a few feet in thickness, while others exceed four hundred feet, and the shales are from a few feet to over five hundred feet in thickness.

When several sands are to be seen on the side of a mountain, or when they can be traced upon the surface of the earth by their outcrop, if bituminized at all, the bitumen will generally be in the geologically lower beds, and when a sand contains bitumen, the underlying sand beds are also liable to contain bitumen.




FIG. V.—"GIANT" COMPRESSED AIR DRILL.

At the present time, nearly all the wells that are being bored are in the vicinity of surface indications, to wit: Oil seepages, outcrops of bituminous rock and gas blow-holes, all of which are signs that the reservoirs of petroleum are leaking, owing to insufficient cover. At present, the wells are generally shallow, but they will increase in depth in time as they have done in other oil fields. The day is not far distant when oil territory will be selected by geologists on account of favorable structure and position, irrespective of surface bitumens. The wells in this territory will have to be drilled to greater depths, but when productive will yield light oil. Owing to the large area and the thickness of the unaltered rocks and the great thickness and the number of oil sands in California, the yield of oil in California in future years will be enormous.

PETROLEUM'S ADVANTAGES AS A FUEL.

A comparison of the consumption of fuel oil with that of coal shows 3.33 barrels of fuel oil to be equivalent to one ton of good imported coal. Figuring oil at \$1.40 a barrel and coal at \$7.50 a ton in San Francisco, it shows the cost of oil to be \$4.66 as against \$7.50 for its equivalent in coal. Moreover, the labor required to operate with coal is far greater than with oil, in most instances being nearly double.

The perfect cleanliness of fuel oil and the ease and simplicity of supply and regulation makes it a most desirable substitute for coal. As long as coal remains at \$7.50 a ton in California, it cannot be expected that oil will fall below its present price; not at least for some time to come. In the year 1899 there were 1,740,027 tons of coal imported into the state of California; to supplant this, 5,792,278 barrels of oil will be required. As the supply becomes more permanent, the uses of fuel oil will multiply.

The removal of the gasoline, benzene and illuminating oil, leaves an oil with a high-flashing point, which would be less dangerous to use in a locomotive and otherwise than a fuel oil of low flashing point. The removal of the water also improves the oil for fuel purposes, as it does not have to be evaporated by the fire.

The asphalts in the crude oil are objectionable for the manufacture of gas. When the asphalts are subjected to the temperature necessary to gassify the oil, sulphurous gases are formed

(principally sulphurated hydrogen), and as the asphalts contain a large percentage of sulphur, these gases are formed in quantity and require a large amount of a purifier for their removal.

The presence of asphaltum also fouls the chequer bricks in the superheater and carbureter in making water gas, and the retorts in making oil gas.

At present, the market value of asphaltum is too high for it to be economically used for either the manufacture of gas or for fuel purposes. The large percentage of sulphur in natural asphaltum or in those obtained as a residue in the distillation of crude petroleum, make them an undesirable fuel. During combustion with oxygen the sulphur combines with the oxygen to form sulphur dioxide. Sulphur dioxide in absorbing water or the vapor of water, changes to sulphurous acid. By oxidation the sulphurous acid is changed to sulphuric acid, which may lodge on the surface of the boiler and attack the iron, forming sulphate of iron. Through this action the sulphur contained in the asphalt is a cause of corrosion in boilers. Owing to the presence of sulphur, the fuel value of asphaltum is small when compared with the other hydro-carbons contained in crude oil.

DISTILLATES TO REPLACE CRUDE OIL.

The time is not very distant when crude California oil will not be used for the manufacture of gas. Distillates will be substituted for crude oil for the reasons given in this paper; therefore, it will be of interest to know what action distillation will have upon the crude California oils. In Pennsylvania the upper half of the still is left exposed to the air to facilitate decomposition. During the first distillation of crude California petroleum oil, decomposition of any part of the oil should be avoided; consequently the still should be completely bricked in so that the vapors will be kept fully heated until they escape the condenser.

In the manner of cracking as practiced in Pennsylvania, there must be a great loss of heat from the exposed surface of the still. The laboratory and practice show that the distilling, manipulating and purifying of crude California oil must be totally different from the methods in use in Pennsylvania, Canada, and elsewhere. Most of the crude California oils should be distilled twice. From experiments made, it would appear that the vapors of the lower hydro-carbons during distillation are contaminated by the decomposition of the sulphur compounds contained in the higher hydro-carbons, such decompositions being caused by heat. Usually the higher the boiling point a distillate contained during any one run of a still, the greater the amount of sulphur compounds contained in the same.




FIG. VI.—ELECTRIC LOCOMOTIVE, GONDOLA STYLE.

DISTILLATION OF SULPHUROUS OILS.

In distilling oils containing sulphur, the main body of the sulphur compounds remain in the higher hydro-carbons. Owing to this action, by repeated distillation, the sulphur compounds are generally eliminated to a great extent, but hardly ever completely from the oil.

A distillate having a certain specific gravity when distilled under atmospheric pressure from crude petroleum may contain sulphur in notable quantity; whereas a distillate of the same specific gravity when distilled from the same crude petroleum in vacua may be comparatively free from sulphur. This is probably owing to the fact that a greater temperature is required to vaporize the oil when under atmospheric pressure than in vacua, this additional heat decomposing the sulphur compounds.

At ordinary temperatures, petroleum oil does not absorb sulphureted hydrogen when collected on the surface of the oil. If hydrogen at a high temperature or in a nascent condition is introduced into the vapors of the light hydro-carbons during distillation, the sulphur vapors which are formed by the decomposition of the sulphur compounds contained in the lighter hydro-carbons, combine with the hydrogen and can be carried from the still. But if the hydrogen is omitted, the sulphur from the decomposition of the sulphur compounds combines with the hydro-carbons to form complex sulphur compounds, which are removed with difficulty. It is supposed that when in a crude state and not distilled, the lower hydro-carbons in the California petroleum do not contain sulphur compounds to any marked extent, but are sulphurized during distillation by the decomposition of the sulphur compounds contained in the higher compounds.

The asphalts obtained by the distillation of California petroleum contain from four to seven per cent of sulphur. Vapors of sulphur have a greater affinity for heated hydrogen forming sulphureted hydrogen than for heated hydro-carbon vapors to form sulphur compounds. When hydrogen is in a nascent condition, it will replace sulphur in the liquid compounds of sulphur and hydro-carbons by inverse substitution. The activity of this action is increased by heat. At 60° Fahr. the action is very feeble, but at 200° Fahr. the action is rapid, and at higher heats the action is still more rapid.

CLASSIFICATION OF COMPOUNDS.

As has been stated, California crude petroleum is composed of a number of hydro-carbons and

having the following commercial names and physical characteristics:

The following are the percentages of the distillates contained by the first distillation from many crude California oils:

Naphtha	traces	15 per cent
Illuminating	6.00	27 per cent
Gas Distillate	16.00	30 per cent
Lubricating	20.00	52 per cent
Asphalt and loss	7.00	25 per cent

In the first distillation the following are the temperatures at which the following distillates are distilled:

Crude Naphtha	to 150°C.
Illuminating Distillate	150° to 300°C.
Gas Distillate	300° to 350°C.
Lubricating	350°

Owing to the highly complex composition and great diversity of California oils, the above figures are to be considered only as suggestive.

Crude California Oil 20 B. Distillates	Gravity		Weight of 1 gallon in lbs.	Percentage obtained approx. mate.
	Approximate Beume.	Specific Gravity.		
Gasoline	75	0.6820	5.69	3
Benzine	63	0.7253	6.04	4
Illuminating ..	45	0.8000	6.66	13
Mineral Sperrm.	38	0.8333	6.94	8
Gas Distillate ..	28	0.8860	7.38	11
Light Lubricating	26	0.8974	7.48	8
Neutral	23	0.9150	7.62	10
Heavy Lubricating	21	0.9271	7.72	5
Valve Lubricating	15	0.9655	8.04	4
Asphalt	11
Loss	13
Total	100

The Robins Belt Awards.

We present herewith an illustration of the Robins Conveying Belt Co.'s exhibit at the Vincennes machinery annex of the Paris Exposition. The exhibit shown secured for the company a Grand Prix, the only one awarded to any exhibitor of conveying machinery at Paris. The display shown consisted of a twenty-inch Robins belt conveyor ninety feet in length and running level under a series of bins. The conveyor, after clearing the bins takes a curved incline, raising the material

tributing the material into the bins and reversing automatically at each end of the bins without the assistance of an operator. This system has a capacity of 200 tons an hour, and during the exposition it was constantly in operation handling broken stone.

Other exhibits of equal merit were made by the Robins company at Paris. One of these was in the machinery and electricity building and consisted of two twenty-inch conveyors thirty-five feet in length. The other exhibit was in the mining building, where there was shown a one-quarter size model of the Vincennes exhibit, including the automatic trippers. Both of the latter named displays were also in constant operation. Besides its machinery, the company displayed a large collection of photographs of its belt conveyors, showing installations in every country in the world where mining is carried on. The crowds examined the photographs with great interest, but it was the conveyors themselves that attracted most attention, especially those on which the automatically reversing trippers were in operation. This was the first exhibition of this invention in Europe. The regularity and smoothness of its working and its economical operation won for it the favorable decision of the judges as well as the admiration of the spectators. The Robins Conveying Belt Co. still has on hand at its New York offices in the Park Row Building a small number of catalogues attractively gotten up in French and English, which were prepared for distribution at the exhibits.

The Properties of Brass Made from Copper Containing Sub-Oxide.

By Erwin S. Sperry, Bridgeport, Conn.

The oxidation of metals melted in contact with air takes place with dissimilar results. Tin, lead or zinc are examples of a class, the oxides of which float on the surface of the melted metal. First a film is produced, which covers the surface; then, if agitation from any cause exposes new metal to the action of the air, additional oxidation takes place, and the film is increased in volume. This change goes on until a considerable quantity of oxide (or "dross," as it is technically called) is formed; depending, of course, upon the duration of the exposure of the metal to the atmosphere. When such metals are poured, the dross may be skimmed off; and clean metal will



THE ROBINS CONVEYING BELT CO.'S DISPLAY AT VINCENNES.


hydro-carbon compounds mutually dissolved one within the other, and having different boiling points. Owing to this they can be fractionally distilled so as to separate them into fractions

to a height of seven feet, whence it is delivered to a horizontal twenty-inch conveyor which in turn carries it in the reverse direction. A patent tripper operates on the upper line of conveyor, dis-

be left underneath. The removal of such oxides is, therefore, merely a mechanical process. In the case of copper, however, the result is quite different. The sub-oxide of copper (Cu_2O) is readily

soluble in molten copper; and therefore, instead of the formation of a film of oxide, to be finally removed as dross, the surface of the metal remains bright and clear, because the oxide has been dissolved as soon as it was produced.

It is customary in the process of copper-refining to leave a small quantity of oxide in the metal, in order to oxidize any traces of bismuth, arsenic or antimony which have not been entirely removed. As a result, these metals exist in the commercial product as oxides, and not as metals, which would form an alloy with the copper and so injure its quality. In making copper bars for the manufacture of wire of high electrical conductivity, and cakes to be rolled into sheet, this practice is, without doubt, beneficial; but it does not improve the copper for the manufacture of brass or other alloys. Zinc is a strong reducing agent; and the study of its thermo-chemical reactions has shown that it will reduce not only the oxide of copper according to the reaction



but the oxides of bismuth, arsenic and antimony as well. In the manufacture of brass, therefore, all the other metallic oxides are reduced to metal, with the formation of oxide of zinc.

It is well known that, by reason of the absorption of oxygen, copper rapidly deteriorates when melted in a crucible. Each successive melting, therefore, injures its quality. Small amounts of oxygen do not seem to affect appreciably the "hot-working" qualities of copper, but tend to make the metal cold-short. In the manufacture of sheet-copper the tendency to crack during the process of rolling is overcome by reason of the fact that the metal is "broken-down" hot; the cold-working which is afterward put upon it does not then have the tendency to crack it. Pure copper is much softer than that which contains oxygen.

In order to determine the influence of sub-oxide of copper on brass, it was necessary to make copper containing varying quantities of sub-oxide, and then to use these products instead of the pure material. It was decided to introduce into the copper the maximum amount of sub-oxide, and to use this product, first without any admixture of pure material, and then with the addition of varying amounts of pure copper, thereby decreasing the percentage of contained oxygen. The ideal method, however, seemed to be to melt pure copper in a crucible, and then add some oxidizing agent like saltpeter. Such a method was also tried.

It is believed that the experiments thus made demonstrate that oxygen in copper, unless present in abnormally large amounts, does not exert a deleterious influence on the quality of brass intended for rolling into sheet. If oxygen is present in excessive amounts (quantities seldom occurring in practice unless the melter is lax in his methods), salamanders are apt to form. If it is present in less amount, salamanders may not form, but the brass manifests a tendency to crack in rolling. This is due, no doubt, to the zinc oxide present, which prevents perfect cohesion. From still smaller quantities of oxygen, practically no injury is noticed. The proportion may even be as high as 0.55 per cent and no adverse results happen; but more than ordinary care must be exercised to keep the metal thoroughly covered with charcoal.

The amount of oxygen in commercial copper is more or less variable, depending upon the capacities of the refiner; but in the best brands great care is taken to keep within as narrow limits as possible. The pitch, of course, determines this point.

According to advices received in personal communications from chemists representing two leading brands of copper on the market (one Lake and the other Electrolytic), the amount of oxygen which exists in these brands of copper may be taken as follows:

	Lake. Per cent.	Electrolytic. Per cent.
Oxygen Contained in Ingot Copper.....	0.012	0.010

On a careful perusal of the results of the various experiments referred to, it may be readily seen that no injurious influence can possibly be exerted by such a small proportion of oxygen as 0.01 per cent. Good sheet-brass was made from copper containing over fifty times this quantity. Although the initial amount of oxygen in copper may be quite minute, and not sufficient to exert any influence on brass, yet if the caster is not cautious, and neglects the frequent additions of charcoal, this small percentage may be increased

many times by the oxidizing influence of the atmosphere.

In conclusion it may be said that, unless the amount of oxygen in commercial copper exceeds the figure given above, it cannot, *per se*, be called an injurious impurity.*

Water Power in the Snake River District.

A Suggested Hydraulic Pumping Plant for Power, Irrigation and the Treatment of Gold Sands.

By John Birkinbine, Philadelphia, Pa.

The following data, collected during a visit to the Snake river district, in Idaho, are offered as indicating the possible utilization of a waterfall for irrigation by pumping, the working of gold placers, the generation of electricity for light and power, and possibly for manufacturing purposes. For irrigation and placer washing, a portion of the water is applied to wheels and pumps to elevate another portion. These notes do not describe any new methods in hydraulics, in electrical development, in irrigation or in hydraulicking auriferous sands, but rather suggest the possibility of various applications of the water power available, either contemporaneously or in different seasons.

As the minimum flow in the Snake river is in the winter, when the snows on the mountains are not melting, while the normal or possible flood-flow is during the season when irrigation is necessary, the application of water for other purposes may possibly alternate with irrigation. The Snake river heads on the continental divide, close to the Yellowstone Park in the state of Wyoming, and flows southwestward through eastern Idaho, then westward, and then northward, forming a portion of the boundary between Idaho, Oregon and Washington, and finally uniting with the Columbia river in the latter state. The three prominent falls on the stream, after it has obtained considerable volume, are the Idaho, the American and the Shoshone falls, the latter being the most noted. The data here given concern the conditions at the American falls, the point where the Oregon Short Line railroad crosses the Snake river, twenty-six miles west of Pocatello, Idaho.

The Snake river has here a width of 750 feet, and a break in a lava-flow forms a series of cascades (the American falls) having a drop at low water of 39.8 feet. As the volume of the flow increases, the difference between the water levels below and above the falls is somewhat reduced; but from the information obtainable the fall water will not rise more than 1.5 feet for each foot of increased height in the level of the head-water; and the additional volume of water will more than compensate for the reduced head. It is therefore safe to base estimates of power upon the flow and the fall at low water stage.

The drainage basin of the Snake river, above the American falls, approximates 22,000 square miles—equal to one-half the area of the state of Pennsylvania. Mr. F. H. Newell, hydrographer of the United States Geological Survey, records stream measurements made at two points upon the Snake river, one above and one below the American falls.

At the Idaho falls (seventy miles above the American falls), with a drainage area of 10,000 square miles, the minimum discharge of the Snake river was found to be 2,000 cubic feet per second in 1890, and 2,250 cubic feet per second in 1892, approximating 0.2 cubic feet per second per square mile of drainage area. The elevation of the Idaho falls is 4,710 feet, and that of the American falls is 4,341 feet, above sea level. At Montgomery ferry, twenty-five miles below the American falls, with a drainage area of 22,600 square miles, the minimum flow was reported as 4,420 cubic feet. At each of these stations the flood-flow exceeds 50,000 cubic feet per second. Owing to the superposition of lava benches one upon another, some of the water, following the planes of juncture, appears in numerous large springs, at intervals along the shores of the river, thus affecting estimates of the flow based upon the drainage area. The investigations made, however, indicate that a minimum flow of over 4,100 cubic feet per second can be depended upon; and that with good water wheels, properly installed, about 13,000

horse-power can be developed at the American falls with the average low water discharge.

The locality permits the erection of a power plant, at small expense, on either side of the river below the railroad bridge. It is possible, with water rights granted on both shores of the river, that more satisfactory results may be obtained by dividing the plant, especially for irrigation purposes; that is, by installing part on the east side of the river and part on the west side; or it may be preferable to connect the eastern shore with a rocky island which divides the river, or to convey electrical energy across the stream by wire.

The fall, being an ordinary one, will require no special form of water wheels, or pumps, or of electric generators. Hence any development will be relieved from unusual expenditures for equipment, and it will be possible to follow an initial installation capable of meeting immediate requirements by others, as augmented power is demanded, without proportionately increased cost.

A properly designed plant will raise one cubic foot of water to the plateau for every five cubic feet applied to the wheels at the American falls; and if a lower lift be found desirable, for placer washings, etc., the proportion of water consumed in this way will be smaller.

IRRIGATION.

The great stretch of sage brush plain in south-eastern Idaho, composed largely of decomposed lava, produces, under irrigation, crops of wheat, alfalfa, potatoes, turnips, etc.; and the harder fruits yield satisfactorily. Large expenditures upon canals and ditches in northern Utah and in Idaho, and the crops obtained from watered lands, testify to the local appreciation of irrigation. The existing installations for irrigation, with few exceptions, withdraw water from the rivers by long feeder canals, which supply the main and lateral irrigation ditches.

The territory on the west side of the Snake at the American falls rises quite abruptly to a mesa, or plateau, about 100 feet above the water level. The eastern side, although ascending more gradually, is cut by draws or ravines, and possesses a more uneven topography. The average descent of the Snake river is about six feet per mile, and as a feeder ditch requires a fall approximating one foot per mile, a main canal twenty miles long would be required to bring water to this plateau, 100 feet above river level.

To avoid this expense an experimental pumping plant was erected, consisting of two twenty-three-inch horizontal turbine wheels, belted to two thirty-two-inch centrifugal pumps, having a guaranteed combined capacity of delivering 750 cubic feet of water per minute to the main ditch 104 feet above the river. The wheels, however, utilize but three-fourths of the available fall. The guaranteed capacity of the wheels and pumps as installed (450 cubic feet per minute) will irrigate 1,000 acres.

AURIFEROUS SANDS.

The existence of free gold in large quantity, but generally finely comminuted (much of it being float-gold), is well known, and the Snake river is actively exploited by dredges and ground-sluicing. The most desirable deposits of auriferous sands are either above the river level, and therefore unworkable, except by hand labor or by water artificially elevated, or are in bars in the bed of the stream, from which the sand and the water for washing it must be raised by mechanical power.

Close to the American falls the territory adjoining the shores is worked at a number of places, the material being handled by scrapers drawn by horses, and treated in crude ground sluices with satisfactory results. Samples of the concentrates were obtained, and also samples, taken over the area excavated, were panned out, showing numerous "colors."

The present operations are confined to bars, or to localities where the stripping is slight, because the material must be handled by animal labor or by steam dredges, which latter must pay from \$4 to \$6 per ton of coal, delivered at the dredges. It is reported that sixty dredges are at work on the Snake river.

Electric power developed at the American falls may possibly be conveyed to operate dredges at other points on the river, at rates which, while profitable to the generating company, will permit a reduction in the cost of operating the dredges.

With water delivered to the top of the banks, and used through pipes and nozzles, this territory yields more gold at smaller cost per ounce.

*Extract from paper read at Canadian meeting of American Institute of Mining Engineers. The complete paper describes minutely fourteen experiments on which the conclusions stated are based.—Editor.

Three sluice-heads of water, supplied by the 750 cubic feet per minute furnished by the present plant, should each wash at least 500 cubic yards per day when in operation; i. e., they will move 1,500 cubic yards per twenty-four hours, and twenty-six cubic feet of water will therefore be required per cubic foot of material washed. But even if a more liberal supply of water must be pumped, this will permit the moving of the material to sluices at a cost below that required for dredging, and much below that which prevails at the active ground-sluicing operations.

The project is to use the irrigation ditches for conveying water to the gold diggings; but it may be found advantageous to attack some of the auriferous sands with water which need not be elevated as high as for the ditches; and greater service can thus be secured from a given river volume, applied as power to pump the water for washing. If, however, gold washing is carried on as an adjunct to an irrigation system as planned, there is opportunity for special saving in each department.

A late report of hydraulicking from the end of one of the irrigation ditches indicates the recovery of gold (.938 to .951 fine) to the value of from fifty to seventy-five cents per cubic yard of material moved.

All of the gold in the Snake river district is finely comminuted, and the magnetic iron sand associated with it is also quite finely divided. It may be found practicable to withdraw the iron sands by magnetic separators, leaving a smaller volume to be subjected to amalgamation.

IRON-SAND.

In the abstraction of gold a large amount of this finely comminuted iron sand is collected as a by-product; and if this can be obtained free from other sand by supplementing the sluice work with magnetic separators it may be possible to form the material into briquettes and smelt it in blast furnaces, or it may be converted into iron sponge by a direct process. Up to the present time the difficulty of obtaining a uniform product has interfered with the utilization of direct processes, but future advances in electro-metallurgy may make these sands convertible; at present this is not assured. The distribution of the iron sands is such that the cost of winning them alone will be too great to encourage their utilization; but when obtained as a by-product from gold washing it may be possible to convert them into merchantable material.

THE LIGHTING AND HEATING OF POCATELLO.

By railroad American falls is twenty-six miles from Pocatello, but a pole line can reduce this to about twenty-two miles by utilizing a pass. Pocatello, with a population of 5,500, is located in the Fort Hall Indian reservation, and consequently has little near-by farm land to contribute to its prosperity; but much improvement is expected from the passage by Congress of a bill which provides for the purchase of 100,000 acres of the reservation, tributary to Pocatello, and the opening of it for settlement. This means cultivating the farm lands and exploiting the mineral deposits.

It is contemplated to utilize a portion of the power available at the American falls to generate electricity, which will be conveyed to Pocatello, and to provide for such industries as may find the use of cheap power desirable at or near the falls. The fact that the railroad crosses the Snake river immediately at the falls gives encouragement to expect such possible utilization of a part of the power.

The general scheme is an evidence of the revival of interest in water power development which characterizes the present time—a revival made possible chiefly by improvements in the design of water-wheels and in the application of electrical energy to many purposes.

The features of this undertaking, now in the initial stage of development, have been described in order to invite attention to the possibilities of other localities which may possess similar advantages.*

Mine Development Defined.

The Supreme Court at San Francisco recently decided that the development of a mine does not necessarily consist in surface work, or work done upon the claim itself. Houston Mann located the Ontario mine in San Bernardino county, Cal., and owned the continuous and overlapping claim called the Jeanette. He was engaged in driving

tunnels on the Jeanette for the purpose of tapping the ledges of both claims, when Al Budlong and George Deck entered upon the Ontario mine location, and suit was brought by Mann to oust them. In the lower court a decree was entered in favor of the defendants, the findings upholding the contention of the defendants that the mine had been abandoned by the plaintiff.

The Supreme Court has reversed the decree, holding that "the necessary amount of work thus having been done upon the Ontario with the manifestly honest intent of striking the lode, and developing the mine upon a definite plan, even if that plan should result in failure, it cannot be judiciously said that the work contemplated by the law was not done."

Dredging in British Columbia.

E. C. Kingswell of Kamloops, B. C., is the author of an interesting letter addressed to the editor of the Mining Journal of London on the possibilities of dredging in British Columbia. Mr. Kingswell was born in New Zealand and lived there thirty-five years. He has had fourteen years' experience in all kinds of mining, and his opinion that British Columbia rivers will compare favorably with those of New Zealand for dredging, is therefore entitled to careful consideration. He presents these reasons for his belief:

First, the climate, in my estimation, is more favorable than New Zealand, and, as it does not rain half as much as it does upon the Clutha, and the rivers only rise up for about six weeks, and then quickly fall as soon as the snow melts; this will enable the dredges to work in the centre of streams nearly all summer.

Secondly, vast areas of British Columbia have been worked to water level by the old pioneers, and very large quantities of gold have been taken out, especially in the famous Cariboo district, and most of the small streams flowing into the large rivers contain and carry gold and act as granular feeders to the main rivers.

Thirdly, the wash here, especially in the now famous North Thompson, is especially friable, and has a proved soft blue marine bottom, and the wash has no alluvial clay to carry away the fine gold, and for ninety miles up—as far as I have been—I saw no boulders that could possibly interfere with any ordinary New Zealand dredge. In that distance I only found one canyon that could not be worked (about one mile), and this canyon opened out into a grand basin that will be a famous dredging area, in my estimation.

Fourthly, the gold seems to be evenly distributed through the wash. I could only get down to eighteen feet deep, and in that distance I found it average fifteen cents per yard. All visible gold was easily saved. I did not require to use quicksilver at all. The black sand, which averages about one per cent of the full, assayed very high, up to \$30 per ton. I consider, though, that a very large proportion of this gold would be saved upon a dredge with 200 feet of tables; I used a small rocker. All the bars upon the river carry payable gold. I have had as much as \$8. per yard washed out of bars. Numbers of Indians and white men wash all the fall and part of winter, and do very well.

Fifthly, the timber upon the bank of this river is a very light pine, and never lodges in the wash, gets carried down the stream to lake and sea. I never came across a buried log in my six months' experience of rivers here. The timber here is very light. A team can be driven anywhere upon the banks; no difficulty will be experienced in removing trees, as there are no tap roots, and it burns very easily. Fuel can be easily and cheaply got from sides of mountains and banks of streams. In my opinion, ample power can be got from several small rivers that flow into Thompson, and can be utilized as an electric motive power. Hundreds of feet of fall can be got at very little cost, and the hills contain hundreds of lakes that could be tapped.

Sixthly, the river here has a very slight fall, and is a particularly slow stream, averaging about two and one-half miles an hour; no difficulty in anchoring a dredge, and the river has splendid alluvial banks that I have proved auriferous. The average height, I should say, is about ten feet. The river does not change its course, and has not done so for a generation.

Seventhly, the law here allows you to take up five miles of any river bed (as against one mile in New Zealand) for £12 10s. per mile rent and a royalty of 2s. per ounce of gold. Bench claims can be taken up to make a dredging area of six to 800 acres. I have taken up in one stretch ten miles of river bed and bench claims that will keep

twenty dredges working a lifetime. A claim is very easily secured in British Columbia. No advertising or court fees to be paid. The Gold Commissioner recommends the Minister to grant a claim and it is done, and you secure right in a month, whereas in New Zealand advertising, lawyer's fees, etc., cost a small fortune.

Eightly, there is magnificent timber all over British Columbia to build the pontoons, and roads and railways are in close proximity to dredging areas. In fact, I unhesitatingly say that British Columbia is in every way an ideal country for dredging, and holds out a certainty for the British investor, provided, of course, that the claim is properly reported upon and tested. I might mention that an English company has a New Zealand dredge at Lytton, sixty miles from here, upon the Fraser River. A New Zealander has taken charge of her, and the part owner, Mr. Cobbedick, now says publicly that he is more than satisfied with his first month's returns. Another dredge is just about to be built upon the North Thompson, and, having thoroughly tested the ground, I will guarantee that she will return to her Liverpool owners a fortune, provided, of course, that they carry out the New Zealand principle of dredging. I might say, as regards creek and dry land dredging, that I have seen ideal ground to start dredging. I have seen hundreds of acres turned over for surface gold, and no bottom was reached; several of these ideal places were on edges of big lakes, etc. In my limited travels I have been pointed out plenty of ground that could not be dredged, and I am aware of failures upon the Fraser; but no wonder. I say all these dredges were of the spoon and dipper pattern, and could not lift as much in a day as our dredges can lift in an hour. In my estimation the Fraser will not be a good dredging field. The area is limited, and the bottom is very rough. No doubt there are some very rich basins and bars in it, but it cannot compare with the North Thompson and others in British Columbia.

In conclusion, let me strongly advise the British investor to look into this field and copy the success of the New Zealanders, and I will guarantee British Columbian rivers will return the money a hundred fold. Of course, I have fish to fry, and, therefore, am sure to crack it up, but if I have made any misstatements I shall be pleased to be hauled down.

The San Lucas Canyon.

George Shaw of Santa Ana, Cal., says: The San Lucas canyon presents an appearance of the mining days of '49. The whole canyon is taken up by claims and a number of good mines are being worked. Camps and miners' lodges are scattered about over the claims, but none makes as good a showing as the Three Nations, which is being worked by a gang of fifteen men. George Shaw, in company with five other young men from this city, has been working on this claim for its Santa Ana stockholder. They have sunk one shaft down to the bedrock and tunneled for a number of feet under the mountain. The boys have made good wages during their stay in spite of the lack of water, which is the only drawback to the place. Paying dirt is plentiful, but water without paying for it is very scarce and must be hauled a long distance.

As soon as circumstances will allow the boys will return to their work, and this time to work in earnest. They have negotiated for some mining machinery and expect to startle the camp on their return. There is a quartz claim being worked in the canyon by W. E. Johnson of Ferris, which is expected to surprise the miners of this district. This claim is the best of its kind being worked in the canyon, although it is but partly developed, and as yet its real value is unknown. Many old miners have failed to give credit to the stories of the Mission Indians in regard to gold in large quantities to be found in our mountains, but from the way the San Lucas canyon is developing their stories may yet be proven true.

Northern Washington's Coal Fields.

Israel C. Russell of the United States Geological Survey has completed an examination of the sections of the state of Washington north of the Northern Pacific Railroad, where the road crosses the Cascade mountains. The section extends to the international boundary line, a distance of about 100 miles. Mr. Russell says of the coal in that vicinity:

"The most valuable of the mineral deposits here claiming attention are the coal seams in the Ros-

*Transactions Am. Inst. M. E.

lyn sandstone. At the town of Roslyn a shaft of 628 feet in depth has been sunk, and from its bottom an extensive series of galleries excavated in the main coal seam, which is five feet four inches thick. The coal is bituminous and highly valuable for generating purposes. At the Cle Elum mine, in the eastern outskirts of the village of Cle Elum, a shaft 250 feet deep, begun in 1894, reached a seam of coal 4.5 to 5.5 feet thick. In July, 1897, a drift had been carried eastward from the bottom of this shaft for sixty feet, another westward about 600 feet, and another northward about 300 feet. The dip of the strata exposed in these workings is south at an angle of fourteen degrees. The output of the mine at the date just stated was 125 tons per day. This coal seam is not the same as that worked at Roslyn, but occurs at a higher level in the geological series. At a locality in the hills about two miles north of Cle Elum, the Ellensburg Coal Mining Co. has worked another coal seam in a small way by means of a drift starting at the outcrop of the coal and running eastward about 600 feet. The coal is there four feet thick.

"The total output of these mines, derived mainly from the workings at Roslyn, was 231,534 tons, with a value of \$485,520 in 1895, and 481,710 tons, with a value of \$1,027,209 in 1896.

"Tests made by means of a diamond drill conducted by the company operating the Roslyn mines, show that coal of workable thickness and good quality underlies an area measuring a square mile or more in the valley of Yakima, to the southeast of Cle Elum. This area extends to the Yakima river, but whether it occurs to the south of the river, as might reasonably be expected, has not been ascertained. Coal outcrops in the valley of the main trunk of Teanaway river, to the north of Roslyn and Cle Elum, but no mines have been operated in that region. Examinations for coal have been made on First creek, near the north end of Green canyon, at the head of Williams creek, on the west side of Table mountain and on Naneum creek, a southward flowing stream which has excavated a canyon-like valley in the more elevated portions of the Table mountain plateau. Coal seams have been found at each of these localities, but not in commercial quantities. Whether these examinations have been sufficient to demonstrate the absence of valuable coal seams is not known to the public. Several openings have been made in search of coal near Camas Land, along the Peshastin, below the mouth of Camas creek, and in the valley of the Wenatchee, but thus far without success. It does not seem, however, that any of these tests were sufficiently extended to demonstrate the absence of workable seams."

Coal Measures of Routt County, Colorado.

Prof. F. V. Hayden has written for the Evening Post of Denver the following interesting letter about Routt county's anthracite deposits:

"This county (Routt) is probably better supplied with coal than any other portion of the state, extending across the whole county a distance of nearly sixty miles, and more than that in width. At some points, however, basalt or volcanic rock shows up, in which vicinity the coal has been turned out, as the volcanic action shows strong evidence of being a later period than the coal deposits. These volcanic fires have, where the heat has not been too great, probably coked the coal deposits, and ages of time, together with great pressure has compacted this coked matter into genuine anthracite. So far as is at present known there is but one place in the county where anthracite is found, namely in the Elk Head range, about twenty miles from Steamboat Springs, in a nearly north-west course. Here the earth has been upheaved and two veins exposed, probably nearly 100 feet apart. These veins average about five and six feet each in thickness. The coal in these veins is very hard and averages well with Eastern coal in quality. In fact, it is claimed by parties who have tested both Pennsylvania coal and specimens from this field that the Routt county product gives less ash and slightly more carbon. In doing the necessary development work to secure this coal land the coal was wheeled out on the dump and has lain there exposed to the elements without covering. Last fall J. W. Hughes & Co. purchased several tons for use in a base burner stove in their fifty by eighty-foot store at Steamboat Springs. The result was that they kept the room comfortable with it even after an exposure of nine years to weather that would almost have disintegrated a granite boulder. That this is the

only section of the country where anthracite is to be found is a mistake, as every condition for the formation of the same character of fuel is found in a dozen different portions of the county far removed from each other, these beds only being exposed by some internal upheaval, cracking along the line of the same, one side dropping to place and the other remaining tilted. Taking other portions of the field into consideration and as a guide, there is evidently a still lower and thicker vein underlying the two exposed, the two upper ones agreeing closely with these in thickness, while the one lying probably 100 to 150 feet deeper ranges in thickness from fourteen to twenty feet. The farther we go west the more erosion has taken place, first one vein then another, until finally all have been rubbed or worn away. As to the general quality of the coal in this section, it is a very safe statement to make that we have no poor coal. On first opening a bank before a depth is reached the product burns freely, but slacks easily. As greater depth is reached this tendency to slack disappears; a very little sulphur is found in any of it, and the tendency to slack is only conspicuous by its almost entire absence.

"Probably one-half of the field has been appropriated by individuals, the greater portion by homestead, pre-emption, timber culture and desert claims, the Colorado Fuel & Iron Co. having done about all the filing as legitimate coal claims. The general character of the coal here is lignite, although of far better quality than is found on the eastern slope, semi-coking and considerable of it semi-coked. This is a peculiar statement, but can only be qualified by saying that as

An Effective Pipe Wrench.

Machinists often have trouble with pipe wrenches which they seem to be unable to operate without crushing or badly bruising the pipe. We present herewith a cut of the Atlas pipe wrench which is designed with a view to avoiding this trouble. The cut shows an eighteen-inch wrench holding a two-inch pipe, and makes it easy for one to see why the wrench does not bruise the pipe. The teeth of the wrench hold the pipe at an angle, with the gripping point in advance of the handle, so that in screwing the pipe one uses it ahead, but does not dig into the pipe and drag it as with some wrenches. It is said to be impossible for the Atlas wrench to lock on the pipe.

The Atlas wrench is fully as effective when extended as when used on smaller sizes of pipe. The movable jaw can be placed in any one of three slots clearly shown in the cut. In this instance it is in the third slot. By shifting it to the second or middle slot, the wrench can be used on smaller sizes of pipe, and when in the first it is ready for use on the smallest size. In the eighteen-inch wrench, for instance, the first slot is for pipe measuring from one-quarter to one inch, the second for pipe from one and one-quarter to one and one-half inches, and the third for two-inch pipe. The movable jaw shown in the illustration is not a screw jaw and has no weak parts. The wrench has no nuts and no delicate parts which can get out of order or break. It is constructed of special drop-forged steel and every wrench is thoroughly tested before it leaves the shop of the makers. The twenty-four-inch wrench takes a pipe one-half inch larger than



THE ATLAS PIPE WRENCH.

a majority of it is neither anthracite, cannel or bituminous, it must certainly be as stated or a new name coined to fit the occasion. Lying within this coal measure we find an extensive oil field. This basin is within one mile of the eastern edge of the field and is being fast located by men interested in such matters. Since January, five separate corporations have had representatives in the field. The first two secured by lease and location 10,000 acres. What the three remaining outfits will be satisfied with can only be imagined. Already we are becoming familiar with derrick, pipe line and refinery talk, but so far there has been no great distribution of wealth. When this much-hoped for time will come we can only exclaim, in the language of our lately defeated enemies: Qui en sabe?"

Qualitative Tests for Boracic Acid.

In the Journal of the American Chemical Society there appears a valuable suggestion as to the conducting of qualitative tests for boracic acid, by E. M. and M. L. Wade, the Los Angeles assayers. The writers say:

It seems not to have occurred to authorities on the subject to test the effect of the alcoholic vapors of boracic acid on turmeric paper. We find that, if the test is applied in the following manner, the presence of boracic acid in minerals is rendered more certain and delicate:

Use a test-tube about 2.5 cm. in diameter and twenty cm. long. Put into the tube about 0.1 gram of the substance, 0.5 cc. hydrochloric acid, and ten cc. wood alcohol. Boil vigorously down to small bulk, agitating the lower end of the tube in flame of burner, and holding the moistened end of a piece of turmeric paper just outside the mouth, so as to catch the vapors. Boracic acid will finally color the turmeric a characteristic red. Now, if the turmeric is placed vertically on the side of a beaker so as to dip into a little distilled water to which a few drops of ammonia have been added, a pinkish to deep purple or blue will be produced, in marked contrast to the red produced by the ammonia on the end of the paper unaffected by the vapors.

the smaller ones, while another inch in the size of the pipe is allowed by the use of the thirty-six-inch wrench. A set of four wrenches would thus handle all pipes ranging from an eighth of an inch to four and one-half inches. The Atlas wrench is made by the Atlas Pipe Wrench Co., Flood Bldg., San Francisco, and an eastern office is maintained by the company at 121 Liberty St., New York City.

Nova Scotia Iron Mines.

George B. Cowlam has sent an interesting letter to the editor of the American Manufacturer concerning the recent discovery of iron ores in Antigonish county, Nova Scotia. The writer claims that this will be the next great center of interest and activity in the world's great iron trade. He says: "Here in a ridge nine miles long and in the main 1,000 feet high, parallel with and a couple of miles distant from the straits of Northumberland, are vertical veins of solid, compact hematite averaging something over fifty per cent metallic iron, with a total width of ninety-eight feet. It is estimated that in the nine miles there are 450,000,000 tons of ore above sea level, nine-tenths of it above drainage level, with possibility of increase from incoming new veins and certainty of increase by going below sea level. These veins are all disclosed in a narrow gorge which cuts the mountain to its base and have been faced up at various levels from summit to bottom of gorge. They have been traced and in many cases cut along the top and ends of the range showing their continuance throughout with no change except that the veins broaden somewhat in the southwest end of the range, which is the higher and broader part of the mountain. These ores can be mined at a cost not above quarrying, very cheaply transported to numerous harbors by the building of about thirty miles of railroad, and can be laid down in English ports, 2,000 miles distant, at a cost of \$1.25 to \$1.50 per ton, to our Atlantic ports at even lower figures, barring a duty of forty cents. With these ores in British hands the export trade in both ores and iron and steel from America can be not only controlled but absorbed, as the quantity of ore is sufficient to fur-

nish 5,000,000 tons of pig iron a year for forty years or more and may be largely increased.

"The property is being rapidly uncovered, and will doubtless be on the market late this fall or early next spring, when our iron makers will have a chance to compete with those of Great Britain for control.

"Coking coal lies just east of the iron range, and ten miles away abundant limestone, so that conditions are much like those around Birmingham, Ala., plus a bounty of three dollars a ton."

Yellow Aster's Pumping Plant.

The Randsburg Miner reports that the pumping plant of the Yellow Aster Company is nearly completed and will soon be in operation. The Miner says:

After the pump is started and they can handle the water, work will be resumed and the well sunk deeper. This water system with everything connected with it, including well, pipe line, reservoirs, engines and pump, will represent an outlay of not far from \$75,000, and is very thorough and complete, everything being of the best. The next move of the company will be either to sell the mines and all connected with them, or increase the capacity of the mill by adding forty more stamps, and this will be determined shortly.

Applications to purchase are received daily, and men have made long and costly journeys, with little or no encouragement, to interview the owners, and if the management decides to sell a fancy price can be obtained without trouble. The fact that the water problem, a difficult one in this desert country, is solved and water is developed and a magnificent system of works established to deliver it on the ground at the mines will enable the Yellow Aster people to get much more than this plant has cost in negotiating a sale. No time will be wasted, however, on this score. If a sale is not soon made, or an excellent prospect of one, the company will immediately proceed to put up forty additional stamps, as they feel sure they have plenty of water to run 100 as well as seventy.

Last month 3,894 tons of ore were mined and mined with an average force of sixty-two men in the mines. This was an average of four and one-third tons to the stamp, and at an actual cost of mining and milling of \$2.36 per ton. Considering the cost of everything here on the desert and that the water was pumped from deep wells six miles away from the mill this is getting it down to pretty close figures.

The Guiana Gold Fields.

United States Consul George H. Moulton, whose station is at Demerara in British Guiana, is at home on a leave of absence. He talks interestingly concerning the conditions of gold mining in British Guiana and Venezuela, and it seems to be his opinion that these fields do not furnish an especially attractive outlook for American miners. He says:

"The rush to the gold fields of British Guiana and Venezuela, which was expected to follow the settlement of the Venezuelan boundary dispute, failed to materialize. The new boundary fixed by the arbitration court is quietly accepted by the people of British Guiana and Venezuela, and no further dispute is likely to arise. Gold mining is still being prosecuted in the British Guiana gold fields, and there are a few Americans who are there trying to make their fortunes.

"The yield of these gold fields is about \$2,000,000 a year. All the gold obtained is secured by placer mining. No shafts have yet been sunk for lode mining. Mining in British Guiana is attended by the greatest difficulties and hardships, and there is also some danger to life and limb. The gold fields are all at some distance in the interior. To reach them the miners have to travel through swamp lands and dense brush, which are infested by alligators, enormous reptiles, and wild beasts. Everything the miners carry along has to be packed by men. The Essequibo and Demerara rivers are great rivers, but they are not navigable for more than seventy-five miles, owing to many obstructions and frequent rapids. The miners who go into the interior by following these rivers court great danger.

"I know of one American miner who has a claim which it takes him twenty-three days to reach from the seashore, but so swift are the streams by which he travels that he can come down to the seashore in a week. British Guiana is no place for American miners. They can do better in Colorado or Montana."

SWISS STEEL INDUSTRY: Switzerland has not until now been noted as a center for steel production, though her engineers have long held a high position in the mechanical world. Recently, however, a company has been formed to work the great deposits in the Bernese Oberland, where there are many million tons of ore available, averaging fifty per cent of iron. It is intended to smelt the metal electrically, the large water power, cheaply obtainable, giving the project a reasonable prospect of success.

PEAT AS FUEL IN RUSSIA: Consul Hughes writes from Coburg—"The question of the scarcity of fuel in Russia has long occupied the attention of scientists. Coal is found only in small quantities, while wood is by no means sufficiently abundant to warrant extensive consumption. It is proposed to surmount the difficulty by turning the enormous quantities of peat to account. In many districts, the turf almost represents the staple fuel. Its calorific power is said to be double that of wood. The turf is compressed into small briquettes and sent to the market. It is estimated that the cost of manufacturing it for commercial purposes is about \$5.84 a ton, which at present compares very favorably with the price of coal.

The Iron and Steel Supplement.

The second edition of the supplement to the Iron & Steel Directory of the American Iron & Steel Association has just been issued by James M. Swank, general manager of the Association, from his office, No. 261 S. 4th St., Philadelphia. The present supplement is issued as a more complete list of the iron and steel consolidations than the descriptive list which appeared in March. It comprises the organizations included in the March list, besides many others. The list has been confined to consolidations embracing the ownership of blast furnaces, rolling mills, steel works, in plate works and auxiliary industries such as bridge and shipbuilding. It contains only companies that have been consolidated since January 1, 1898, when the last directory to the iron and steel works of the United States was issued.

The book is a handy little volume of seventy-eight pages with board covers, and will be of great value to all persons in any respect interested in the immense enterprises described. Complete lists are given of the branch concerns of the big companies.

Mr. Swank says in his preface that every consolidation described is in good faith what it pretends to be, and contributes his opinion in the "trust problem" by describing the typical consolidation in the iron and steel industries as follows:

"It represents a large investment of capital for the purpose of uniting in one ownership and under one management independent and often widely separated plants. This policy of concentration of capital and energy, which is in accordance with the industrial spirit and necessities of the age and is world-wide, is amply justified by the increased facilities it affords for securing economy in production and efficiency in management. That these consolidations have not been organized to repress competition or to arbitrarily maintain prices is abundantly proven by the active competition which prevails between many of them and by the rapid decline that has recently taken place in all iron and steel prices."

For detailed information concerning the plants mentioned and their products reference is given in the supplement to the pages in the directory in which the plants are fully described. Copies of the book may be secured by applications to Mr. Swank at the price of \$2 a copy.

Latest Mining Decisions.

(Specially prepared for THE MINING AND METALLURGICAL JOURNAL.)

Plaintiff located a mining claim, and thereafter defendant entered on the land, claiming it as vacant mineral land, in that plaintiff had failed to do the amount of work required by the law for five years previous. Plaintiffs owned a claim that overlapped the claim in dispute, and on the land common to both claims had done work in the way of tunneling largely in excess of that required by law, with the manifest intention of striking the lode of the claim in dispute. Held, that a finding that the work performed could not be a benefit to the claim in dispute, and that plaintiffs were not entitled to same, was erroneous, since the court could not be permitted to

substitute its judgment as to the expediency of the method employed for developing a mine for that of the owners. *Mann vs. Budlong et al.*, 62 Pac. Rep. (Cal.) 120.

TRADE NEWS.

The Jeffrey Mfg. Co. of Columbus, O., requests us to announce that their chain catalogue is now ready for distribution. Like all of the trade literature issued by this company, this catalogue is most attractively prepared and is of much interest to mining engineers and superintendents.

The Sullivan Machinery Co. has moved its Chicago offices from 54-60 N. Clinton St. to Rooms 1220-1221 Merchants' Loan & Trust Building, 135 Adams St. The store and shipping department will remain in Clinton St. The officers of the company extend a cordial invitation to their friends to call upon them at their new headquarters.

The contract for the erection of new buildings in Jamaica Plain, Mass., for the use of the Buff & Buff Mfg. Co., manufacturers of engineering instruments, has been awarded to John P. Campbell, a Boston contractor. The plans call for two-story brick structures to be built according to the latest type of mill construction. An isolated stone building will be included to accommodate the concise graduating engines owned by the company.

D. Van Nostrand & Co., sellers of scientific books at 23 Murray St., New York City, describe in their July and August bulletin an extensive handbook on diamond drilling intended for use in prospecting and exploiting gold-bearing and other mineral properties. The author is G. A. Denny, who has had considerable experience in South Africa. The drills described are those of the Sullivan Machinery Co. and the M. C. Bullock Mfg. Co., both of Chicago. Particulars as to the cost of this apparatus and the manner of their working are given in detail. The price of the book is \$5.

We are in receipt of an attractive catalogue from the George E. Dow Pumping Engine Co. of San Francisco. The catalogue describes in detail the steam, electric and power pumps and hydraulic machinery made by this well-known house. It is a book of 113 pages. Especial attention is given to the Dow compound sinking pump which has been extensively introduced in mining operations where large quantities of water more or less burdened with foreign materials have to be handled. The Dow mine station pumping plant adapted to the deepest mines is also illustrated and described. Copies of the catalogue are sent to all applicants interested in mining operations.

Construction and Development News.

Luke Latimer will develop gold deposits near Washington, Ga.

A pyritic smelter of 100 tons capacity is to be put up at Ouray, Colo.

The Centennial-Eureka mine of Salt Lake City, Utah, is to be provided with a smelter.

The App mine at Sonora, Tuolumne county, Cal., is to add forty more stamps to its mill.

The Golden West Co. of Tuolumne county, Cal., may erect a new mill upon its property.

The Mt. Jefferson mine at Groveland, Tuolumne county, Cal., is erecting a twenty-stamp mill.

The Shawmut mine at Sonora, Tuolumne county, Cal., is erecting a chlorination plant.

The Merced Gold Mining Co. of Mariposa, Cal., intends to enlarge its plant in the near future.

Two five-foot concentrators are being put in at the Keystone mine in Amador county, Cal.

The Texas Coal & Fuel Co. of Weatherford, Tex., wants machinery for developing coal mines.

The Mariposa Grant Co. of Mariposa, Cal., may purchase a new ten-stamp mill for the Mariposa mine.

The Quinnimont Coal & Iron Co. of Quinnimont, W. Va., is in the market for coal mining equipments.

When the work of straightening the shaft of the Humbolt mine of Helena, Mont., is completed, a steam hoist may be installed.

The management of the Juno mine of Nelson, B. C., has resolved to make the mine a producer. A plant to treat the ore is to be installed.

The Carnegie Steel Co. of Pittsburgh, Pa., will build a rod mill in connection with the new group of finishing mills to be built at Duquesne.

Ten more stamps are to be added to the mill of the Mt. Jefferson mine near Sonora, Tuolumne county, Cal.

A large smelting plant is being built in the township of Denison, Ont., Canada, by the Ludwig Mond interests.

It is reported that the Oregon Reduction Works at Baker City, Ore., will build a smelter plant and a branch smelter in Burkement.

Ed. Kay of Jackson, Cal., is in charge of the construction of a ten-stamp mill fourteen miles from Nevada City, Nevada county, Cal.

The Humboldt mine of Georgetown, Colo., is being cleaned out, and a whim will be put up at once, when development work will be pushed.

The Mineral Products Co., which has its headquarters at Moncton, N. B., is considering the construction of smelting works to handle manganese ores.

The new Pittsburg & Baltimore Coal Co., which is preparing to operate mines on 3,000 acres of land south of Irwin, Pa., will be ready to start in a short time.

The Ballarat Mining Co. at Ballarat, Inyo county, Cal., will probably increase its stamp mill to forty stamps soon. F. H. Verencamp is the superintendent.

McGiverty & Brown, who own the Driscoll mine in Washington Gulch, Mont., are now getting out ore and developing the mine with the purpose of putting up a mill.

The Congress Gold Co., W. F. Staunton, superintendent, of Congress, Ariz., is contemplating the erection of a new forty-stamp mill and the enlargement of their cyanide plant.

The Nickel-Copper Co. of Hamilton, Ont., is pushing developments in the ore fields. This company has a fifty-ton smelting plant in course of erection at Worthington station.

Justus Collins of Collinsville, W. Va., has recently bought 1,200 acres of New River coal lands. Mr. Collins purposes developing the property as the projected railroad is built to it.

Maj. H. M. Russell of Los Angeles, Cal., is manager of the Mammoth mine near Isabella, Kern county, Cal., and intends adding twenty more stamps to his ten-stamp mill.

The St. Louis Co. of Virginia City, Nev., has recently added to its property. The work of developing and extracting the low-grade ores will begin before the close of the season.

The Gold King Mining Co. has closed down its El Paso mine in Poverty Gulch, Cripple Creek, Colo., to install a new plant that will be a duplicate of the one recently placed in the Strong mine.

The McClintic-Marshall Construction Co., Park building, Pittsburg, Pa., has bought a site of fourteen acres in Rankin, near the plant of the American Steel & Wire Co., and will put up new works.

The Eagle Bird mine at Maybert, Nevada county, Cal., is to be extensively opened in the near future. It is the property of the Eagle Bird Mining Co. and W. M. Wilson is superintendent.

The Gold Bug property, owned by the Gold Bug Mining Co., at Georgetown, El Dorado county, Cal., is to have an electric power plant. W. E. Thorne, M. E., is the manager and superintendent.

The Scott-Valentine syndicate of England is making a deal for the Britannia mine, Vancouver, B. C. If the deal is completed the mine will be developed on an extensive scale and smelters will be erected.

A steel hoop mill will be erected in connection with the steel works and tin-plate mill now building at South Sharon, Pa. F. V. Buhl, John Stevenson, Jr., of Sharon, and the Clark Bros. of Pittsburg, are interested.

Louis Will, a capitalist of Syracuse, N. Y., has purchased the Yellow Jacket group of mines, near Rossland, B. C. He intends to improve it by adding a new mill, a tramway two and one-half miles long, and an electric plant.

Barry N. Hilliard of Wallace, Ida., one of the owners of the Murray mine, wants to put in a plant and hoist and begin extensive work, but there are other owners whose money is tied up in other claims, and it may take considerable time to come to an agreement.

Machinery is being constantly added to the Dos Cabezas mines at Dos Cabezas, eighteen miles south of Wilcox, Ariz., owned by the Dos Cabezas Consolidated Mines Co., composed of Los Angeles parties, and it is now reported that a sixty-five-ton smelter is to be erected soon.

John R. Tregloan, the owner of the Excelsior

mine at Amador City, Amador county, Cal., intends to equip and develop the property in the near future. This is a new mine and adjoins the Bunker Hill on the east.

All improvements are being moved to the mouth of the Watt tunnel on the Brown Bear property, at Deadwood, Trinity county, Cal. The Brown Bear Mining Co. is the owner, with Chas. D. Dobler as manager and superintendent.

The Pennsylvania Steel Works at Harrisburg Pa., recently bought ground adjoining their present property, and upon this they intend to build. A new machine shop will be 300 feet long, and will be equipped with large quantities of machinery.

The addition of 120 stamps is to be made to the mill of the Royal Consolidated Mines Co. at Hodson, Calaveras county, Cal., forty stamps of which are now being installed. J. C. Kemp van El is the superintendent and W. F. Larrigan the secretary.

C. C. Bush, Jr., and H. C. Woodrow, who have a bond and lease on the Texas group of mines at Hart, Shasta county, Cal., are extending a tunnel 1,500 feet and sinking a new shaft. They will add twenty more stamps and a cyanide plant to the present twenty-stamp mill.

Additional furnaces and a new plant for the utilization of low-grade ores are to be erected on the property of the Mountain Copper Co. at Keswick, Shasta county, Cal. Lewis T. Wright is the general manager and H. W. Edwards assistant general manager for the company.

The Caballero Onyx Mining Co. of New Mexico has been organized by El Paso business men with a capital of \$350,000 for the purpose of developing and working the company's onyx mines. The company will put in its own manufacturing plant, and hopes to supply Europe as well as this country. The officers are Lew Gilbert, president; H. E. Runkle, vice-president; C. W. Alexander, secretary. The main office is in El Paso, Tex.

It is reported in Mariposa, Cal., that the ore from the Mariposa mine, on the old Mariposa grant, controlled by the Mariposa Commercial & Mining Co., averages about \$20 a ton, and this has so encouraged the management that they intend erecting a ten-stamp mill upon the property. The ore is now milled at the Princeton mill, another of the company's properties.

At the Shawinigan Falls, on the St. Maurice river, Quebec, industrial developments are proceeding on a large scale. The power company which is completing works for utilizing the falls, to produce hydraulic and electric energy, has already expended a large sum. A. C. Rice of Worcester, Mass., is the company's engineer. He will place all contracts for the development of power, erection of buildings and the furnishing of machinery.

The Congress Gold Co. at Congress, Ariz., with W. F. Staunton as manager and superintendent, contemplates the erection of a new forty-stamp mill and cyanide plant. The depth of the main shaft is now 2,600 feet, while the length of the main tunnel is 1,200 feet. There are forty stamps now in operation and twenty concentrators. The daily capacity of the cyanide plant is 130 tons of ore. There are 350 men employed in and about the property.

New Mining Applications.

Herman J. Rossi, Wallace, Ida.: De Long lode, Lalande district, Shoshone county, Ida.

John P. O'Neill, Burke, Ida.: Mono Traction lode, Lalande district, Shoshone county, Ida.

Marshall M. Taylor, Wallace, Ida.: Cape Nome lode, Hunter district, Shoshone county, Ida.

James Johnson and J. H. Clive, Galena, Nev.: Washington lode claim, Lander county, Nev.

George Hofheims, Bland, N. M.: Monte Cristo group of lode claims, Bernalillo county, N. M.

Louise E. Cramer, Breckenridge, Colo.: Louise placer, Pollock district, Summit county, Colo.

Jacob E. Corbett and Ira A. Flood, Denver, Colo.: Lake placer, Miners district, Summit county, Colo.

Martin Hammer and P. A. Sorensen, Salt Lake City, Utah: Northern Light lode claim, Summit county, Utah.

Hecla Mining Co., by Henry R. Allen, attorney, Wallace, Ida.: Mascot lode, Lalande district, Shoshone county, Ida.

Illinois Mining Co., by its attorney, D. J. Williams, Provo, Utah: Syndicate lode claim, Salt Lake county, Utah.

John T. Hodson, Salt Lake City, Utah: Bunker Hill lode claim, West Mountain district, Salt Lake county, Utah.

Clarence Cunningham, Wallace, Ida.: Mary R., Traction, and Evening Star lodes, Hunter district, Shoshone county, Ida.

Empire State-Idaho Mining & Developing Co., by E. Saxon Ward, Wardner, Ida.: Arizona vein, Yreka district, Shoshone county, Ida.

San Miguel Consolidated Gold Mining Co., Telluride, Colo.: Synvita and Pactola lodes: San Miguel district, San Miguel county, Colo.

Chas. H. Lashbrook, Bingham, Utah: Centennial, Gondola, Paragon, Rub, Rhue No. 2, and Rhue No. 3 lodes, Salt Lake county, Utah.

Joseph Lerwill and Fred Richards, Bingham, Salt Lake county, Utah: Yukon lode claim, West Mountain district, Salt Lake county, Utah.

J. M. Moad, L. E. Wade, P. B. Coffelt and G. L. Moad, Red River, Taos county, N. Mex.: Esther mine, Red River district, Taos county, New Mex.

J. H. Clive, Galena, Nev., by attorney, James Johnston, of same place: Ethel C. lode mining claim, Battle Mountain district, Lander county, Nev.

James K. Shaw, Salt Lake City, Utah, and Raphael S. Giuliani, Bingham, Utah: Diamond Extension, No. 2, Salt Lake and Tooele counties, Utah.

Butler Mining & Milling Co., by its agent, W. A. Wight, of Salt Lake City: B. F. Butler, No. 2 lode claim, West Mountain district, Salt Lake county, Utah.

Hercules Consolidated Mining Co., by Thomas H. Kane, attorney, Silverton, Colo.: Excelsior lode, and State Street lode, Animas district, San Juan county, Colo.

Trade Dollar Consolidated Mining Co., through its attorney, James Hutchinson, Dewey, Owyhee county, Ida.: Gordon lode claim, Carson district, Owyhee county, Ida.

J. A. Blossom, Battle Mountain, Nev.: Copper King and Copper Queen mines, Widow, Blue Bird and Sweet Marie claims, Battle Mountain district, Lander county, Nev.

Trade Dollar Consolidated Mining Co., through its attorney, James Hutchinson, Dewey, Owyhee county, Ida.: Sunflower lode claim, Carson district, Owyhee county, Ida.

Trade Dollar Consolidated Mining Co., through its attorney, James Hutchinson, Dewey, Owyhee county, Ida.: McNair lode claim, in Carson City district, Owyhee county, Ida.

Black Crook Mining & Milling Co., by its attorney, William Binford, Boise City, Ida.: Black Crook, Imp and Demon Consolidated lodes, West View district, Boise City, Ida.

Charles F. Painter, for himself and as attorney for the San Miguel Consolidated Gold Mining Co., Telluride, San Miguel county, Colo.: Golden Butterfly lode, San Miguel district, San Miguel county, Colo.

PERSONAL.

J. B. Parks is at present superintendent of the Pacific Dredge Co., which is operating on the American River in California.

August Ziesing has been appointed general western representative of the American Bridge Co. with headquarters at Chicago, Ill.

William Magenan has resigned his position as assayer for the Dexter Gold Mining Co. at Tuscarora, Nev., and A. V. Corry has been appointed in his place.

T. D. Pease of the Liberty Mining & Smelting Co. of Tucson, Ariz., has been in New York looking after affairs connected with his mine. The superintendent of the mine is W. R. Wemple.

W. F. Aldrich, president of the Aldrich Mining Co. at Aldrich, Ala., was offered a nomination for Congress in his district for a third term. He has declined the honor, however, in order to give his entire time to his mining interests.

K. Shimamura, a graduate of a Tokio school, and a mining engineer associated with the Mytsu Bishi Co. of Japan, has been making a tour through the mining sections of Colorado, Montana and Utah.

Walter Hovey Hill, general manager of the Idaho Little Giant Mining Co., Ltd., at Warren, Idaho, is in New York City in the interests of his company. He reports a gratifying state of affairs at the mines and believes that the property has a promising future ahead.

CORRESPONDENCE

CALIFORNIA.

(From Our Special Correspondent.)

Santa Ana, Cal., September 27, 1900.

The hot weather period on the desert is passing away and the miners are returning to their claims. In some places up in the mountains the prospectors worked through the year. From New York peak at Manvel word is received that Joe Lyere ran a tunnel in on water seepings, and by thus working now has about a one-inch flow of elegant spring water. This brings the Good Hope mine and group into the market. The whole group of fourteen claims is being negotiated for by the United Mines Mining Co. This deal is nearly completed, and if closed the Good Hope vein will be developed, and after a crushing and concentrating plant are erected, the product will go to the smelters. The outcrop of this vein carries from \$5 to \$9 gold per ton, with some lead, concentrating about fifteen tons into one ton of concentrates.

There are several deals nearly consummated for the development of the Manvel gold fields. Considerable lead is being shown up. Black tellurides of lead in quartz have been found which show over \$160 gold per ton. This came from the Old Shoes mine, where a contract has been made for the sinking of 100 feet more in the present shaft. Drifting on the vein below is about finished and many claims have been located in this camp and many have had the annual assessment done, showing fine bodies of gold, lead, silver and copper ores. Depth on these veins is all that is required for a good production of smelting ores. It will soon be known who finally secured by purchase the Old Shoes mine and group of claims. The last transactions of the deal are now being closed.

A new company has had an expert mineralogist and metallurgist at work investigating the Santa Ana range of mountains for several months past. This range of mountains is the dividing line between Riverside and Orange counties. The mineral zone circles around Santiago Peak and Saddle Back mountain, the west half of this circle being in Orange county. It is fairly well established and covered with locations. The core of this range is of erupted igneous, rocks, basaltic and chloritic, with granite metamorphosed fields therein. The peak is about 4,000 feet high and the long chain summit just tops 3,000 feet.

The camps on the western slope in Orange county are, Silverado, Alma, Shakespeare and Yeagers property. A great deal of prospecting has been done in past years, and the search has been and is now to determine whether the field is gold-bearing to any extent and to learn the nature of the ores carrying the gold. The lower field of ore-bearing veins has an elevation of 2,400 to 2,700 feet, and the belt of mineralized rock runs southeast to northwest in breaks, with the veins cutting across the belt diagonally. This belt, as stated above, lies in a circle of great dimensions, its west side or rim being on Santiago creek, about three miles above Madame Mojaska's ranch home, at which point is the Alma group of claims—Alma, Boston, Galena, La Esparanza, Eagle, Prospect, Geneva, Mojaska and King Solomon. A 400-foot tunnel on the Alma cuts the vein at a depth of 350 feet. The ore is galena and the production record shows 123½ tons of ore shipped; gross value, \$10,713, net receipts, \$8,160. This shows that the 123½ tons netted about \$66 a ton, and the reduction charge then (San Francisco) was about \$20.70 a ton, including freights. No gold was reported in that shipment, the values being given for the lead and silver contents of the ore. Recent assays of samples of this ore body gave (1) silver, seventy-four ounces; lead, 53.5 per cent; (2) silver, 32.1-3 ounces; lead, 41.55 per cent, and copper, 4.5 per cent, so that ore from the Alma, according to the second assay will net now about \$76 per ton. A fair ore body is in sight, with a mill on the ground and plenty of water to run it.

Evidently the best mine of the group is the King Solomon, which has exposed a great rib of oxidized iron and lead ore ready for grinding into paints. It is of various colors and worth about as much for paint as for the gold it contains. The owner, Mr. Morrow, looks for a top notch price in consequence. There is considerable work done upon the property.

One mile and a half to the southeast is the Shakespeare group of eight more claims, with about 1,000 feet of work done. The assays of these ore show values as below:

	Gold.	Silver.	Lead.	Copper.
1.	\$7.75	\$2.87	Trace	46.7%
2.	2.06	1.36	13.
3.	546.22	71%
4.	12.92	14.74	1.	18.7
5.	1.03	1.08	3.
6.	2.06	3.47	7.6
7.	20.67	12.71	40.9
8.	39.18	56.2
9.	2.58	4.20	6.2
10.	4.13	8.37	19.86	25.3
11.	500.96	72.42
12.	56.05	59.1	1.
13.	57.13	41.55	4.3

The copper, lead, gold and silver showings are good. It is said that the United Mines Mining Co. has bought this ground; at any rate, it is known that they have been and are now negotiating for it with the intention of running a lower tunnel to cut the two parallel veins. A 200-pound lump of ore from the Shakespeare workings gave values of \$1,100 gold per ton. The past development of this group has been surface tunnels, on and into the veins, but they have developed a good water supply. The slope of the mountain is to the south, into the Trabuca canyon. The formation of this mineral belt is chloritic igneous rocks, together with volcanic metamorphosed granites.

Nearly due east from here, six miles up the Trabuca canyon, are the Yeager claims, nine in all, with 3,000 feet of workings, a concentration mill, and buildings, and about 45,000 bricks ready for a smelting plant. There is plenty of fine timber on these claims, and an abundance of water. A 1,200-foot crosscut tunnel discloses, it is claimed, a mineral body over 300 feet thick, and the foot wall not yet encountered. Nickel has recently been discovered in it. This whole group and plant is soon to be turned over to an expert, to determine the values of the exposed ore bodies and tonnage in sight. It is a big undertaking, and if, as claimed, this ore body shows sufficient values to make it pay, it means considerable mining in the locality. The field appears to be the backbone of the Santa Ana range, and the strike of the veins is toward Santiago peak. A yellow iron pyrite is predominant in the vein, and the values are in gold.

To the southward on the west slope of this range considerable prospecting is being done to discover the lodes that give the large, coarse gold nuggets found in the placers of Lucas canyon above the Hot Sulphur Springs.

It is rumored in this section that the Santa Fe Railroad will encourage the erection of a smelter at Olive Station (on their system) in the Santa Ana canyon, where there is available oil for power purposes, and also fluxing material, and with the great abundance of ores on the range, there is nothing lacking but the capital to build the reduction works. S. A.

MICHIGAN.

(From Our Special Correspondent.)

Houghton, Mich., October 6, 1900.

The new shaft in the Quincy No. 7 is about ready to begin operations. The shaft goes down 4,200 feet and is sunk on a catenary curve which starts from the surface at an angle of fifty-eight degrees with the horizon and at the bottom flattens to an angle of thirty-eight degrees. As the shaft opened a stretch of ground already reached on a number of levels running south from the No. 6 shaft, it could be sunk in several sections simultaneously. The men previously working in shaft No. 6 will be transferred to No. 7 for the present, and the skip track in No. 6 will be re-laid to accommodate skips carrying six-ton loads in place of the four and one-half ton loads now hoisted. No. 6 will then go into commission once more and another force of 200 men will be added. It is likely that the Quincy will have 3,000 names on its payroll within a few years.

Four new pumps will be installed in the Michigan mine at once to dispose of the heavy flow of water from the old Minnesota mine. The Michigan is now nearly deep enough to touch the bottom workings of the old Minnesota, and will drain the old mine by driving pipes through the trap rock between the two mines. After the Minnesota is unwatered, a cross-cut will be driven to connect it with the Michigan, and the contact vein will be thoroughly explored. The operators expect to be well rewarded for their work in the old mine, for the miners who were working it nearly twenty-five years ago believe that they left much copper behind.

The Calumet & Hecla's monster pumping engine "Michigan," said to be the largest pump in the world, is to have a companion, the "Arcadia," of 22,000,000 gallons capacity. This is being put in place for a new six-stamp mill which will treat 1,800 tons of conglomerate a day or 2,700 tons of amygdaloid. A product of twenty-seven tons a day would make the amygdaloid of the Calumet & Hecla a larger producer than the Quincy.

MISSOURI.

(From Our Special Correspondent.)

Joplin, Mo., October 8, 1900.

On Wednesday night the price of zinc ore was advanced in a few lots a dollar, and in most of the big lots a half-dollar over the price of the previous week. When the bidding began on Wednesday the price was \$27.50 and bids ranged upward to \$28.50. The upward trend of prices was led by the representatives of the Edgar Zinc Co. which on Monday bought up ten carloads at Oronogo, nine at Webb City and much more at Joplin. Other smelting companies need large quantities of ore for their winter stock, and the demand is likely to keep prices well up for some time in the future. King Jack brought the highest price—\$28.50.

The advance in price tended to cut down the sales, and district shipments aggregated 463 tons of zinc and thirty-nine tons of lead less than in the previous week, the decrease in value being \$12,299. The total district sales for the week were zinc, 9,615,770; lead, 986,780; value zinc, \$115,982; lead, \$22,530; total, \$138,512.

GENERAL NEWS

ALASKA.

Consul McCook of Dawson City says that more claims have been worked this summer than in any previous season. On account of the extra rainfall there was sufficient water for sluicing. Many owners will work their claims only during the summer, letting them lie idle in winter, as they can dump the dirt or clay directly into the sluice boxes in summer, and not have to handle the ground twice. Machinery is found everywhere in the district; no one thinks now of working claims without boller, engine and pump. The amount of gold sent out to August 22, as per consular invoices, was \$12,500,000; it is possible that about \$250,000 has gone out without any record.

Seattle men are opening up a good silver-lead property on Admiralty Island which was discovered in July. The vein is more than 100 feet wide, the surface ore assaying over \$15 in silver and lead and the value increasing with depth. It is proposed to connect the mine with the shore by a narrow gauge tramway.

Transportation facilities in the direction of Dawson are fully occupied with the rush of provisions and machinery. This will be the busiest winter in the history of the Klondike, and efforts are being made to store up supplies at Dawson for the entire season.

Up to September 30, the Government Assay Office at Seattle recorded receipts of \$15,000,000, of which \$2,000,000 was from Nome, and most of the rest from the Klondike and Atlin. About \$1,000,000 more will be added to this total before the season closes. Many miners are stoutly defending Nome against the serious reports which have been spreading abroad concerning the famous beach. They say that if it had not been for lack of water and for mining litigation, the production of the beach would have reached enormous figures. With the new camps now opening up, they predict an output of from \$6,000,000 to \$10,000,000 for next season from Nome.

ARIZONA.

The Minnesota, Connor and Merrimac mines at Chloride have been bought by the Philadelphia & Arizona Mining & Milling Co. for \$300,000.

It is reported that the McGuire mine, four miles south of Kingman, has been sold. After a well has been sunk, the owners will erect a 100-ton plant.

W. S. Connor reports the discovery of new placer ground on Lynx Creek. The new ground is at the mouth of Accidental Gulch and Mr. Connor believes that it is an old channel of the creek.

Eighteen feet of water have accumulated in the

shaft of the Isle Royale at Helvetia. The water was struck in a cross-cut at the 300-foot level. If it proves that the body of water is permanent it will mean much for the future of Helvetia Camp. A cave similar to that found on the Copper Queen mine at Bisbee has been broken into, disclosing native copper and an abundance of water.

CALIFORNIA.

H. E. Finley and J. W. Calloway have a seven-foot ledge in the St. Patrick mine, near Ballarat, Inyo county. The ore is said to run about \$20 a ton, with richer streaks.

The Riverside mine and mill, on the Gavilan grant in Riverside county, are running full time. The July clean-up was \$2,680, netting \$1,600, while that for August was slightly more.

The forty stamps of the Keystone Consolidated Co.'s mill at Amador City, Amador county, are now running steadily. Two five-foot concentrators are being put in for each battery. Affairs at the mine are in excellent condition.

The Ballarat company has let two contracts for work in their mine in Inyo county. T. H. Verencamp is the superintendent. The mill will probably be increased to forty stamps in the near future.

One hundred men have been put to work on the smelter site at Bully Hill, Shasta county. Superintendent Brown has reported that a railroad will be built at the Bully Hill by Captain J. R. De Lamar. The contract for rails and ties has been let. Surveyors are running grade lines over the hills and the work of construction will soon begin.

The latest story from the Coolgardie placer field, north of Barstow, according to the San Bernardino Transcript, has been received over the wire from Kramer. W. O. Lyon, a telegraph operator in the employ of the Santa Fe-Pacific Railroad at that point, has just returned from a six weeks' trip with a dry washer, during which time he saved \$900 in coarse gold. He considers this very good remuneration for a two months' leave of absence, and it is probable that he will return to the fields and continue the work of dry washing instead of "jerking lightning."

Dover, Reyber & Dover, at Stone Corral, near Ballarat, Inyo county, have a four-stamp mill running on good ore from the Gold Note mine.

The Golden West Co., operating on the Comstock ranch, Tuolumne county, has encountered a fine body of ore aside from the present shoot now being developed. The new discovery is a ledge four feet wide, showing well the width of the vein. The old shoot is about 100 feet long, and is high grade. If the outlook continues promising a mill will be erected in the near future with steam for power, there being plenty of water for milling purposes. The work is under the supervision of F. R. Restano.

A. M. Dean has sold to Otto Dittach a one-half interest in the Great Humboldt mine in the Pine-cate district of Riverside county.

At the App mine, at Sonora, Tuolumne county, the ore bodies are opened up from the 1,000-foot level to the surface, and the outlook for this property is very flattering. It is the intention to put in an additional forty stamp at the mill, as the ore reserves fully warrant such an outlay. The timbers for the addition to the mill are now being secured.

R. E. Gilland has purchased from Frank Brown a one-eighth interest in the Major mine, south of Perris, Riverside county.

The mill at the Jumper mine, in Tuolumne county, has closed down on account of the scarcity of water. Fifty men have been laid off as a result. Timbering and development work will continue.

The inclined shaft at the Alpine mine, near Placerville, El Dorado county, is down 125 feet. A crosscut recently encountered a well-defined ledge of good pay ore.

The Buckboard mine has had sixty tons of ore milled at the Red Dog, which produced a gold brick worth \$1,000, showing the ore taken out in the development work to run about \$16.50 a ton.

A lot of eleven tons of ore from the Little Man mine, at Ballarat, Inyo county, owned by "Shorty" Morris, averaged \$50 to the ton.

Assays from quartz lately taken out of the Dewey mine, in the Gazelle district, Shasta county, ran up to \$500 a ton, with considerable ore in sight.

E. K. Stevenot of San Francisco has lately made a report on the Orloilo mine, near San Andreas, Calaveras county, for the Board of Directors.

It is believed that the extension of the famous Sheep Ranch vein has been found in the Ritter mine, four miles from that great property in Calaveras county.

The Riverside mill, at Carters, Tuolumne county, is running steadily. The reopening of the old mine has resulted in some rich rock being uncovered.

The old mill is to be again started on the Kimble mine, near Oroville, El Dorado county. Development work is being steadily prosecuted.

Development is to be resumed at once on the Gopher-Boulder property, in the Kelsey district, El Dorado county.

Fair progress is being made in the Over tunnel on Bald Mountain, Tuolumne county, the rim rock of lime having already been penetrated seventy feet. It is not thought that the belt will exceed 100 feet in width before a slate formation will be encountered.

Work on the Central Hill gravel mine, in Calaveras county, has been stopped on account of the lack of water, and no water can be secured now until the rainy season sets in. At the last workings, which were of a development character, a rather singular bank was left, disclosing a page in the history of this interesting river bed, which differs from any other yet found. Pure sulphur forms on the face of the bank in fungus-shaped exudations, and the little trickling stream from the bank is highly mineralized and of an extremely saline nature. Further along is seen the stump of a tree, rich in wood agate and specimens. This should be sent to the State Mining Bureau for exhibition.

The sinking of the incline shaft on the Minnehaha mine, near Logtown, El Dorado county, is still continued. The shaft is now about fifty feet in depth and good ore is being hoisted.

The mine in Lassen county, owned by Charles Littlefield, was recently bonded for \$5,000.

The Mariposa Grant Co., with headquarters at Mariposa, in the county of the same name, is making arrangements to buy a twenty-stamp mill in Tuolumne county, to be put up at the Mariposa mine. If the mill being negotiated for cannot be secured, they will purchase a new ten-stamp mill. Sinking is to be resumed at once, and 200 feet more will be sunk on the mine.

The Red Dog mill, at Randsburg, Kern county, is milling between fifty and sixty tons of ore for the Butte Lode Mining Co.

The Confidence mine, at Sonora, Tuolumne county, will soon be running full blast. Retimbering the shaft is now in progress.

There are, at present about 75 men employed at the Declez quarries, near West Riverside, in Riverside county, taking out rock for the San Pedro harbor breakwater. This force will soon be doubled. A grading outfit is now at the quarry, and several new sidetracks will be put in to untouched portions of the quarry.

A discovery of a large vein of good coal is reported at Santa Rosa, Sonoma county.

Tunnel No. 2 of the Hart Consolidated Co., near Garden Valley, El Dorado county, is now in the mountain about 175 feet. The owners expect to tap the ledge shortly.

The Kinyon mine, at Randsburg, Kern county, has been leased by Swartout & Jones, who are now clearing out the shaft.

The large boiler at the old Blanchard mine, on Weaver Creek, has been moved to the Ribbon Rock mine, on the mother lode, south of Placerville, El Dorado county. The boiler, which will furnish sixty HP., is nearly in place. Development work is being actively prosecuted at the mine.

W. A. Hoyt and A. S. White, the owners of the Golden Eagle, located a few miles beyond West Riverside, are still at work on the mine. They have men employed running a tunnel to crosscut the main ledge some distance below the surface croppings. The tunnel has now reached a depth of seventy-five feet, and is to be used as an entrance to the mine for transporting the ore to the surface.

The Val Verde, at Johannesburg, Kern county, has had 100 tons of ore milled at the Red Dog mill. The ore was taken out in the development of the property, which gives promise of being a steady producer.

The new twenty-stamp mill for the Mt. Jefferson property, at Groveland, Tuolumne county, is about completed, and operations will soon commence in earnest. A quantity of sulphurets is being hauled to Jamestown, to be shipped for treatment.

The new chlorination plant at the Shawmut mine, another of Tuolumne's bonanzas, is progressing favorably, the foundation having been

laid, and the frame work placed in position. The mill on the property is not running.

An immense ledge of rich ore, said to be sixty feet in width, has been discovered by Mr. Walker of Menifee at Rosamond, Kern county.

Work is expected to commence shortly at the California Borax Works, near Searles, Kern county. The works are in splendid condition, and when started up there will be no necessity of an immediate close-down.

COLORADO.

The September output of the Cripple Creek mines was 35,000 tons, valued at \$1,950,000.

John Grand of Detroit, Mich., has bought the Galena group of mines in Gilpin county from the Alpha Mining Co. He represents an English concern which will make other purchases and undertake mining operations on a large scale.

The Forest Hill Consolidated Mining Co. of Gunnison and the Canton & Pittsburg Mining Co. are developing claims on Forest Hill in Gilpin county. They own thirty-one claims consisting of 300 acres.

The option on the Camp Bird mine in Ouray county has been extended two months at the request of John Hays Hammond, who is examining the mine in the interest of an English concern. The final examination was made on September 22, and the extension of time was granted by J. W. Benson, general manager, representing Thomas F. Walsh, the owner, in order that the prospective purchasers might have a full opportunity to investigate the property. The price set was originally \$15,000,000, but the extension of the option will make the property cost the Englishmen an additional million if Mr. Walsh has his way about it.

The strike at Stratton's Independence, caused by the announcement that the men would be obliged to change their clothing after leaving the mines in order that they might be searched for stolen treasure, was settled by a compromise by which only those who are actually suspected of stealing will be obliged to submit to examination.

IDAHO.

The Iola mine at Warren is being worked with considerable success by the lessees. It has a ten-stamp mill. At the same place, the Rescue is being pumped out by the Idaho Consolidated Co., which intends to open the ore bodies in the lower levels and sink as far as the present hoist and pump will permit.

The Daisy mine at Quartzburg is producing ore that mills \$100 a ton and has a five-stamp mill running steadily.

Report comes from Idaho City that the large properties of the Atlantic Gold and Silver Mines, a company of Englishmen, have been purchased by J. C. Johnson of Lincoln, Neb. The mines will soon be opened up extensively. The Atlantic lode is one of the largest in the west, running from 100 to 250 feet in width, and having been tested to the depth of 1,600 feet by tunnels.

MONTANA.

On a mine owned by R. A. Bell of Helena, situated twelve miles from Helena, a wonderfully rich strike has been made. The mine is known as the East Pacific. It is declared that the present strike runs from \$30,000 to \$40,000 gold a ton. The strike was made while drifting tunnel No. 4, which is now more than 2,000 feet below the surface, while making a drift at a depth of about 900 feet. It is evident that the ore increases in value with the sinking. Mr. Bell claims to have found pieces of ore which are at least one-half solid gold. Before this strike the East Pacific had produced upwards of \$1,500,000 in gold. It is believed that the East Pacific's ore shoot is one of the longest in the west, the pay shoot in tunnel No. 4 being over 2,500 feet long. While the vein is not wide, its length makes it a most remarkable discovery. The ore is sometimes of low grade, but the average is so high that the mine is certain to be a wealth producer of the first order.

The Barden tract in the Helena copper district has been bonded by F. Aug. Heinze for \$15,000.

O. P. Chisholm of Bozeman has taken a bond on the coal lands of Conrad & Cooney in Gallatin county, the price being \$125,000. The coal is semi-anthracite and well adapted for smelting and domestic purposes.

In the Kearsarge mine, Madison county, a valuable strike has been made. Smelter returns show a high percentage of gold. In the General Shafter

mine, adjoining the Kearsarge, a three-foot vein of high-grade ore has been found.

In North Helmsville, Deer Lodge county, a lively copper camp is springing up. An ore body sixteen feet wide and quite rich in copper has been encountered by Russell & Co. sixty-five feet down. Ore running about \$75, with concentrates \$200 in gold and lead has been found at the Ptarmigan mine in the same vicinity.

SOUTH DAKOTA.

Twenty additional stamps have been ordered by the Homestake Company of Lead for the Caladonia mill at Terraville, which will be ready for ore within a month. An extension is being made on the Black Hills and Fort Pierre Railroad down to the mill. The De Smet's machinery for its new hoisting plant is on hand, and the starting of these two old mills by the Homestake company will call for the work of 600 men.

Wisconsin capitalists have bonded the Yellow Bird mine in the Hornblende district and are running a long tunnel to tap the main ore vein. A hoisting plant will be erected. The ore runs from \$18 to \$120 a ton in free gold.

A. D. Ticknor, owning properties in the Bear Gulch district, has made a rich discovery of free milling ore on his claims. One assay runs as high as \$5,660 a ton.

The Big Bend Mining Co. is working a placer on Rapid River below Pactola and is cleaning up nearly \$1,000 a day in gold. D. C. Sherman of Pactola is associated with two New Yorkers on the work. A steam dredge is now at work on gravel carrying about fifty cents in gold to the cubic yard.

The Pluma chlorination works will soon be started by the Horseshoe Mining Co., which has discovered a large body of ore at Terry.

UTAH.

Settlements of \$2,153,485 were made in the ore and bullion market at Salt Lake City in September. This is the record figure for any single month of this year. In the total is included the Consolidated Mercur's first shipment of gold bullion, forwarded on September 15 and valued at \$182,446, also the \$30,000 product of the cyanide plants that passed through the gold sampling rooms of the American Smelting & Refining Co. Ores forwarded by individual buyers and the copper, gold and silver bullion amounting to 481,000 pounds, forwarded by the Highland Boy to eastern refineries would add about \$200,000 to the total.

The Horn Silver Mining Co. has issued a report showing that it has marketed in the past year 150,000 tons of crude ore and concentrates with a total value of \$600,000. The company will close its anniversary with over \$250,000 in the treasury. A feature of the next year's business at the mine will be the handling of the zinc ores.

WASHINGTON.

The Palmer Mountain tunnel is now 2,650 feet in length and is growing at the rate of 130 feet every thirty days. The enterprise appears to be most successful, and the operators are now trying to determine the most advisable manner and method of treating the large bodies of ore. So far as quantity and depth go there is no longer any doubt.

A strike has been made in the Anaconda group in Becker River district which has been bonded by eastern capitalists. The ore body is about fifteen feet wide, with gold and copper values from \$30 to \$60.

A discovery of anthracite coal is reported in Snohomish county, sixty miles from tidewater. The extent of the coal bed is not yet known.

The two mills in Slate Creek district are working on the ores of the Eureka and Mammoth gold mines. It is likely that the mills will run throughout the winter, for there is an abundance of ore on hand which would take the full attention of several mills of much larger capacity.

IRON AND STEEL

PRESSED STEEL CAR BUSINESS: President Schoen of the Pressed Steel Car Co. is quoted as stating that his company recently took contracts within eight days for steel cars approximating in money value nearly \$7,000,000.

SHIPMENTS FROM DULUTH: The shipments of iron ore from the head of the Lakes, for the season to October 1, were 7,582,969 gross tons, as

compared with 5,918,309 tons for the corresponding period last year, an increase of 1,664,660 tons. The shipments for the month of September were 1,682,552 tons, as compared with 1,058,628 tons for the same month last year.

STEEL SHEET COMPANY MOVING TO NEW YORK: October 13 was the date set for the removal of the operating offices of the American Sheet Steel Co. from Pittsburg to New York City. The New York headquarters of this company will be in the Battery Park Building, where the American Tin Plate Co., the American Steel Hoop Co. and the National Steel Co. are already located.

DISSATISFIED RAILROADS: Certain railroad interests have been dissatisfied with the price of rails as fixed by the rail makers' pool, and have been insisting that \$22 a ton should be the price instead of \$26. It has been said that President James J. Hill had called a meeting of railroad presidents to take joint action on the matter. Mr. Hill denies that he has called such a meeting or has even heard of such a meeting. President Cowen of the Baltimore & Ohio, President Truesdale of the Delaware, Lackawanna & Western, and several other railroad officials deny that they have heard of any such meeting. Carnegie officials are also quoted as denying the report that that company was likely to reduce the price of rails, and say it has positively determined to maintain the \$26 rate.

STEEL AND WIRE DIVIDENDS: The following is a statement of a director of the American Steel & Wire Co. concerning the statement attributed to Mr. Gates that the payment of dividends on the common stock is a mistake:—"I do not believe that any director of the American Steel & Wire Co. made the statement that the payment of the dividend on the common stock was a mistake. The earnings last year were so large that after paying out the \$2,800,000 dividend on the preferred there was \$10,000,000 left, and if a company issues common stock, the holders of that common stock are entitled to their share in good years. This year the dividend on the common and preferred stocks was actually earned in the first six months for the entire year. In July and August business was light, but in September the volume of business has been larger than last year and probably beats all records. At this rate the present large holdings of raw materials, as well as the finished goods will be soon turned into money, and nobody can tell at the present time what the company will do regarding the dividend on the common stock next March, the dividend for January having already been declared in February. The demand for all wire is exceedingly good, and the condition of the company is just as good to-day as when insiders declared the stock cheap at fifty. Regarding opposition, there is some opposition in the wire trade to-day, and it is only to the interest of the company that there always should be. The country is growing, exports are growing and there is enough business for a few other companies if they start up."

COMPETITION BETWEEN BIG STEEL COMPANIES: In the division between the various large combinations that have been formed during the last few years in the iron and steel trade there has been no exact separation of the various branches of such manufacture. Bradstreet's in a recent editorial article says that several of the companies created by a union of different plants compete with each other in the production and sale of certain classes of products, and the rivalry arising from this and the cutting of prices by the different companies has been among the serious difficulties with which the large iron and steel industrialists have had to contend. A recognition of this fact is afforded by a rather curious deal which, it is announced, has just been effected between the Republic Iron & Steel Co. and the American Sheet Steel Co. Under an arrangement recently effected, the American Sheet Steel Co. is to abandon the departments of some of its plants which have heretofore been engaged in the manufacture of bar iron and to transfer the same to the Republic Iron Co. On the other hand, the Republic Iron & Steel Co. exchanges for the above establishments certain portions of its properties at which steel sheets were made, and turns them over to the American Sheet Steel Co. either to operate or dismantle, as may be deemed most advantageous. It is, of course, hardly possible that any general tendency to make exchanges of this kind will result, but the conclusion may be drawn that managers of large industrial combinations are inclined to diminish the number of points at which unnecessary competition could arise between the various concerns.

COLORADO FUEL AND IRON AFFAIRS: Says President Osgood—"The general business situation in the far West, as I see it, is excellent. In the case of our company the coal and coke business is the largest ever known. The demand is very large and requires our best exertions to meet it. The steel business of the company has doubled in the past thirty days, and while prices are still low the tendency is stiffer, and the outlook, so far as we are concerned, is encouraging. I look for a healthy business after the election, provided Mr. McKinley is re-elected. The railroads in the West are so prosperous that I am confident they will be large purchasers of rails. The new price is undoubtedly satisfactory to most railroad presidents. The steel rail industry is a large one, and directly related to many other large industries, and it is therefore not to the interest of the railroads to see abnormally low prices for rails. Furthermore, if the price of rails be made unduly low it encourages reckless competition in the way of new railroad construction. Then, too, a low price for new rails means that railroads get so much less for old material. The difference between \$26 per ton and \$23, which I understand was the figure predicted by some, is only about \$300 per mile for an ordinary road. With the ability of most railroads to borrow money this would mean only about \$12 a year per mile added to fixed charges. It is not reasonable to suppose that this difference would deter railroads from putting down new rails when needed. It may also be worth stating that if ocean tonnage could be secured a ready export market could now be found for rails at present prices."

COAL AND COKE

PACIFIC COAST CO'S BUNKERS BURNED: On September 22 the coal bunkers of the Pacific Coast Co. at Astoria were completely destroyed by fire. They contained at the time between 600 and 700 tons of coal. The loss is estimated at \$30,000.

ACTIVITY AT CAPE BRETON: Charles Fergie is directing extensive operations in the coal beds of Mackenzie & Mann at Broad Cove, on the northwest coast of Cape Breton. It is estimated that these properties contain at least 100,000,000 tons of workable coal, equal in quality, it is believed, to that of the Dominion Coal Co., and the seams are favorably situated for shipping. Mr. Fergie expects to have one mine fully equipped and in active operation within a year.

LEHIGH VALLEY CO'S PRIZE: The Lehigh Valley Coal Co. received the highest prize in the gift of the judges at the Paris Exposition for its display. The exhibition included a reproduction of the company's No. 40 shaft and breaker as they actually exist at the mine. There were also specimens of the different varieties of coal mined and many other interesting features. The judges accompanied their prize by a note complimenting the company and its officials for the novelty and completeness of their display.

COAL OUTPUT IN 1899: Edward Parker of the Division of Mines and Mineral Resources of the United States Geological Survey, has just made public his report on the coal production of this country during last year. The report shows that 1899 was by far the most remarkable in the history of the United States coal mining. The production was larger than ever before by nearly 34,000,000 tons, and prices were greatly improved in all sections of the country. The production of anthracite was 53,944,647 tons, an increase of 2,161,525 tons over the record of 1895, the highest production reported hitherto. The production of bituminous coal was 172,608,917 tons. This figure surpasses all previous reports and puts this country at the head of the world's coal producers. The increase was 33,765,325 tons, or 15.35 per cent over 1898 and 53,518,327 tons, or 26.73 per cent over 1897. Comparing the product in 1899 with some of the earlier years of our history, a still more remarkable advance is shown. In 1889 our total production of coal was 141,229,613 tons, showing an increase in ten years of 112,510,379 tons, or nearly eighty per cent. In 1879 our production amounted to only 66,452,960 tons, compared with which the output in 1899 shows an increase of about 288 per cent, while in thirty years the production has increased about 700 per cent, the yield in 1899 being eight times that of 1869, one generation ago. In the same period the production of Great Britain has about doubled, that of Germany has been multiplied by four, and that of France by 2.5. In 1869 the total product of Great Britain was nearly four times that

of the United States, and that of Germany exceeded ours by about twenty per cent. In the bituminous trade the production and consumption were limited only by the ability of railroads to furnish the cars and provide the means of hauling them, and in some cases by the ability of operators to secure the labor sufficient to keep the tonnage up to the demand. It was the first time in many years that the productive capacity of the bituminous mines was not in excess of the market requirements for at least a portion of the year. The wonderful activity which prevailed throughout the year in the iron and steel trades created a demand for coke that kept practically every available oven in the country operating to its full capacity and taxed the railroads entering the coking districts to provide transportation for the output. The entire year was one of remarkable activity in all branches of the coal business and will have a notable place in the history of the trade. One of the effects of the enormous increase in production was the placing of the United States ahead of Great Britain as the leading coal producer of the world.

THE METAL MARKETS.

General Review and Forecast of Trade Conditions

Silver Strong—Copper Quiet but Firm—Tin Apathetic—Lead Firm—Spelter Active—Steel in Suspense—Coal Waiting.

On the editorial page we discuss at some length the recent history of the silver market and the probable course of the same in the next few months. The position taken there is that the producers of silver may reasonably expect to receive for their product better prices on the average than they have enjoyed for several years. The advance has been gradual and legitimate, without speculative features; and the same commercial causes that have caused and supported the advance are still operative, having by no means spent their force. On the 12th inst. the commercial price of bar silver was 63½¢. Mexican dollars stood at 50½¢.

COPPER QUIET, BUT STEADY.

Not for a long time has the copper market developed so little activity as during the last two weeks. No weakness has resulted from the comparative quiet, and the general tone has been consistently firm. Probably the near approach of the election period and the natural disposition of manufacturers to move slowly at such times account for the limited dealings in this staple. The best opinion still appears to favor high prices for the metal in the next few months; and even large consumers, whose interest it is to think and talk bearishly, do not now in private discussion express hope of an early return to lower values. They seem to be basing their calculations for the next year on the present range of copper values. Our latest quotation for lake copper was 16.87½¢, and for Electrolytic, 16½¢.

THE MINOR METALS.

Tin reacted with some vigor from the extreme depression of last month, but it did not hold the advance, and the buyers seem to have no fear of the market. They are covering only their immediate wants, and are satisfied to let the future take care of itself. The closing price was 28½¢.

Lead continues in good demand, and considerable quantities of the metal are passing steadily into consumption. For the first eight months of the year the Treasury Department reports imports of lead into the United States as 132.3 million pounds, as compared with 146.2 in the same period last year. Our re-exports of foreign lead refined here, however, were 105.8 million pounds this year, as compared with 125.3 last year. The net balance of imports, therefore, this year was 26.5 million pounds, as compared with 20.9 last year. We report the current price of lead as 4.35 New York and 4.27½ St. Louis.

Spelter is moving freely at fair prices. The European market continues strong, and exports are heavy. We report the current price as 4.10c. New York, with St. Louis about fifteen points lower.

IRON AND STEEL.

The iron market is in an unsatisfactory condition owing partly to the deadlock caused by the disposition of the railroads not to accept the \$26 price for steel rails named by the combination, and partly to the policy of conservative caution that is naturally followed by the great iron and steel industries in an ante-election period. Prices are inclined to sag under the conditions de-

scribed, and in some articles the lowest prices yet recorded in the present decline have been made in the last few days. It is unlikely that any decided change for the better will occur until the election is over. By that time the steel-rail problem will have been solved in all likelihood, and in other respects the way will have been cleared for an early resumption of activity. The latest demand of the country for iron and steel in all forms is undoubtedly enormous, and the best judges look for an era of fair prices and great activity in every department of the iron industry.

COAL AND COKE.

It is hardly worth while to discuss this market until the anthracite strike has been settled. At this writing it is expected that a settlement will have been made by the time this matter is in print, although some little time will be required at best for the machinery of production to attain its normal efficiency. It looks now as if the miners would be successful in their demand for increased wages, and if so the consequent higher prices to consumers may curtail sales somewhat. On the whole, however, the outlook is fair for a winter of activity and profit to anthracite operators.

The bituminous branch of the industry continues to flourish. It is profiting from the troubles in the anthracite region, and the only difficulty that producers have is to obtain cars enough to fill their orders.

NEW INCORPORATIONS.

COLORADO.

SALVADOR GOLD MINING AND MILLING CO., Denver; \$300,000; H. K. Chittenden.
NORTHWESTERN OIL & COAL CO., Colorado Springs; \$1,000,000; W. W. Shemwell.
IDAHO SPRINGS GOLD PRODUCING CO., Idaho Springs; operating mines, etc.; \$250,000; R. Marshall.
COLORADO MINES CO., Denver; \$2,000,000; F. Rekey.
DOROTHY GOLD MINING CO., Cripple Creek; \$1,500,000; H. M. Sprague.
PIONEER LYNN MINING CO., Denver; \$100,000; C. W. Grose.
NORTHAMPTON GOLD MINING & MILLING CO., Cripple Creek; \$1,000,000; A. T. McDill.
CHICAGO MINING & LEASING CO., Chicago; Ill.; \$500,000; W. M. Wemott.
RENO MINING CO., Mineral, Wyo.; \$25,000; G. C. Dewey.
KITIE M. MINING & LEASING CO., Cripple Creek; \$100,000; S. C. Cummings.
AMERICAN EAGLE MINING CO., Georgetown; \$100,000; W. H. Pease.
GAREUTT MINING CO., Leadville; \$40,000; I. Mortenson.
CHARTER OAK CHANCELLOR MINING & MILLING CO., Georgetown; \$50,000; W. H. Maxton.
MISER GOLD MINING & MILLING CO., Denver; \$1,000,000; A. Ross.
YOUNGSTOWN MINING CO., Fair Play; \$500,000; C. E. Semple.
AUROGENTUM MINING CO., Leadville; \$100,000; L. H. Weber.
EVALYN MINING & LEASING CO., Leadville; \$500,000; J. H. Fletcher.
NEW MEXICO SMELTING AND REFINING CO., Denver; smelting and refining business; \$1,000,000; A. J. Frank.
LORD BYRON MINING CO., Georgetown; \$500,000; W. M. Giller.
THERESA MINING & LEASING CO., Denver; \$10,000; D. E. Parais.
SOUTH WINNIE LEASING & MINING CO., Leadville; \$250,000; L. F. Long.
ENGLISH-AMERICAN GOLD MINING CO., Cripple Creek; \$1,250,000; E. Yokel, Chicago, Ill.
MAJOR GOLD MINING & MILLING CO., Boulder; \$200,000; M. H. Davis.
LATSHAW MINING, TUNNEL & MILLING CO., Buena Vista; \$2,000,000; I. M. Latshaw.
COLORADO SPRINGS COPPER MINING & TUNNEL CO., Colorado Springs; \$25,000; D. A. Russell.
FIRST NATIONAL GOLD MINING CO., Denver; \$100,000; F. I. White.
GOLDEN AGE NO. 2 MINING & MILLING CO., Boulder; \$250,000; D. Mowery.
OREGON & BOSTON MINING CO., Boston; \$500,000; E. A. Kingman.
KOKOMO PIONEER MINING & MILLING CO., Idaho Springs; \$1,000,000; F. L. Burton.
QUARTZ MINING & MILLING CO., Silverton; \$100,000; E. P. Watson.

SNOWSHOE GOLD MINING CO., Denver; \$5,000; A. J. Monahan.
LING GOLD MINING CO., Boston, Mass.; \$100,000; G. W. Flynn.
COLORADO CITY MINING & LEASING CO., Colorado Springs; \$10,000; R. S. Briscoe.
REILING GOLD DREDGING CO., Colorado Springs; \$150,000; H. J. Relling.
DELAWARE.

LA TRINIDAD MINING & MILLING CO. OF MEXICO, Wilmington; \$500,000; A. A. Waite.
OAXACA MINING & INVESTMENT CO., Wilmington; \$500,000; M. S. Stout, Denton, Tex.
NATIONAL SMELTING CO., Dover; smelting business; \$500,000; A. W. Gilliland, St. Louis, Mo.
BINGHAM CONSOLIDATED MINES CO., Dover; \$650,000; J. Virdin.

INDIANA.

GREEN HILL COAL & MINING CO., Sullivan; mine coal; \$500,000; D. Mathews, Columbus, O.
RIVERSIDE MINING & MILLING CO., Greensburg; operate mines and water power; \$60,000; G. L. Roberts.
GLEN OAK COAL MINING CO., Terre Haute; operate coal mines; \$20,000; S. Egle.
BLOOMFIELD MINING, GAS & OIL CO., Bloomfield; mine coal and sink oil and gas wells; \$5,000; L. H. Jones.
JOHN H. BULL MINING CO., Lafayette; mine lead and zinc; \$50,000; E. V. Burt.

MAINE.

AMERICAN MINING & METAL EXTRACTION CO., Portland; \$200,000; J. J. Henry, Boston, Mass.
DEER CREEK GOLD MINING & MILLING CO., Portland; \$10,000,000; R. L. Lee, Plainfield.
ST. REGIS ADIRONDACK GOLD MINING CO., Portland; \$200,000; H. P. Abecorn, Boston, Mass.
TOURNAINE GOLD MINING & MILLING CO., Portland; \$150,000; J. E. Kilduff, Boston, Mass.
THOMAS STRAHAN CO., Portland; \$150,000; G. H. Smith, Arlington, Mass.
HOPE GOLD MINING CO., Portland; \$200,000; G. H. Gould.

MICHIGAN.

KENDRICK GOLD MINING CO., Detroit; \$100,000; E. D. Williamson.
EARL MINING & SMELTING CO., Detroit; \$50,000; J. G. Ferguson.

MINNESOTA.

MINNEAPOLIS MINING & DEVELOPMENT CO., Minneapolis; \$50,000; H. C. Peterson.

MISSOURI.

SWANSEA COPPER CO., St. Louis; \$250,000; D. G. Gibson, Webster Groves.
CLIFF LEAD & ZINC MINING CO., Joplin; \$12,000; H. Crossman.
GRANITE MINING CO., Webb City; \$50,000; J. G. McRoberts.
MARION MINING CO., Joplin; \$50,000; J. W. Allen.
CLEAN-MOORE LEAD, ZINC & REALTY CO., Pioneer; \$200,000; F. Clear, Joplin.
MANANITA MINING CO., Kansas City; \$5,000; C. L. Merry.
BEN FRANKLIN ZINC MINING CO., Joplin; lead and zinc mining; \$50,000; F. P. Fairchild.

NEW JERSEY.

GOLDSTONE MINING & MILLING CO., Jersey City; \$300,000; P. Whitney.
GOLDEN GRANT MINING & MILLING CO., Camden; \$1,000,000; G. W. Mark.
ELWOOD MINING & MILLING CO., Jersey City; \$100,000; H. G. C. Thornton, Cranford, O.
PORCUPINE MOUNTAIN COPPER CO., Jersey City; \$2,500,000; T. C. Bates, Worcester, Mass.
PANAL PLACER CO., Jersey City; \$250,000; F. L. Patton, Jr.

PENNSYLVANIA.

JAMES McNEIL & BRO. CO., Pittsburgh; manufacture iron and steel; \$150,000; T. McNeil, Sr.

TEXAS.

TEXAS COAL & MINING CO., Austin; mining coal; \$50,000; William H. Stacy.

WASHINGTON.

NORTH STAR MINING CO., Seattle; \$1,000,000; A. Fraser.
AENEAS VALLEY GOLD MINING CO., Republic; \$100,000; J. W. Sneed.
BRIGHT SPOT GOLD MINING CO., Weherville, Wis.; deal in mines, smelting works, etc.; \$1,000,000; R. Boeltcher.
GREAT WESTERN COPPER CO., Spokane; \$15,000; A. S. Dibble.
UNITED STATES CONSOLIDATED MICA MINING CO., Spokane; \$250,000; A. Munro, Idaho.

MINING STOCK QUOTATIONS IN VARIOUS MARKETS

Mining stocks multiply incessantly, and we cannot undertake to record them all. We keep, however, complete records of all mining stocks, wherever listed, and we shall be glad to furnish any subscriber, on request, with detailed information about quotations. The prices given below are in most cases those current at the close of business on the day we go to press—two days before the date of issue.—Mining and Metallurgical Journal.

BOSTON.			SALT LAKE.			MEXICO.		
Adventure.....	4 50	Old Colony Cop. 3 00	Anchor.....	—	Jon Bowers Ex. 00%	Name of Company.	State.	Price.
Alouez.....	1 50	Old Dominion. 20 00	Ajax.....	46	Low. Mam'oth 44			
Anacosta.....	18 00	Oscoda..... 64 50	Alco.....	50	Little Pitts'h. 00%			
Arvidian.....	4 25	Parrott..... 44 00	Black Bear..	4 00	Mammoth..... 2 20			
Atlantic.....	22 50	Rhode Island. 3 50	Cent. Eureka..	10 00	Mercur.....			
Battle.....	21 50	Santa Fe..... 6 00	Chloride Point	—	May Day..... 43			
Bonanza.....	11 00	Tamarack..... 233 00	Daly.....	1 75	North Light.. 06			
Boston & Mont. 323 06		Tecumseh.....	Daly West.....	19 00	Ontario..... 5 62%			
Butte & Boston 61 00		Tri-Mountain. 8 75	Dalton & Lark.	—	Petro.....			
Cal'met & Hecla 755 00		Victoria..... 2 00	Dexter.....	1 25	Rich. Anac'nda			
Centennial.....	15 50	United States. 30 25	Daisy.....	02%	Sunshine..... 4 00			
Credit.....	8 50	Utah Con..... 75	Engle & Blue Pl	65	Swanson..... 1 25			
Copper Range..	38 50	White Knob.. 13 00	Emerald.....	—	Sunbeam..... 32			
Dominion Coal	14 00	Winona..... 2 50	Four Aces.....	02	Sacramento.. 33%			
Franklin.....	30 00	Wolverine..... 40 50	Geyser Marion	15	Silver King... 58 00			
Marcell.....	16 00	Zinc..... 9 00	Grand Central	5 05	Star Concl... 1 05%			
Mohawk.....	—	—	Golden Eagle..	—	Tetro.....			
NEW YORK.			Horn Silver... 1 25	Utah..... 84	Utah..... 10%			
Adams Con.....	—	Golden Fleece. 25	Homestake....	—	Valco..... 02%			
Alamo.....	—	Gould & Curry. 32	Ingot.....	—	Y.M.M. Placer			
Alcoa.....	—	Hale & Norr's 31	Joe Bowers....	03%	Yankee Con.. 20			
Amalgama'd.....	87 00	Horn Silver... 68	SPOKANE.					
Anacosta C.....	45 00	Isabella..... 1 11	Ben Hur.....	—	Morning Glory 07%			
Argentum.....	—	Jack Pot..... 18	Black Mt. Lion	—	Mountain Lion 58			
Best & Belcher 34 00		Julia Conso... 18	Butte & Boston	—	Pearl.....			
Breece.....	—	King & Pemb.. —	Deer Trail No. 2	04	Princess Ma'de			
Brit. Col.....	11 50	La Crosse..... —	Golden Harv'st	—	Quip..... 15			
Brunswick.....	—	Leadville..... 07	Insurgent.....	—	Republie..... 80			
Caladonia.....	41 00	Little Chief.. 18	Jim Blaine.....	10	Tom Thumb.. 20			
Catalpa.....	—	Mexican..... 34	L.Pine Sur. Con	09	SAN FRANCISCO.			
Chollar.....	—	Mollie Gibson. 26	Alpha Con.....	05	Kentucky Con. 03			
Chrysolite.....	03	Moulton..... 55	Alta.....	02	Lady Wash Con 03			
Com. T. stock.	—	Mount Rosa... 55	Andes.....	09	Mexican..... 37			
Com. T. bonds	—	Ontario..... —	Belcher.....	17	Occidental.. 06			
Com. T. script	—	Ophir..... 55	Best & Belcher	30	Ophir..... 80			
Con. Cal. & Va.	1 25	Pharmacist.. 13	Bullion.....	05	Overman..... 10			
Cr. & Cr. Creek	12%	Phoenix..... 14	Caladonia.....	41	Potosi..... 23			
Crescent.....	—	Phosphate... 18	Challenge.....	20	Suez Belcher 36			
Cripple Ck Con	02	Plymouth..... 3	Chollar.....	25	Savage..... 02			
Crossus.....	—	Portland..... 3 15	Confidence....	75	Sierra Nevada. 36			
Crown Point..	—	Potosi..... 23	Con. Cal. & Va.	1 25	Standard..... 3 90			
Damon.....	17%	Quicksilver.. 750	Con. Imperial.	01	St. Louis..... 15			
Deadwood Ter	50	Quicksilver pr. 7 50	Crown Point.. 13	Sydenham..... 04	Union Con..... 13			
Elkton.....	—	Savage..... 35	Deer Trail No. 2	04	Utah Con..... 24			
Eureka Con...	—	Sierra Nevada. 80	Golden Fleece.	20	Yellow Jacket. 24			
Fath De Smet.	—	Small Hopes.. 30	Gold King.....	1 17	—			
Findlay.....	15	Specimen..... —	Gold Knob.....	12	—			
Garfield.....	08	—	Gold Sover'gn.	07%	—			
			Gould.....	32	—			
			Hart.....	18	—			

PORTLAND IMNAHA COPPER MINING CO., Spokane; \$1,500,000; F. H. Sanders.
 BERT CHANGE MINING CO., Seattle; \$1,500,000; A. W. Hager.
 LAKE CHELAN COPPER CO., Spokane; purchase and lease mining lands; \$10,000; W. Truitt.
 HOME MINING CO., Cle-Elum; \$200,000; T. Johnson.
 SILVER BUTTE MINING CO., Tacoma; \$10,000; H. E. Huatvold.
 MINERAL HILL CONSOLIDATED CO., Spokane; \$700,000; J. R. Boysell.
 CEDAR VALLEY GOLD MINING CO., Spokane; \$500,000; L. K. Armstrong.
 ELWELL DARRINGTON MINING CO., Seattle; \$1,000,000; J. A. Elwell.

LUCKY EIGHT MINING CO., Seattle; \$1,200,000; J. E. Lowry.
 CANADIAN AMERICAN MINING CO., New Whatcom; \$2,500,000; J. E. Mitchell.
 RICHARD R. MINING CO., Spokane; \$50,000; W. C. Dice.
 VIOLET MILLING & MINING CO., Seattle; \$1,500,000; J. M. Roberts.
 DIXIE QUEEN GOLD MINING CO., Spokane; \$1,000,000; W. H. Plummer.
 TEARAWAY MINING SYNDICATE, Seattle; \$250,000; R. A. Barru.
 GEORGE REED MINING CO., Spokane; \$150,000; J. W. Graham.
 SANGER DEVELOPMENT CO., Walla Walla; \$40,000; W. M. Moore.

MILWAUKEE PALMER, MOUNT GOLD & COPPER TUNNEL CO., Weherville; \$6,000,000; J. J. Hughes, Seattle.
 MARIETTA MINING CO., Everett; \$1,500,000; W. R. Stockbridge.

WEST VIRGINIA.

LONE PINE MINING CO., Prescott, Ari.; \$3,000,000; F. Evans, New York City.
 FAIRMONT COAL MINING CO., Fairmont; general coal and coke business; \$1,000,000; A. B. Fleming.
 PLEASANT VALLEY MINING & MILLING CO., Ecstun, Mass.; \$400,000; W. P. Jackson.
 CENTER GOLD & COPPER MINING CO., Center, N. C.; \$250,000; J. V. Bruyn, New York City.

WANTED

Advertisements of this class containing not more than five lines will be inserted for not exceeding three months in any year, free of charge, for all paid-up annual subscribers.

Other than above, 20 cents a line. Advertisements not accepted for less than one month.

ASSAYERS AND MINERS to correspond with us in regard to Minerals and Crystal Groups for Cabinets. Best prices paid for fine cabinet specimens.

ROY HOPPING,
129 4th Ave., N. Y.

CAPITALIST or Promoter required to form company to purchase and operate fifty miles of gold dredging territory (not Yukon). Estimated value per cubic yd., 30 to 60 cents; estimated cost per cubic yd., 3 to 5 cents; estimated amount of auriferous gravel, 70,000,000 cubic yds. Address, "N. W. T.," New York Office, M. and M. Journal.

CHEMIST desires position in commercial laboratory or technical works. Best of references as to professional and business ability. J. W. FELL, Asheville, N. C.

MINING engineer, with camping and assay outfit, would be glad to join a prospecting party on reasonable terms. Address, PROSPECT, Mining and Metallurgical Journal Office.

PARTNER required in active management very extensive gold dredging interests. Price of share, \$20,000. References exchanged. Placer engineer preferred. Address, CANADA, New York Office, M. and M. Journal.

EXPERT hydraulic and steam engineer, experienced in transmission of power by electricity, desires position (Colorado or Montana preferred) as superintendent of mining power plant. Address, E. S. C., Mining and Metallurgical Journal.

WANTED.—Position as superintendent by pushing and up-to-date mining engineer, who understands all branches of mining and milling gold ores. Has his own assay outfit, and would be willing in a small mine to do the assaying and surveying. Address, D. P. A., Mining and Metallurgical Journal Office.

GEORGIA GOLD MINING.—Party long experienced in mining and milling desires co-operation for handling choice exploited property secured by lease-option. Very small amount needed. Correspondence solicited. MINER, 24 Ellis St., Atlanta, Ga.

SITUATION WANTED.—A competent and experienced mill man desires position on concentrators or batter frame. Highest references. Address, L. W., 509 Kearny St., Room 2, first floor, San Francisco, Cal.

AN EXPERIENCED assayer and bullion refiner with the best of references, several years' experience, and a university training, desires employment with some mining company. HAROLD FRENCH, Los Angeles Office, M. & M. Journal.

WANTED: PARTNER or Co. to open coal mine near RANDSBURG. Three veins, the third being nine feet, four feet solid coal, 101 feet from surface. Two first veins opened with shaft, 1,600 acres discovered along the rim of field.

F. H. HEALD, Randsburg, Cal.

ENGINEER and Metallurgist of long experience, fearless, energetic, trustworthy, seeks position; managing, erecting, reporting or developing. Speaks French, German, Spanish and excellent Chinese. Exceptional testimonials. Will go anywhere. Address, MINERO, Mining and Metallurgical Journal Office.

MINING MEN, business men and pleasure-seekers, given prompt attention and good service. Daily stage operated to and from Helvetia. BARKLEY BROS., Proprietors the Tucson Stables, corner Congress St. and Sixth Ave., Tucson.

FOR SALE

FOR SALE.—Near Birmingham, Ala., a rich iron mine. Brown hematite ore. 26-foot vein, average 65 per cent. Also fine vein of silver and copper. For full particulars, address G. W. WRIGHT, Groesbeck, Texas.

Mines in San Bartolo District, Pacific Coast, Tepic, Mexico. To Actual Investors Only.—For Sale.

A GROUP of very promising lode claims with considerable workings upon them, but caved in. Any amount of ore in sight. Low grade ore. Assays show, gold, 1 ounce; silver, 30 ounces, to the ton. Water power and timber close to the mines. Write for particulars to LIC. ELIAS GALINDO, Tepic, Mexico, P. O. B. 26.

COPPER claim for sale. Vein 30 feet wide, averages 15 per cent copper and \$12 gold per ton. Will sell on easy terms, or bond to responsible parties. Unencumbered, and not in litigation. MRS. FRANK RYLAND, Wickenburg, Ariz.

A LARGE Gold deposit. Will average \$15.00 free gold suitable for Cyanide process. Twelve miles from rail/road, in Arizona. Terms reasonable.
 H. P. DURRELL,
 El Paso, Texas.

TREMAIN Two-Stamp Steam Mill at Tucson, Arizona. 15-HP. Boiler Pump, and everything complete, set up ready for work. In excellent condition; used less than six months. Address, DREDGING MINING MACHINERY CO., Kansas City, Mo.

PENNSYLVANIA COAL LAND FOR SALE.—20,000 acres within 18 miles of Pittsburgh, on river and rail. Vein six to seven feet. All mine openings would be self-draining. Full description furnished. **SAMUEL BORDENKIRCHER**, 76 Hillsdale Ave., Cleveland, O.

FOR SALE.—Manganese.—An immense deposit of high-grade manganese ore; close to S. P. R. R., and but a few miles from the Pacific Coast R. R., which connects with Port Harford, where large vessels can enter. Address
Box 20, San Luis Obispo, Cal.

230 ACRES of patented land in one of the richest localities in California for \$5,000. It is quartz property, can be worked by tunnels. Has plenty free timber; cheap water. Three miles from railroad. This is a bargain. Address
Box 209, Placerville, California.

COAL LANDS FOR SALE CHEAP.—10,000 acres best coal land in Westmoreland County, Pa., convenient to water and railroad. Three openings already made. Particulars upon application. **SAM'L BORDENKIRCHER**, 76 Hillsdale Ave., Cleveland, O.

MINES IN TATEPUZCO DISTRICT, FOR SALE.—Lease or Bond.—Five old mines, forming group with 1,000 tons of ore in the dumps. Concentrating ore, averaging 30 ozs. silver and 1/2 oz. to the ton; lead, 30%; iron, 13%; zinc, 12%. Lands suitable for raising live stock; 40,000 acres, with water and timber rights. Reports and maps sent on application. Address: **LIC. ELIAS GALINDO**, Tepic, Mexico, P. O. B. No. 26.

BUYERS' GUIDE

Our Buyers' Guide is arranged to assist those who expect to purchase machinery and supplies to find quickly and easily the addresses of the leading dealers. A postal card addressed to this paper will bring you the catalogues of all houses named under any classification.

AIR COMPRESSORS

Edw P. Allis Co., Milwaukee, Wis.
M. O. Bullock Mfg. Co., Chicago, Ill.
Colorado Iron Wks., Denver, Colo.
W. H. Emanuel, Chicago, Ill.
Fairbanks, Morse & Co., Chicago, Ill.
Gates Iron Works, Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Ingersoll-Sergeant Drill Co., N. Y. City
Parke & Lacy Co., S. Francisco, Cal.
Willis Shaw, Chicago, Ill.
Sullivan Machinery Co., Chicago, Ill.
Union Gas Engine Co., S. Francisco, Cal.
Weber Gas & Gasoline Eng. Co., Kansas City, Mo.
J. W. Wigmore & Sons Co., Los Angeles, Cal.

AMALGAM PLATES

Edw P. Allis Co., Milwaukee, Wis.
E. G. Denniston, S. Francisco, Cal.
Joshua Hendy Machine Wks., S. Francisco, Cal.
San Francisco Novelty & Plating Wks., S. Francisco, Cal.
John Taylor & Co., S. Francisco, Cal.

ARC DYNAMOS

W. H. Emanuel, Denver, Colo.

ASSAYERS AND CHEMISTS

W. O. Abbott, Tombstone, Ariz.
Lew E. Aubury, Los Angeles, Cal.
Baker & Co., N. Y. City and Newark, N. J.
E. E. Burlingame & Co., Denver, Colo.
Baily & Monro, Detroit, Mich.
Wm. M. Courtes, S. Francisco, Cal.
Louis Falkenau, Philadelphia, Pa.
Hamlin & Morrison, Philadelphia, Pa.

A PROMISING group of copper mines, located 14 miles from Tucson, Pima County, Arizona. For particulars apply to **W. S. NEFF**, 137 S. Fourth Ave., Tucson, Ariz.

MINES FOR SALE; or will purchase and explore mines. Knowledge of mining in Mexico. **CHARLES VON ERXLEBEN**, Civil and Mining Engineer, U. S. Deputy Mineral Surveyor, Tucson, Ariz.

THE UNITED MINES MINING CO.

is a corporation organized under the laws of the State of Delaware, with an authorized capital stock of \$400,000; par value, \$1.00 per share; non-assessable and no personal liability of shareholders. Principal office at Wilmington, Delaware, with Delaware Charter Guarantee & Trust Co., and branch executive office at Santa Ana, Orange County, California. At par value 180,000 shares of this stock are issued for mines and oil lands, equipment and supplies. The balance, 220,000 shares, is being sold at par value for cash. Subscriptions for these shares (one or many) can now be made and paid for at par, \$1.00 per share, all down, or in advance in installments of not less than 10% per month. The certificates are issued to subscribers when fully paid. The cash thus received will be used in the furtherance of the Company's interests and the prosecution of its business affairs. The properties will be rapidly and thoroughly developed and energetically operated so as to produce the best results for the shareholders. The production of gold, copper, lead and silver ores and oil, as well as any other business co-incident therewith will be vigorously handled. This is a good healthy enterprise, with excellent propositions in hand for immediate operations. Your correspondence and patronage are requested. In your remittances send Post Office Money Order or drafts on New York City banks, payable to the United Mines Mining Co., and address all correspondence to **GILES OTIS PEARCE**, General Manager, Santa Ana, Orange County, California.

A. A. Hanks.

Clarence Hersey, S. Francisco, Cal.
Oxden Assay Co., Leadville, Colo.
R. A. Forz, Denver, Colo.
John T. Reed, Los Angeles, Cal.
D. W. Reckhart, San Bernardino, Cal.
Ricketts & Banks, El Paso, Tex.
Selby Smelting & Lead Co., N. Y. City
Ernest H. Simonds, S. Francisco, Cal.
Simonds & Wainwright, S. Francisco, Cal.
State Ore Sampling Works, N. Y. City
Wade & Wade, Los Angeles, Cal.
Henry E. Wood, Denver, Colo.

ASSAYERS' SUPPLIES

Wm. Ainsworth & Sons, Denver, Colo.
Baker & Adamson Chemical Co., Easton, Pa.
Baker & Co., N. Y. City
F. W. Braun & Co., Los Angeles, Cal.
Denver Fire Clay Co., Denver, Colo.
Queen & Co., Philadelphia, Pa.
Richards & Co., Ltd., N. Y. City
Roessler & Hasselbacher Chemical Co., N. Y. City
Smith & Thompson, Denver, Colo.
John Taylor & Co., S. Francisco, Cal.
Henry Troemner, Philadelphia, Pa.
Western Chemical Co., Denver, Colo.

BABBITT METAL

Joshua Hendy Machine Wks., S. Francisco, Cal.
BAR IRON AND STEEL
J. W. Wigmore & Sons Co., Los Angeles, Cal.

BANKERS AND BROKERS

Lytle & Co., Galena, Kan.
Morgan-Watson Mining & Construction Co., Cleveland, O.

BELT DRESSING

Jos. Dixon Crucible Co., Jersey City, N. J.

BELTING

Edw P. Allis Co., Milwaukee, Wis.
Gutta Percha & Rubber Mfg. Co., S. Francisco, Cal.
Goodyear Rubber Co., S. Francisco, Cal.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Jeffrey Mfg. Co., Columbus, O.
Link-Belt Machinery Co., Chicago, Ill.

Robins' Conveying Belt Co., N. Y. City
Shultz Belting Co., St. Louis, Mo.
S. S. Machinery Co., Denver, Colo.
J. W. Wigmore & Sons Co., Los Angeles, Cal.

BLACK DIAMONDS

Theo. Lexow, N. Y. City
I. C. Yawger, N. Y. City

BLASTING BATTERIES, ETC.

Metallie Cap Mfg. Co., N. Y. City
J. W. Wigmore & Sons Co., Los Angeles, Cal.

BOILERS

Edw P. Allis Co., Milwaukee, Wis.
California Anti-Caloric Co., S. Francisco, Cal.
Colorado Iron Works, Denver, Colo.
Fairbanks, Morse & Co., Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Jas. Leffel & Co., Springfield, O.
Chas. C. Moore & Co., S. Francisco, Cal.
Murray Iron Works, Burlington, Iowa
Ruggles-Coles Engineering Co., N. Y. City
S. S. Machinery Co., Denver, Colo.
Wm. B. Seafie & Sons, Pittsburg, Pa.
J. W. Wigmore & Sons Co., Los Angeles, Cal.

BOILER COMPOUNDS

Geo. W. Lord, Philadelphia, Pa.

BOILER COVERING

California Anti-Caloric Co., S. Francisco, Cal.

BOILER TUBE CLEANERS

Coggeshall Mfg. Co., N. Y. City

BOOKS

Mining & Metallurgical Journal, N. Y. City
Philadelphia Book Co., Philadelphia, Pa.
D. Van Nostrand Co., N. Y. City

BRASS GOODS

American Injector Co., Detroit, Mich.
Joshua Hendy Machine Wks., S. Francisco, Cal.

BUCKETS

Joshua Hendy Machine Wks., S. Francisco, Cal.
Jeffrey Mfg. Co., Columbus, O.
Link-Belt Machinery Co., Chicago, Ill.
Thomson & Boyle, Los Angeles, Cal.
Weber Gas & Gasoline Eng. Co., Kansas City, Mo.
J. W. Wigmore & Sons Co., Los Angeles, Cal.

CAP CRIMPERS

Metallie Cap Mfg. Co., N. Y. City

CARBONS

American Diamond Rock Drill Co., N. Y. City
M. O. Bullock Mfg. Co., Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Theo. Lexow, N. Y. City

CARS (DUMP AND MINE)

Edw P. Allis Co., Milwaukee, Wis.
M. O. Bullock Mfg. Co., Chicago, Ill.
Colorado Iron Works, Denver, Colo.
Fairbanks, Morse & Co., Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Thomson & Boyle, Los Angeles, Cal.
Weber Gas & Gasoline Eng. Co., Kansas City, Mo.
J. W. Wigmore & Sons Co., Los Angeles, Cal.

CASTINGS

Chrome Steel Wks., Brooklyn, N. Y.
Joshua Hendy Machine Wks., S. Francisco, Cal.

Jas. Leffel & Co., Springfield, O.
Ruggles-Coles Engineering Co., N. Y. City
Sullivan Machinery Co., Chicago, Ill.
I. C. Yawger, N. Y. City

CHEMICALS

Baker & Adamson Chemical Co., Easton, Pa.
F. W. Braun & Co., Los Angeles, Cal.
Denver Fire Clay Co., Denver, Colo.
Richards & Co., Ltd., N. Y. City
Roessler & Hasselbacher Chemical Co., N. Y. City
John Taylor & Co., S. Francisco, Cal.
Western Chemical Co., Denver, Colo.

COAL CRUSHERS

Link-Belt Machinery Co., Chicago, Ill.
Williams Patent Crusher & Pulverizer Co., St. Louis, Mo.

COAL CUTTERS

Ingersoll-Sergeant Drill Co., N. Y. City
Jeffrey Mfg. Co., Columbus, O.
Link-Belt Machinery Co., Chicago, Ill.
Sullivan Machinery Co., Chicago, Ill.

COAL-HANDLING MACHINERY

M. O. Bullock Mfg. Co., Chicago, Ill.
Columbus, O.
Link-Belt Machinery Co., Chicago, Ill.
Robins' Conveying Belt Co., N. Y. City
S. S. Machinery Co., Denver, Colo.
Trenton Iron Co., Trenton, N. J.

CONCENTRATORS, CRUSHERS, ETC.

Edw P. Allis Co., Milwaukee, Wis.
Bradley Pulverizer Co., Boston, Mass.
F. W. Braun & Co., Los Angeles, Cal.
Frue Vanning Machine Co., S. Francisco, Cal.
Gates Iron Works, Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Link-Belt Machinery Co., Chicago, Ill.
New Standard Co., Los Angeles, Cal.
Willis Shaw, Chicago, Ill.
S. S. Machinery Co., Denver, Colo.
John Taylor & Co., S. Francisco, Cal.
J. W. Wigmore & Sons Co., Los Angeles, Cal.
Williams Patent Crusher & Pulverizer Co., St. Louis, Mo.
Woodbury Concentrator, S. Francisco, Cal.

CONVEYING MACHINERY

California Wire Works, S. Francisco, Cal.
Colorado Iron Wks., Denver, Colo.
W. H. Emanuel, Denver, Colo.
Adolf Fress, Los Angeles, Cal.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Jeffrey Mfg. Co., Columbus, O.
Lidgerwood Mfg. Co., N. Y. City
Link-Belt Machinery Co., Chicago, Ill.
Robins' Conveying Belt Co., N. Y. City
Trenton Iron Co., Trenton, N. J.

COPPER DEALERS

Montana Ore Purchasing Co., N. Y. City
State Ore Sampling Co., Denver, Colo.


CRUCIBLES

F. W. Braun & Co., Los Angeles, Cal.
Denver Fire Clay Co., Denver, Colo.
Jos. Dixon Crucible Co., Jersey City, N. J.
John Taylor & Co., S. Francisco, Cal.

(Continued on page XI.)

Crushes

Large Rock



to


4

inch.

ROLL JAW CRUSHER.

SEND FOR CIRCULAR.

STURTEVANT MILL CO., 115 CLAYTON ST., BOSTON, MASS.



Finlayson

Patent Aerial
Wire Rope

For Transportation of Ore,
Dirt, Timber, etc.

Loads and Unloads
Automatically

Operated by One Man

Estimates on Application

A. LESCHEN & SONS ROPE CO.,

HOME OFFICE:
920-922 North First St., St. Louis, Mo.



Patent Flattened Strand and Round Strand

Tough, Strong, Safe, Durable

BRANCH OFFICE:
47-49 South Canal St., Chicago, Ill.

DRYERS

For Concentrates, Lime, Slag
Rock and Clay.

ROBT. G. MCGANN & COMPANY,
The Rookery, Chicago.

RUGGLES-COLES ENGINEERING CO., 39-41 Cortlandt St., N.Y.

THE CUMMER DRYERS.

For Drying
Everything Mechanically

Concentrates, ores, coal, bricks, clay, etc.

No Steam is used Hundreds in Operation

F. D. Cummer & Sons Co.,

Cleveland, Ohio

"IMPULSE" WATER WHEEL

The latest and best Water Wheel, the "Impulse." Used by the best engineers and pronounced the best.

Highest Efficiency. Best Mechanical Construction.

CATALOGUES ON
APPLICATION

AMERICAN IMPULSE WHEEL CO.

120 Liberty Street, New York

Western Agents: WOLFF & ZWICKER IRON WORKS, Portland, Oregon

Turbine
AND
Cascade

WATER WHEEL


Adapted to all Heads from
3 Feet to 2000 Feet

39 YEARS designing and
building wheels for any and all
conditions. We guarantee sat-
isfaction. State your Head and
requirements.

New pamphlet of either
style wheel on application.


James Leffel & Co.

SPRINGFIELD, OHIO, U. S. A.



First Quality in all Lines

Mining Machinery and Supplies



Steam

Engines

Hoists

Pumps

Boilers

Gasoline

Engines

Hoists

Air Compressors

Pumping Plants

Our Combined Geared Gasoline Engine and Hoist,
and Combined Gasoline Engine and Air Compressor
Especially Adapted for Mining Purposes.

Fairbanks' Standard Scales,

Mining Cars, Car Wheels, Spiral Riveted Pipe, Pipe and Fittings.

Fairbanks, Morse & Co.


Chicago,
Cleveland,
Cincinnati,
Louisville,

Indianapolis,
St. Paul,
Minneapolis,

St. Louis,
Kansas City
Omaha,

Denver,
San Francisco,
Los Angeles,
Portland, Ore.

NEW STANDARD CONCENTRATOR



A Concentrator which establishes a NEW STANDARD in
the concentration of Ores;
Saves a larger percentage of mineral, as it saves both coarse
and fine;

Requires little attention, has the greatest range of adjustment, and requires less water than any other Concentrator made;
Requires less than one-quarter horse-power to run it; has few working parts and no wearing parts; made strong and durable;
will out-last any other Concentrator made; no parts to wear out or break, and any
necessary replacements can be made in a few moments.

No. 2 New Standard Concentrator will handle from 15 to 30 tons of material per 24
hours, depending upon percentage of concentrates. The machine will produce one ton of
concentrates per 24 hours from material carrying 5 per cent of heavy mineral, turning
out a product free from silica.

The table is hung free from the operating mechanism, and the motion of the table
does not wear or strain the working parts.

Weight of machine, crated, 1600 pounds.

Price, \$400.00 f. o. b.

New Standard Concentrator Co.

Los Angeles, Cal., U. S. A.

[Western Union Code used.]

"GRAND PRIX"

At the Paris Exposition

The following Awards have been officially announced:


GRAND PRIX,	-	-	Group XI, Class 63, Mining Apparatus.
Gold Medal,	-	-	" IV, " 21, Compressors.
Silver Medal,	-	-	" VI, " 28, Models of Apparatus used on Chicago Drainage Canal.
Honorable Mention,	-	-	" IV, " 20, Small Motors on Channelers; Various Motors.

This Company has received the only GRAND PRIX awarded to any Manufacturer in this line.

The **Ingersoll-Sergeant** Drill Co.
26 CORTLANDT STREET, NEW YORK

THE EDWARD P. ALLIS COMPANY, MILWAUKEE, WISCONSIN.

**MINING,
MILLING
AND
SMELTING
PLANTS.**



AMALGAM BARREL.

**LEYNER DRILLS,
AIR COMPRESSORS,
CONCENTRATORS,
ORE FEEDERS,
ORE CRUSHERS.**

REYNOLDS CORLISS ENGINES.

SULLIVAN MACHINERY CO.

CHICAGO, ILLINOIS

Sullivan Diamond Prospecting Drills

For Prospecting for and Developing Minerals



Rock Drills for Sinking, Drifting and Stopping


CHICAGO OFFICES, Rooms 1220-1221, 135 Adams Street

DENVER, COL., OFFICE, 332 Seventeenth St.

NEW YORK OFFICE, 71 Broadway

HENSHAW, BULKLEY & CO., Agents, San Francisco, Cal.





The Copper Matting Furnace

here illustrated, shows our latest type RECTANGULAR COPPER MATTING FURNACE, with Flange Steel Jackets, and Cast Iron Auxiliary Jackets above. Being entirely independent of lower jackets and supported by the four columns and mantel frame, this Matting Furnace requires no brick work except that necessary to line the hearth.

We manufacture SMELTING FURNACES and EQUIPMENTS for the treatment of

**Gold, Silver, Lead,
Copper and Nickel Ores**

of any desired tonnage capacity above 40 tons per day and put them into successful operation under guarantee.

Write for catalogue showing different styles of furnaces. We are the originators of the Narrow Face, Large Diameter, High Speed Crushing Rolls. A full description of crushing machinery is given in a special catalogue.

We are sole manufacturers of the IMPROVED BARTLETT CONCENTRATING TABLE. Our special catalogue on this subject gives all the latest information on the concentration of Ores.

The Colorado Iron Works Co.

Established 1860

Denver, Colo., U. S. A.

GATES IRON WORKS

A Perfect
Prospector's
Mill

The Tremain Steam Stamp Mill

has helped to make many paying mines. It is cheap and portable.

The Mascot Gold Mining and Milling Company

CLEVELAND, Ohio, Jan. 14, 1899.

GATES IRON WORKS,

650 Elston Ave., Chicago, Ill.

GENTLEMEN:—In September we purchased a Tremain Steam Stamp Mill from your Company, and am pleased to say that it gave entire satisfaction. We are running it at 175 drops per minute on 60-lbs. pressure of steam, at which pressure and speed it has a capacity of 14 tons per 24 hours through a 40 mesh screen.

The machine is all that you claim for it, and we expect to order another before spring. Four other parties in our district are intending to order Tremain mills. It is giving more than satisfaction. All the old timers predicted a failure from the start, but we are pleased to state they are all in favor of it now.

Yours very truly,

(Signed) E. E. ROGERS,
President and General Manager.


Send for our Catalog No. 8

San Francisco Agents

American Manufacturers' Association
20 Fremont Street

Main Office and Works

650 Elston Ave., Chicago





Sorting Belts

Last longer than
Sorting Tables and
NEVER JAM

Robins Conveying Belt Co.
Park Row Building
New York

JEFFREY ELEVATING CONVEYING MACHINERY

NEW ILLUSTRATED
CATALOGUE

NOW READY

SEND FOR COPY

THE JEFFREY MFG. CO.
COLUMBUS, OHIO, U. S. A.

BRANCHES

41 Dey Street
New York

544 Equitable Bldg.
Denver

BUYERS' GUIDE—Continued.

CUPEL MACHINES

F W Braun & Co., Los Angeles, Cal

CYANIDE

F W Braun & Co., Los Angeles, Cal

Rossier & Hasselacher Chemical Co., N Y City

John Taylor & Co., S Francisco, Cal

CYANIDE PLANTS

Thomson & Boyle, Los Angeles, Cal

DIAMONDS

American Diamond Rock Drill Co., N Y City

M C Bullock Mfg Co., Chicago, Ill

Theo Lexow, N Y City

Sullivan Machinery Co., Chicago, Ill

I C Yawger, N Y City

DIAMOND DRILLS

American Diamond Rock Drill Co., N Y City

M C Bullock Mfg Co., Chicago, Ill

Joshua Hendy Machine Wks., S Francisco, Cal

Sullivan Machinery Co., Chicago, Ill

DIAMOND DRILL DIAMONDS

Theo Lexow, N Y City

I C Yawger, N Y City

DRAWING MATERIALS

F E Brandis, Sons & Co., Brooklyn, N Y

Eugene Dietzgen Co., Chicago, Ill

Joe Dixon Crucible Co., Jersey City, N J

Adolf Fress, Los Angeles, Cal

F C Knight & Co., Philadelphia, Pa

L Mannase Co., Chicago, Ill

Queen & Co., Philadelphia, Pa

F Weber & Co., Philadelphia, Pa

DREDGING MACHINERY

Joshua Hendy Machine Wks., S Francisco, Cal

Jeffrey Mfg Co., Columbus, O

Lidgerwood Mfg Co., N Y City

Robins Conveying Belt Co., N Y City

Weber Gas & Gasoline Eng Co., Kansas City, Mo

DRILLS (ROCK)

Edw P Allis Co., Milwaukee, Wis

American Diamond Rock Drill Co., N Y City

M C Bullock Mfg Co., Chicago, Ill

W H Emanuel, Denver, Colo

Joshua Hendy Machine Wks., S Francisco, Cal

Howells Mining Drill Co., Plymouth, Pa

Ingersoll-Sergeant Drill Co., N Y City

Willis Shaw, Chicago, Ill

Sullivan Machinery Co., Chicago, Ill

J Wigmore & Sons Co., Los Angeles, Cal

DRILL STEEL

M C Bullock Mfg Co., Chicago, Ill

Joshua Hendy Machine Wks., S Francisco, Cal

Ingersoll-Sergeant Drill Co., N Y City

J Wigmore & Sons Co., Los Angeles, Cal

DRYERS

Colorado Iron Wks., Denver, Colo

F D Cummer & Sons Co., Cleveland, O

Joshua Hendy Machine Wks., S Francisco, Cal

Ruggles-Coles Engineering Co., N Y City

DRY WASHERS

A G Godfrey, Los Angeles, Cal

DUMP CARS

Edw P Allis Co., Milwaukee, Wis

M C Bullock Mfg Co., Chicago, Ill

Colorado Iron Wks., Denver, Colo

Fairbanks, Morse & Co., Chicago, Ill

Joshua Hendy Machine Wks., S Francisco, Cal

Willis Shaw, Chicago, Ill

Thomson & Boyle, Los Angeles, Cal

Trenton Iron Co., Trenton, N J

Weber Gas & Gasoline Eng Co., Kansas City, Mo

J Wigmore & Sons Co., Los Angeles, Cal

ELECTRICAL SUPPLIES

American Impulse Wheel Co., N Y City

Joshua Hendy Machine Wks., S Francisco, Cal

Jeffrey Mfg Co., Columbus, O

John Taylor & Co., S Francisco, Cal

ELECTRIC HOISTS

Lidgerwood Mfg Co., N Y City

Link-Belt Machinery Co., Chicago, Ill

All of the Principal...

Mining Districts
of the Southwest

Reached by the

**Southern
Pacific
Company**

THREE ROUTES

Between California

and the East

SUNSET OGDEN SHASTA

Write for Literature

G. W. LUCE

Ass't Gen. Freight and Pass. Agent

Douglas Building, Los Angeles, Cal.
261 South Spring Street

If You Travel

Between the East and West the

**Santa Fe
Route**

will take you in the most comfortable way. It is the only line with its own tracks between Chicago, Kansas City, San Francisco, Los Angeles and San Diego, with daily trains carrying Pullman Palace and Tourist Sleeping Cars, Reclining Chair Cars (Seats Free). Before making your trip get full particulars of any

Santa Fe Route Agent

ELEVATORS (CONVEYORS)

Colorado Iron Wks., Denver, Colo

Joshua Hendy Machine Wks., S Francisco, Cal

Jeffrey Mfg Co., Columbus, O

Link-Belt Machinery Co., Chicago, Ill

Robins Conveying Belt Co., N Y City

S S Machinery Co., Denver, Colo

J Wigmore & Sons Co., Los Angeles, Cal

ENGINES

Edw P Allis Co., Milwaukee, Wis

M C Bullock Mfg Co., Chicago, Ill

Jas Leffel & Co., Columbus, O

Chas C Moore & Co., Springfield, O

Murray Iron Works Co., S Francisco, Cal

Oriental Gas Engine Co., Burlington, Ia

S S Machinery Co., S Francisco, Cal

Union Gas Engine Co., Denver, Colo

Weber Gas & Gasoline Eng Co., Kansas City, Mo

J Wigmore & Sons Co., Los Angeles, Cal

ENGINEERS' INSTRUMENTS

Theo Alteneder & Sons, Philadelphia, Pa

G L Berger & Sons, Boston, Mass

F W Braun & Co., Brooklyn, N Y

E Dietzgen Co., Chicago, Ill

Adolf Fress, Los Angeles, Cal

F C Knight & Co., Philadelphia, Pa

Lufkin Rule Co., Saginaw, Mich

THE BEST LOW PRICED GOOD STEAM ENGINE MADE

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.

Globe Machine Works, 135-139 W. 2d St. Cincinnati, O.



Made of FLORIDA YELLOW HEART PINE

will last a lifetime.

If ordered made of FLO RIDA CYPRESS will last forever.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

TANK CO., Box 81 Bridgeport, Florida.

**The Cleveland Mining and
Stock Exchange Co.,**

New England Building, Cleveland, Ohio.

**Morgan-Watson Mining
and Construction Co.**

809-810 New England Bldg., Cleveland, O.

A Reliable Information Bureau
for Miners and Investors to obtain
FACTS regarding Capital and
Mines. Stocks and Mines listed.
Send for prospectus.

We Buy, Sell, Lease and Bond Mines
of all kinds.

We Buy, Sell and Negotiate sales of
mining and other stocks.

We Furnish Machinery to work good
mines under special arrangement.


We Furnish Capital to develop mines.

The Johnston Patented Pipe Wrench

Our 24-inch Wrench is the Best Tool of its kind in the World

A STRICTLY HIGH-GRADE TOOL—DROP FORGED—WARRANTED

		MADE IN THREE SIZES		
		10 in.	18 in.	24 in.
STRONGEST, Never Jams				
SIMPLEST, Self-Adjusting	Pipe	1/2 to 1 in.	1 1/2 to 2 in.	2 1/2 to 3 in.
BEST, Self-Releasing	List	\$2.25	\$3.00	\$6.00



WM. B. VOLGER, Sole Manufacturer

AGENTS: 88 Chambers Street, New York

F. C. WILLIS, 225 Dearborn St., Chicago. STRONG, CARLISLE & HAMMOND CO., Cleveland.
WALTER A. ZELINICKER, 208 North 3d St., St. Louis. THE MINE & SMELTER SUPPLY CO.,
Denver, Colo., and Salt Lake City, Utah. EL PASO MINE, MILL and SUPPLY HOUSE, El
Paso, Texas. THE MILNER & KETTING CO., Birmingham, Ala.

The Latest, Best and Cheapest PIPE WRENCH



No threads to strip. No nuts to jam. Made of special wrench steel, drop-forged.

The good qualities of Chain Pipe Wrench and Screw Pipe Wrench combined, without
the faults of either. Quick, effective and positive in adjustment. Cannot slip, crush
or lock on the pipe. Made in four sizes: 10, 18, 24 and 36-in. Handling from 1/4-in.
wire to 4 1/2-in. pipe. Price no higher

R. H. PEASE, President

P. M. SHEPARD, Treasurer

C. F. RUNYON, Secretary



GATHERING RUBBER

573-579 Market Street
San Francisco, Cal.73 and 75 First Street
Portland, Oregon

Mackintoshes

Rubber Clothing Oil Clothing


Rubber Belting
Packing and Hose

Miners' Rubber Goods

"Crack Proof"

Pure Rubber Boots

Stout's "Snag Proof" Rubber Boots



BERRYMAN

Feed-Water Heaters

Water-tube and Steam-tube

Wonderful Fuel Savers


Frank L. Patterson
134 Liberty St., N. Y.

NEW Lead and Zinc Mining properties are being opened up in the Galena-Empire Kansas District and it is a good time to invest in these properties. We will tell you more about it if you will write us.

Lytle & Co., Galena, Kans.
Office, 7th & Main. Phone, 299.

Lidgerwood Hoisting Engines

Built to gauge on the Duplicate Part System. Quick Delivery Assured

HENSHAW, BULKLEY & CO., Agents
San Francisco

Mine Hoists

STEAM AND ELECTRIC

CABLEWAYS Hoisting and Conveying Devices

Send for Catalogue

Lidgerwood Mfg. Co.

96 Liberty Street, New York

BUYERS' GUIDE (Continued).

GEARING

Edw P Allis Co., Milwaukee, Wis
Joshua Hendy Machine Wks., S Francisco, Cal
Hercules Gas Engine Wks., S Francisco, Cal
Jas Leffel & Co., Springfield, O
Link-Belt Machinery Co., Chicago, Ill
J Wignmore & Sons Co., Los Angeles, Cal
Henshaw, Bulkley & Co., S Francisco, Cal

GOLD WASHERS

A G Godfrey, Los Angeles, Cal
Russell & Kinsey, Los Angeles, Cal

GREASE, GRAPITE, ETC.

Adam Cook's Sons, N Y City
Jos Dixon Crucible Co., Jersey City, N J
Joshua Hendy Machine Wks., S Francisco, Cal

GREASE AND OIL CUPS

American Injector Co., Detroit, Mich

GRIZZLY PLATES

Robt Aitchison Perforated Metal Co., Chicago, Ill

HOISTING MACHINERY

Edw P Allis Co., Milwaukee, Wis
M C Bullock Mfg Co., Chicago, Ill
Colorado Iron Wks., Denver, Colo
W H Emanuel, Denver, Colo
Fairbanks, Morse & Co., Chicago, Ill
Joshua Hendy Machine Wks., S Francisco, Cal
Jeffrey Mfg Co., Columbus, O
Lidgerwood Mfg Co., Chicago, Ill
Link-Belt Machinery Co., Chicago, Ill
Murray Iron Works Co., Burlington, Ia
S S Machinery Co., Denver, Colo
Trenton Iron Co., Trenton, N J
Union Gas Engine Co., S Francisco, Cal
Weber Gas & Gasoline Eng Co., Kansas City, Mo
J Wignmore & Sons Co., Los Angeles, Cal

HYDRAULIC MACHINERY

American Impulse Wheel Co., N Y City
W H Emanuel, Denver, Colo
Joshua Hendy Machine Wks., S Francisco, Cal
Jas Leffel & Co., Springfield, O
Weber Gas & Gasoline Eng Co., Kansas City, Mo

INJECTORS

American Injector Co., Detroit, Mich

INSULATED WIRES

Joshua Hendy Machine Wks., S Francisco, Cal
John Taylor & Co., S Francisco, Cal

LAWYERS

Harlow Mining Agency, Nogales, Ariz

LINK BELTING

Joshua Hendy Machine Wks., S Francisco, Cal
Link-Belt Machinery Co., Chicago, Ill
Taylor Iron and Steel Co., High Bridge, N J
J Wignmore & Sons Co., Los Angeles, Cal

MACHINERY (GENERAL)

Abendroth & Root, N Y City
American Diamond Rock Drill Co., N Y City
American Impulse Wheel Co., N Y City
M C Bullock Mfg Co., Chicago, Ill
Colorado Iron Wks., Denver, Colo
D Campbell Davies & Co., Durango, Mex
W H Emanuel, Denver, Colo
Fairbanks, Morse & Co., Chicago, Ill
Fulton Engine Wks., Los Angeles, Cal
Gates Iron Works, Chicago, Ill
Joshua Hendy Machine Wks., S Francisco, Cal
Jackson Drill & Mfg Co., Denver, Colo
Jeffrey Mfg Co., Columbus, O
Benj F Kelley & Son, N Y City
Link-Belt Machinery Co., S Francisco, Cal
Chas C Moore & Co., Burlington, Ia
Murray Iron Works Co., N Y City
Ruggles-Coles Engineering Co., Chicago, Ill
Willis Shaw, Denver, Colo
S S Machinery Co., Denver, Colo
Scott Supply & Tool Co., Denver, Colo
Sullivan Machinery Co., Chicago, Ill
Walsh & Sons Co., Newark, N J
Weber Gas & Gasoline Eng Co., Kansas City, Mo
J Wignmore & Sons Co., Los Angeles, Cal

MANGANESE STEEL

Taylor Iron & Steel Co., High Bridge, N J

METAL DEALERS

Baker & Co., N Y City and Newark, N J
Johnson, Matthey & Co., London, Eng
D W Reckhart, El Paso, Tex
State Ore Sample Wks., Denver, Colo

METALLURGICAL WORKS

Low E Aubury, Los Angeles, Cal
Gold & Silver Extraction Co., Denver, Colo
G G McNamara, Florence, Ariz
Montana Ore Purchasing Co., N Y City
R A Perez, Los Angeles, Cal
Rickerts & Banks, N Y City
Selby Smelting & Lead Co., S Francisco, Cal
State Ore Sample Wks., Denver, Colo
Wade & Wade, Los Angeles, Cal

MINE CARS

M C Bullock Mfg Co., Chicago, Ill
Colorado Iron Wks., Denver, Colo
Fairbanks, Morse & Co., Chicago, Ill
Joshua Hendy Machine Wks., S Francisco, Cal
Jeffrey Mfg Co., Columbus, O
Link-Belt Machinery Co., Chicago, Ill
C J Talon, S Francisco, Cal
Thomson & Boyle, Los Angeles, Cal
Weber Gas & Gasoline Eng Co., Kansas City, Mo
J Wignmore & Sons Co., Los Angeles, Cal

MINERAL SPECIMENS

Roy Hopping, N Y City

MINING COMPANIES

Lie Elias Galindo, Tepic, Mex
Lytle & Co., Galena, Kans
Montana Ore Purchasing Co., N Y City
Morgan-Watson Mining & Construction Co., Cleveland, O

MINING ENGINEERS

Low E Aubury, Los Angeles, Cal
John A Church, N Y City
Edward S Cobb, S Francisco, Cal
Wm M Courtis, Detroit, Mich
Chas L Dignowity, Boston, Mass
Harlow Mining Agency, Nogales, Ariz
C W Kempton, N Y City
M H Lyon, Joplin, Mo
J W McCoy, Chicago, Ill
P B McCoy, N Y City
G G McNamara, Boise, Ida
J F Milner, Los Angeles, Cal
R A Perez, Los Angeles, Cal
D W Reckhart, El Paso, Tex
J E Sexton, Placerville, Cal
Simonds & Wainwright, N Y City
Theo F Van Wagenen, Beaver Falls, Pa

OIL WELL MACHINERY

Keystone Driller Co., N Y City

ORE PURCHASING COMPANIES

Baker & Co., N Y City and Newark, N J
Gold & Silver Extraction Co., Denver, Colo
Montana Ore Purchasing Co., N Y City
Ogden Assay Co., Denver, Colo
Selby Smelting & Lead Co., S Francisco, Cal
State Ore Sampling Wks., Denver, Colo

ORE TESTING COMPANIES

L E Aubury, Los Angeles, Cal
Gold & Silver Extraction Co., Denver, Colo
Montana Ore Purchasing Co., N Y City

R A Perez, Los Angeles, Cal
Rickerts & Banks, N Y City
State Ore Sampling Wks., Denver, Colo
Wade & Wade, Los Angeles, Cal

PACKING

Adam Cook's Sons, N Y City
Duval Metallic Packing Co., N Y City
Goodyear Rubber Co., S Francisco, Cal
Joshua Hendy Machine Wks., S Francisco, Cal

PATENTS

C H M y Agramonte, Mexico City, Mex
Townsend Bros., Los Angeles, Cal

PERFORATED METALS

Robt Aitchison Perforated Metal Co., Chicago, Ill
Edw P Allis Co., Milwaukee, Wis
Cal Perforating Screen Co., S Francisco, Cal
Estey Wire Works, N Y City
Joshua Hendy Machine Wks., S Francisco, Cal
San Francisco Pioneer Screen Wks., S Francisco, Cal

PICKING TABLES

Link-Belt Machinery Co., Chicago, Ill

PILE DRIVERS

Ingersoll-Sergeant Drill Co., N Y City
Lidgerwood Mfg Co., N Y City
Weber Gas & Gasoline Eng Co., Kansas City, Mo

PIPES

Abendroth & Root, N Y City
Asphalt Paper Pipe Co., Los Angeles, Cal
Joshua Hendy Machine Wks., S Francisco, Cal
Wm B Seale & Sons, Pittsburg, Pa
Francis Smith & Co., S Francisco, Cal
S S Machinery Co., Denver, Colo
Thomson & Boyle, Los Angeles, Cal

PLATE IRON AND STEEL

Wm B Seale & Sons, Pittsburg, Pa
Francis Smith & Co., S Francisco, Cal

PLATINUM

Baker & Co., N Y City and Newark, N J
Johnson, Matthey & Co., London, Eng

PULVERIZERS

Bradley Pulverizer Co., Boston, Mass
Colorado Iron Wks., Denver, Colo
Gates Iron Works, Chicago, Ill
Jeffrey Mfg Co., Columbus, O
Williams Patent Crusher & Pulverizer Co., St Louis, Mo

(Continued on page XIII.)

CYANIDE TANKS! MINING

LEACHING TANKS
SOLUTION "
SUMP "
WATER "
OIL "
EXTRACTION BOXES



Estimates Furnished
for Complete
Cyanide Plants.

Send for Illustrated Catalogue
of
Cyanide Tanks and Fixtures,
Mailed Free.

35 BEALE STREET,
SAN FRANCISCO, CAL.

PACIFIC TANK COMPANY,
MANUFACTURERS.

348 E. SECOND STREET,
LOS ANGELES, CAL.

Analytical Chemists and Assayers

Analysis made of ORES, Waters, Chemicals, Clays, Etc. Umpire Work a Specialty.

Hamlin & Morrison, 114 Chestnut Street Philadelphia, Pa.

Clarence Hersey

ASSAYER AND CHEMIST

Established 1879

LEADVILLE, COLO.

Samples by Mail or Express
Receives Prompt Attention

Specimen Assay Prices
Gold, silver and lead, \$1.00; any two of the above, 75c; any one of above, 50c; copper analysis, \$1.00; platinum, nickel or tin, \$5.
Write for full Price List and Mailing Envelopes.

Assay Office and Ore Testing Works

OF HENRY E. WOOD, Assayer

Control and Umpire Assays a Specialty. Whitley Concentrator in Operation. Write for circular giving prices, etc. Ores tested in carload lots.

1734 Arapahoe Street, Denver, Colorado
Established in Colorado in 1876.

E. E. BURLINGAME & CO.,

ASSAY OFFICE AND CHEMICAL LABORATORY

Established in Colorado, 1866. Samples by mail or express will receive prompt and careful attention. Gold & Silver Bullion Refined, Melted and Assayed OR PURCHASED. Concentration Tests—100 lbs. or car load lots. Write for terms. 1736-1738 Lawrence St., Denver, Colo.

W. O. ABBOTT

ASSAYER

RELIABLE ASSAYS...

Samples by mail receive prompt attention. Gold, .50 Lead, .50 Gold and Silver, .75 Gold, Silver and Copper, 1.50

RICH ORES AND BULLION BOUGHT
Ogden Assay Co., 1429 16th Street, Denver, Colo.



Independent Assay Office.

ESTABLISHED 1888.
D. W. Reckhart, E. M., Proprietor
Agent for Ore Shippers.
Assays and Chemical Analysis.
Mineral Examined and Reported Upon.
BULLION WORK A SPECIALTY.
P. O. Box 88. Office and Laboratory.
Cor. SAN FRANCISCO & CINTRABUA STS.
EL PASO, TEXAS.

Assaying in all its Branches
Chemical Determinations Accurately Made
Tombstone, Arizona

KINDLY NOTICE

...Our...

Book Announcements

ON PAGE XV.

John T. Reed

Assayer and Analytical Chemist

Assays made for all valuable metals. Analysis made of all valuable minerals. Special attention given to the sampling of mines and estimating the value of and testing the nature of their ores. 100-pound lots of ore sampled, and working tests made by Cyanide, Amalgamation and Chlorination Processes.

Office, 522 Court Street,
San Bernardino, Cal.

SIMONDS & WAINWRIGHT

159 Front Street
New York

Chemical and Mining Engineers
Assayers and Analysts

Ores!
Ores!
Ores!

Gold, Silver and Lead Ores and Concentrates

Purchased at Reduced Rates for Treatment

Selby Smelting and Lead Company

416 Montgomery St., San Francisco

CONSIGN SHIPMENTS TO VALLEJO JUNCTION, CAL.

ESTABLISHED 1887

B. Sc. Members American Chemical Society

WADE & WADE ASSAYERS

CHEMICAL ANALYSIS, MILLING, CONCENTRATION and CYANIDE TESTS

115 1/2 N. Main St., Los Angeles, Cal.

Call and See our Stamp Mill and Frue Vanner

You'd Whistle

long and loud if you knew your daily loss in power and heat from wasted steam. Perhaps you're indifferent only because the size of the loss hasn't been proven. Vol. B. of our booklet tells our story. Just drop us a postal.

WM. S. HAINES CO.,
136 South Fourth Street,
Philadelphia, Pa.

The Heintz Steam Trap

State Ore Sampling Co.

DENVER, COLORADO.

We buy Gold, Silver, Lead, Copper, Bismuth, Uranium, Wolframite, Cobalt, molybdenite and Antimony Ores. We have modern mills for sampling ore. We also test ores for the new processes of reduction. Our long experience in the market enables us to pay the highest cash prices for all marketable ore. Write for our "Reference Book." Send analysis of your ore for prices and information.

BAILY & MONNIG, Managers



To Repair Broken Articles use

Major's Cement

Remember MAJOR'S RUBBER CEMENT, MAJOR'S LEATHER CEMENT.

Ore Testing

Complete mill for testing ores on practical scale by all processes to determine the best process adapted to treating any ore submitted.

Processes in use investigated to overcome unnecessary losses, etc.
RICKETTS & BANKS, Metallurgists and Chemists, 104 John Street, New York City



R. A. PEREZ, E.M.

Manager of the Bi-Metallic Assay Office and Chemical Laboratory

Assayer and Chemist

Assaying of Ores, Furnace Products, etc. Amalgamations and Cyanide Tests Carefully Made

Formerly: Underground and Surface Surveyor for the Coahuila and Alamo Coal Co.'s, Coahuila, Mexico.

Assistant Chemist for the Wharton Iron Furnace, Port Oran, N. J.

Chief Assayer for El Paso Smelting Works, El Paso, Texas.

Assistant Chemist, Consolidated Kansas City S. and R. Co., Argentine, Kan.

120 North Main Street, Los Angeles, Cal.



CYANIDE PROCESS

THE McARTHUR-FORREST CYANIDE PROCESS IS THE BEST

For the Treatment of Refractory and Low Grade Gold and Silver Ores and Tailings. We are the originators of the Cyanide Treatment, and have kept up with the times in all improvements in Cyanide Methods.

Successful Plants in Operation in all Western Mining States

Samples Assayed and Fully Reported Upon. Properties Examined. Designs furnished. For Terms and Particulars,

ADDRESS: THE GOLD AND SILVER EXTRACTION CO., of America, Ltd.

WILLIAM RUSSELL, Chief Chemist

GEO. A. ANDERSON, General Manager

Testing Works: 1716 Blake St., Denver, Colo.

268-2102 McPhee Building, Denver, Colo.

Fronmel Screens

THE ROBERT AITCHISON PERFORATED METAL CO.
305 & 305 DEARBORN ST. CHICAGO, ILL.

Reports on Mining and other Properties.

Proprietors of Weekly Anglo-American, a first-class Advertising Medium. Established 9 Years.

Mexican, American and Foreign Patents, Trademarks, etc.

C. H. M. y AGRAMONTE,

P. O. BOX 388. CABLE ADDRESS, "AGRA."

City of Mexico, Mexico.

WARREN'S

NATURAL ASPHALT STONE SURFACED READY ROOFING

THE surface is completed at the factory and does not require painting. Durable and economical. Comparatively fire-proof.

Genuine Trinidad Asphalt
Asphalt 2 and 3 Ply Ready Roofing

Warren Chemical & Mfg. Co., 84 Fulton St., N. Y.

DESIGNED for Application Without the Help of Skilled Roofers



Theodor Lexow
Importers of **CARBONS**
For DIAMOND DRILLS and all
Mechanical Purposes
12 to 16 John Street, New York
HENRY DEMMEYER
Successor to
I. C. YAWGER,
Victor Bishop & Co.

**IMPORTER OF
CARBONS
FOR DIAMOND DRILLS.**
21 MAIDEN LANE, NEW YORK

Eastern Prices Improved
Facilities.
Beaten Finest Work.
Lowest Prices.




Perforated Sheet Metals

For Flour and Rice Mills, Grain Separators, Shaker Screens, Gravel and Cement, Stamp Batteries, Iron, Steel, Russian Iron, American Planish, Zinc, Copper and Brass Screens, for all uses.

Established 1860.

San Francisco Pioneer JOHN W. QUICK, Proprietor.
Screen Works
221 and 223 First Street, San Francisco, Cal.

Hoskins' Patent Hydro-Carbon




Blow-Pipe and Assay Furnaces

No dust. No ashes. Cheap, effective, economical, portable and automatic. Send for Price List to

WM. HOSKINS
81 South Clark St., Room 57
CHICAGO, ILL.

Taylor's Coal Oil and Gasoline Burner, (Patented)



Patented

FOR SALE BY


PRICE, \$6.00

MINE and MILL
SUPPLIES

JOHN TAYLOR & CO., 63 FIRST ST. SAN FRANCISCO CALIFORNIA

Importers and Manufacturers of

ASSAYERS' MATERIALS, CHEMICALS AND ACIDS




(Patented)

Calkin's Automatic Cupel Machine

With this machine 600 cupels of uniform size and density can be made in one hour. They are compact, easily operated, can't get out of order and everlasting. Write for our new Descriptive Pamphlet in which all our specialties are fully described.

F. W. Braun & Co.
Manufacturers of
Modern Assayers' Appliances
LOS ANGELES, CAL.



FACTORY

3101-3141 Blake St.

OFFICE

Denver, Colo.

1742-1746 Champa St.

Sulphuric Acid

Manufactured by
Western Chemical Co.
Denver, Colo.

Also Strictly
Chemically Pure
AMMONIA and

C. P. Acids

for Laboratory Use and Fine Chemical Work

For Chlorination, Refining and other processes. Also Mariatic and Nitric Acids, Blue Vitriol, Copperas, Refined Sulphate of Soda etc.

Improved Bone Ash.

It is 100% better than Bone Ash now being used; will absorb more lead, will never crack or split in the Muffle, can be dropped before or after using without breaking. Cupels can be made and used at once; no drying required. Excessive heat has no effect on them. Will stand shipping any distance. It takes up none of the precious metals in cupelling. Cupels much quicker. Once used always used. Sold under a positive guarantee or money refunded. Now being used by all smelters and assayers who have tried it.

Price of Improved Bone Ash, \$60.00 per ton; \$3.50 per 100 lbs.; or manufactured Cupels, \$1.50 per hundred.

CUMMINGS & SWEARS, Sole Mfrs., 10 Stevenson Street San Francisco, Cal.

For Sale by Justinian Caire Co., 521-523 Market Street
Dealers in Assay Goods and Mining Supplies

P. & B. PAINT

For Mines
Smelters
Chlorination
Works
The Cyanide
Process

P. & B. Roofing put up in Rolls to lay 200 square feet, with Paint and Nails. Absolutely Acid and Alkali Proof.

PARAFFINE PAINT CO., Manufacturers, 312-314 W. 5th St., Los Angeles

BUYERS' GUIDE (Continued)

PUMPS

American Injector Co., Detroit, Mich.
Geo. Dow Pumping Engine Co., S. Francisco, Cal.
V. H. Emanuel, Denver, Colo.
Fairbanks, Morse & Co., Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Benj. F. Kelley & Son, N. Y. City
Link-Belt Machinery Co., Chicago, Ill.
Chas. C. Moore & Co., S. Francisco, Cal.
Pulsometer Steam Pump Co., N. Y. City
S. S. Machinery Co., Denver, Colo.
Weber Gas & Gasoline Eng. Co., Kansas City, Mo.
J. Wigmore & Sons Co., Los Angeles, Cal.

POWDER

California Vigor Powder Co., S. Francisco, Cal.
J. Wigmore & Sons Co., Los Angeles, Cal.

PUMPS (HAND)

Abendroth & Root, N. Y. City

QUARRYING MACHINES

W. H. Emanuel, Denver, Colo.
Sullivan Machinery Co., Chicago, Ill.

RAILROADS

Santa Fe Route, S. Francisco, Cal.
Southern Pacific Co., Los Angeles, Cal.

RAILS

C. J. Tallon, S. Francisco, Cal.

ROOFING

Paraffine Paint Co., Los Angeles, Cal.
Wm. B. Seale & Sons, Pittsburg, Pa.
Warren Chemical & Mfg. Co., N. Y. City

SCALES AND BALANCES

Wm. Ainsworth & Sons, Denver, Colo.
F. W. Braun & Co., Los Angeles, Cal.
Denver Fire Clay Co., Denver, Colo.
Adolf Froese, Los Angeles, Cal.
I. Mannasse Co., Chicago, Ill.
Queen & Co., Philadelphia, Pa.
Richards & Co., Ltd., N. Y. City
Smith & Thompson, Denver, Colo.
Henry Troemner, Philadelphia, Pa.

SCHOOLS AND COLLEGES

Heald's Business College, S. Francisco, Cal.
Michigan College of Mines, Houghton, Mich.
Van Der Naillon School, S. Francisco, Cal.

SCREENS

Robt. Atchison Perforated Metal Co., Chicago, Ill.
Edw. P. Allis Co., Milwaukee, Wis.
California Perforated Screen Co., S. Francisco, Cal.

SEPARATORS

Bestey Wire Works, Denver, Colo.
Gates Iron Works, Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Jeffrey Mfg. Co., Columbus, O.
Link-Belt Machinery Co., Chicago, Ill.
San Francisco Pioneer Screen Wks., S. Francisco, Cal.

SHOES AND DIES

Edw. P. Allis Co., Milwaukee, Wis.
Chrome Steel Works, Brooklyn, N. Y.
Colorado Iron Wks., Denver, Colo.
Gates Iron Works, Chicago, Ill.
Taylor Iron & Steel Co., High Bridge, N. J.

SMELTING WORKS

Gold & Silver Extraction Co., Denver, Colo.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Johnson, Matthey & Co., London, Eng.
Montana Ore Purchasing Co., N. Y. City
Selby Smelting & Lead Co., S. Francisco, Cal.
State Ore Sampling Wks., Denver, Colo.

SMELTING WORKS

Willis Shaw, Chicago, Ill.

STEAM

Willis Shaw, Chicago, Ill.

STEAM

Willis Shaw, Chicago, Ill.

STEAM PIPE COVERING

California Anti-Calorie Co., S. Francisco, Cal.
G. C. Fowler, S. Francisco, Cal.

STRAINERS

Abendroth & Root, N. Y. City

STRUCTURAL IRON AND STEEL

Wm. B. Seale & Sons, Pittsburg, Pa.
Joshua Hendy Machine Wks., S. Francisco, Cal.

TANKS

Edw. P. Allis Co., Milwaukee, Wis.
Colorado Iron Wks., Denver, Colo.
Cypress Tank Co., Bridgeport, Fla.
Gates Iron Works, Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Pacific Tank Co., S. Francisco, Cal.
Ruggles-Coles Engineering Co., N. Y. City
Wm. B. Seale & Sons, Pittsburg, Pa.
S. S. Machinery Co., Denver, Colo.
John Taylor & Co., S. Francisco, Cal.
Thomson & Boyle, Los Angeles, Cal.
J. Wigmore & Sons Co., Los Angeles, Cal.

TOOLS AND SUPPLIES

Scott Supply & Tool Co., Denver, Colo.
Wm. B. Volger, N. Y. City

TRANSITS (ENGINEERS')

Wm. Ainsworth & Sons, Denver, Colo.
C. L. Berger & Sons, Boston, Mass.
Adolf Froese, Los Angeles, Cal.
F. C. Knight & Co., Philadelphia, Pa.
L. Mannasse Co., Chicago, Ill.

TUBE CLEANERS

Coggeshall Mfg. Co., N. Y. City

VALVES

Abendroth & Root, N. Y. City
Joshua Hendy Machine Wks., S. Francisco, Cal.

VOLTMETERS

Abendroth & Root, N. Y. City

WATER FILTERS

Chas. C. Moore & Co., S. Francisco, Cal.
Wm. B. Seale & Sons, Pittsburg, Pa.

WELL-DRILLING MACHINERY

American Diamond Rock Drill Co., N. Y. City
M. C. Bullock Mfg. Co., Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Keystone Driller Co., Beaver Falls, Pa.
Sullivan Machinery Co., Chicago, Ill.
Weber Gas & Gasoline Eng. Co., Kansas City, Mo.

WHEELS (CAR)

Fairbanks, Morse & Co., Chicago, Ill.
Gates Iron Works, Chicago, Ill.
Joshua Hendy Machine Wks., S. Francisco, Cal.
Taylor Iron & Steel Co., High Bridge, N. J.
J. Wigmore & Sons Co., Los Angeles, Cal.

WHEELS (WATER)

American Impulse Wheel Co., N. Y. City
Jas. Leffel & Co., Springfield, O.
J. Wigmore & Sons Co., Los Angeles, Cal.

WIRE

Joshua Hendy Machine Wks., S. Francisco, Cal.
Trouton Iron Co., Trenton, N. J.
J. Wigmore & Sons Co., Los Angeles, Cal.

WIRE ROPE

Trenton Iron Co., Trenton, N. J.

WIRE ROPE TRAMWAYS

California Wire Works, S. Francisco, Cal.
Colorado Iron Wks., Denver, Colo.
W. H. Emanuel, Denver, Colo.
Joshua Hendy Machine Wks., S. Francisco, Cal.

WOOD PRESERVATIVE

Summerville Fernoline Wks., Summerville S. C.

Dow Pumps

Are Manufactured
in Great Variety

For Mining Purposes

OPERATED BY

Steam, Air, Electric or Water Power

Vertical Sinking Pumps

Bucket or Double Plunger
Pattern Deep Mine

Station Pumps

Make Known Your Wants to the

Geo. E. Dow Pumping Engine Co., San Francisco, California

Successors to the DOW STEAM PUMP WORKS

Coggeshall Steam Tube Cleaner


Sent on trial prepaid
to any address

CLEANS CLEAN, LEAVES NO MOISTURE



THE COGGESHALL MFG. CO., 116 Liberty St., New York City
AGENTS WANTED

Send for
Catalogues
of Cyanide
Plants and
Roller Mills



Lane Slow Speed Roller Mill

Slow speed gives perfect amalgamation. Extra good mill for saving fine flour or rusty gold. Crushing capacity exceeds stamps.

**Thomson &
Boyle Co.**
Sole Agents
310-314 Requesena St.
Los Angeles, Cal.



THE Mait Dry Gold Saver

The only thoroughly practical DRY WASHER ever invented; will save a larger per cent. of gold than any other machine. It is Cheap, Light and Durable.


The material used in its construction is of the best, well bolted and screwed (not nailed) together. Woodwork, spruce; lining, galvanized iron; riffle screen, No. 70 mesh, brass wire.

Small size \$35, medium size \$40, large size \$50

A. G. GODFREY, Manufacturer
206 S. Los Angeles St. Los Angeles, Cal.

TO GOLD MINERS!

Every Description of
Mining Plates Made



For Saving Gold
in Quartz and
Placer Mining

Silver Plated Copper Amalgamating Plates

Only Best Copper and Refined Silver Used
Old Mining Plates Replated. Twenty-six Medals Awarded.
Gold, Silver, Nickel, Copper and Brass Plating

Old copper mining plates bought or taken in exchange for new silver-plated plates and full value allowed. Gold extracted from old plates at a moderate cost by a new and economical process. Old plates, which often contain a surplus of gold above the cost of plating, can be re-plated.

Denniston's San Francisco Plating Works

652 Mission St., cor. Annie, San Francisco, Cal.

Telephone, Main 5931

E. G. DENNISTON, Proprietor

Estey Wire Works Co.

Manufacturers of Every Variety of


Wire Cloths Of Brass, Copper, Iron,
Galvanized and Steel Wire
of all meshes and grades. For Mining,
Milling and all other purposes.

65 Fulton Street, New York



Quartz Screens

A specialty. Round, slot
or burned slot holes. Gen-
uine Russian Iron, Homo-
geneous Steel, Cast Steel
or American planished
Iron, Zinc, Copper or
Brass Screens for all purposes.
CALIFORNIA PERFORATING SCREEN CO.
145-147 DEALE ST., SAN FRANCISCO



We Carry in Stock

Lathes, Shapers, Planers,
Drill Presses and
Iron Working Machinery
of all kinds.

Also Tools and Supplies

THE SCOTT SUPPLY & TOOL CO.
DENVER, COLORADO

SPECIALTIES

Pulleys, Shafting
Belting, Boxes
Boilers, Engines
Hoisters
Stamp Mills
Rails, Cable

And All But Little Used

Second Hand Machinery

The S. S. Machinery Co.

... DENVER, COLORADO



Patented Oct. 8, 1899.

For Water Works, Mining and Irrigation Plants.

Alkali water will not affect it. Roots will not affect it. Lighter than iron, therefore saving in freight. Will last longer in the ground than any other pipe made; and cheaper. Write for particulars.

ASPHALT PAPER PIPE CO.,

205 and 207 N. Los Angeles Street, LOS ANGELES, CAL.



The Pulsometer Steam Pump

"THE MINER'S FRIEND"

Often Imitated—Never Equaled Over 20,000 in Use

Recent Important Improvements The Handiest, Simplest and Most Efficient Steam Pump for General Mining, Quarrying, Railroad Irrigation, Drainage, Coal Washing, Tank-filling and for Pumping Back Liquids heavily impregnated with sediment. Muddy or gritty liquids handled without injury to the pump.

AGENTS

PARKE & LACY CO.,
San Francisco, Cal.

A. M. HOLTER HDW. CO.
Helena, Mont.

MITCHELL STAYER & LEWIS CO.,
Portland, Oregon.

CATALOGUE ON APPLICATION
CORRESPONDENCE SOLICITED

Pulsometer Steam Pump Co.

133 Greenwich Street, New York City

Notice to Gold Miners

Established 1865
Incorporated 1890

FOR
SAVING
GOLD

Silver-Plated Copper Amalgamated Plates

In Quartz, Gravel or Beach Mining. Made of best soft Lake Superior copper AT REDUCED PRICES. Our Plates are guaranteed, and by actual experience are proved the best in weight of Silver and durability. Old mining plates replaced, bought, or gold separated.

THOUSANDS OF ORDERS FILLED

San Francisco Novelty and Plating Works

Send for Circulars
Telephone Main 976

88, 70, 72, 74 and 76 First Street
Cor. Mission, San Francisco, Cal.

BOOKS ON MINING AND METALLURGY.

A CAREFULLY SELECTED LIST OF STANDARD WORKS FOR PRACTICAL MINERS, METALLURGISTS, MINING ENGINEERS AND METAL MANUFACTURERS, CHEMISTS AND ASSAYERS.

The Metallurgy of Gold. By M. Eissler. Fourth edition, revised and greatly enlarged. 187 illustrations. 12mo, cloth. \$5.00

A Practical Treatise on the Metallurgical Treatment of Gold-bearing Ores, including the Processes of Concentration and Chlorination, and the Assaying, Melting and Refining of Gold. Full attention is given to the developments in the cyanide processes; and in the five chapters devoted to the subject those metallurgists who desire to avail themselves of the cyanide process will find the methods of procedure described with sufficient fullness and completeness for practical purposes. Not only the working details, but full particulars of the results actually obtained, are given, while a chapter is devoted to the chemistry of the process.

The Metallurgy of Silver. By M. Eissler. A Practical Treatise on the Amalgamation, Roasting and Lixivation of Silver Ores, including the Assaying, Melting and Refining of Silver Bullion. 124 illustrations. Second edition, enlarged. 12mo, cloth. \$4.00

Contents: The Washoe Process of Free Milling on the Comstock Lode, Machinery employed in Crushing and Amalgamation, Cost and Results of Milling Operations, Treatment of Slimes and Tailings, The Washoe Process as applied in other Mining Districts, Chemistry of the Washoe Process, The Dry Process, Chlorination, Roasting and Amalgamation, Roasting Furnaces and Kindred Appliances, Sundry Appliances for Silver Milling, Concentration and Ore Dressing, Extraction of Silver by Leaching Processes, Melting and Assaying.

The Metallurgy of Argentiferous Lead. By M. Eissler. A Practical Treatise on the Smelting of Silver-Lead Ores and the Refining of Lead Bullion, including Reports on Various Smelting Establishments and Descriptions of Modern Smelting Furnaces and Plants in Europe and America. With 183 illustrations. 8vo, cloth. \$5.00

Cyanide Process for the Extraction of Gold and its Practical Application on the Witwatersrand Gold Fields in South Africa. By M. Eissler. Second edition enlarged. 8vo, cloth. Illustrations and folding plates. \$3.00

Engineering Chemistry. By Joshua Phillips. A Practical Treatise for the use of Analytical Chemists, Engineers, Iron Masters, Iron Founders, Students and others. Comprising methods of Analysis and Valuation of the principal materials used in Engineering works, with numerous Analyses, Examples and Suggestions. 314 illustrations. Second edition, revised and enlarged. 8vo, cloth. \$4.00

A Practical Treatise on Hydraulic Mining in California. By Ang. J. Bowie, Jun., M. E. With Description of the Use and Construction of Ditches, Flumes, Wrought-iron Pipes and Dams; Flow of Water on Heavy Grades and its Applicability, under High Pressure to Mining. Fifth edition. Small quarto, cloth. Illustrated. \$5.00

The Prospector's Handbook. By J. W. Anderson. A Guide for the Prospector and Traveller in search of Metal-bearing or other Valuable Minerals. Seventh edition, thoroughly revised and much enlarged. 8vo, cloth. \$1.50

A Manual of Practical Assaying. By H. Van F. Furman. Fourth edition with five Appendices on most recent methods. 8vo, cloth. \$3.00

Contents: Part I. Introductory. Part II. Determinations. Part III. Special Assays and Analysis. Part IV. Calculations.

Notes on Assaying. By P. De Peyster Ricketts, E. M. Ph. D. and Edmund H. Miller, A. M. Ph. D. 8vo, cloth. \$3.00

Prepared with special reference to the wants of the student and practical assayer. Containing also Instructions for laboratory tests by Cyanide, Chlorination, Russell Process, etc., Assays, Outfit, Rapid Volumetric Methods for the Analysis of Ores, etc.

The Alloys and their Constituents. By Prof. Robt. H. Thurston, Cornell University. Second edition. 8vo, cloth. \$2.50

Copper, Tin, Zinc, Lead, Antimony, Bismuth, Nickel, Aluminum, etc.; The Brasses, Bronzes, Copper-Tin-Zinc Alloys; Other Valuable Alloys; Their Qualities, Peculiar Characteristics; Uses and Special Adaptations; Thurston's "Maximum Alloys"; Strength of the Alloys as Commonly made and as affected by Special conditions; The Mechanical Treatment of Metals.

Notes on the Treatment of Gold Ore. By Florence O'Driscoll, 8vo, cloth. \$2.00

"It is an interesting discussion of the properties of gold, its occurrences, the methods of procedure in mining in late years, with the losses incident thereto and remedies for the same. The main object in presenting the work has been to make clear a few misconceptions on the subject, the most fatal of these being that any one method of treatment is efficacious in dealing with all classes of gold ores."—*American Manufacturer*.

Metallurgy of Silver, Gold and Mercury in the United States By Prof. Thos. Egleston, School of Mines, Columbia University. With corrections. \$7.50

Vol. I.—Silver, 8vo, cloth. \$7.50

Showing the latest practice as used in American Metallurgical Establishments. With 180 engravings and folding plates, tables, etc.

Vol. II.—Gold, Mercury, etc. Illustrated with 140 engravings and folding plates, 935 pages. 8vo, cloth. \$7.50

"These treatises cover the whole range of the metallurgy of silver, gold and mercury in this country; and in a clear, pleasing and interesting manner convey information of exceeding value to all in any manner interested in the production of these precious metals."—*Engineering News*.

Iron and Steel. By Prof. Robt. H. Thurston, Cornell University. Sixth edition, revised. 8vo, cloth. \$3.50

The Ores of Iron; Methods of Reduction; Manufacturing Processes, Chemical and Physical Properties of Iron and Steel; Strength, Ductility, Elasticity and Resistance; Effects of Time, Temperature and Repeated Strain; Methods of Test; Specifications.

"Should be in the hands not only of all Engineers but of all Mine Owners and Metallurgists as well."—*Mining Review*.

Hydraulic and Placer Mining. By E. B. Wilson, M. E. 12mo, cloth. \$2.00

Contents: Uses of Water in Mining, Geology of Placer Deposits, Gold Recovery by various methods, Panning, Cradles, Long Tom, Booming, Sluicing, Rifles, Flumes, Ditches, Dams, Pipes, Girdles, Valves, Gates, Water, Miner's Inch, Pressure Box, Diver Gravel Elevators, Exploiting, Dredging Rivers, Traction Dredgers, Appendix containing Location of Claims and General Information.

The Modern High Explosives—Nitro-Glycerine and Dynamite. By Manuel Fisser, Mining Engineer. With many illustrative plates. Third edition. 8vo, cloth. \$4.00

Their Manufacture, their Use and the Application to Mining and Military Engineering; Pyroxyline or Gun Cotton, the Fulminates, Picrates and Chlorates; also, the Chemistry and Analysis of the Elementary Bodies which enter into the Manufacture of the principal Nitro Compounds.

The Ventilation of Mines. By J. T. Beard, C. E., E. M., Secretary of the State Board of Examiners for Mine Inspectors, Iowa. 12mo, cloth. \$2.50

Designed for use in Schools and Colleges and for practical mining men in their study of the subject.

Manual of Mining. By Prof. Magnus C. Ibsen, E. M., Ph. D. Third edition, revised and enlarged. 8vo, cloth. \$4.00

For the use of Mining Engineers and Technical Schools. Treating of Preparatory and Exploratory Work. Methods of Mining, Hoisting Machinery, Pumping, Ventilation Shafts, Tunnels, Blasting, Timbering, etc.

The text has been increased by more than fifty pages in order to introduce additional matter pertaining to the design of cars hoisting appliances and fans.

Catalogue of American Localities of Minerals. By E. S. Dana. Reprinted from sixth edition of the System. 8vo, cloth. \$1.00

A Description of Minerals of Commercial Value. By D. M. Barringer, A. M., LL. B. 168 pages. Oblong, morocco binding. \$2.50

A Practical Reference Book for the Miner, Prospector and Business Man, or any Person who may be interested in the Extraction or Treatment of the Various Metallic or Non-metallic Minerals and for Students either in Field-work or Laboratory.

The Metallurgy of Iron. By Thomas Turner, Associate of the Royal School of Mines. Illustrated by 80 engravings, octavo, 381 pages. cloth. \$5.00

This book is primarily intended for persons who are connected with the manufacture of iron and steel, and who may be assumed to have already some general knowledge of the subject discussed. At the same time the volume may not be without interest to others than those for whom it was specially prepared.

A most valuable summary of useful knowledge relating to every method and stage in the manufacture of cast and wrought iron. An exhaustive and really needed compilation. —*Bulletin of the American Iron and Steel Association*.

The Chlorination Process. By E. B. Wilson, E. M., 12mo, cloth. \$1.50

Contents: Lixivation by Chlorine Solutions; Preparation of the Ore-Roasting Furnaces; The Leaching Process; Filtering; Precipitation; Refining the Precipitates; Resume of Chlorination and Plant; Cost of Chlorination.

A Treatise on Mine-Surveying. By B. H. Brough, Associate of Royal School of Mines. With 102 illustrations. Octavo, 340 pages, cloth. \$2.50

The work is intended primarily for students; and, at the same time, it will also be found useful as a companion to the standard works of reference on land surveying. The methods of surveying in the Pennsylvania anthracite mines are fully dwelt on, and the most recent forms of American instruments are described and illustrated. A description is also given of the methods adopted in the survey of metalliferous mine-claims in the Western United States.

"It is the kind of book which has long been wanted, and no English-speaking mine agent or mining student will consider his technical library complete without it."—*Nature*.

Prospecting for Minerals. A Practical Handbook for Prospectors, Explorers, Settlers and all interested in the Opening up and Development of New Land. By S. Herbert Cox. With illustrations. Large crown octavo. \$2.00

The object of this volume is to give a sketch of those subjects which underlie the calling of the prospector without encroaching to any great extent upon the provinces occupied by the sciences of mineralogy and geology or the arts of mining and metallurgy. To the practical prospector it may give certain hints as regards the recognition of minerals with which he is unacquainted, while to the student it may afford an introduction to the subject which will be of use in directing his work into the proper channels.

Getting Gold. A Gold-Mining Hand-Book for Practical Men. By J. C. F. Johnson, F. G. S., A. I. M. E. With illustrations. Crown octavo, cloth. \$1.50

A compendium, in specially concrete form, of useful information respecting the processes of winning from the soil and after-treatment of gold and gold ores, including some original discoveries by the author. Practical information, original and selected, is given to mining company directors, mine managers, quartzmill operators and prospectors.

A Text-Book of Assaying. By C. and J. J. Beringer. For the use of those connected with mines. Third edition. With numerous Diagrams and Index. Crown octavo. 400 pages. Cloth. \$3.25

Prepared to meet the existing want of a practical "handy-book" for the assayer. The author has given the results of a series of experiments showing the effect of varying conditions on the accuracy of the process. Statements like those generally made, that "this or that substance interferes" are insufficient. It is necessary to know under what conditions and extent.

"A really meritorious work, that may be safely depended upon either for systematic instruction or for reference."—*Nature*.

Blasting. By Oscar Guttman, Assoc. M. Inst. C. E. A Hand Book for the use of Engineers, and others engaged in Mining, Tunneling, Quarrying, etc. With 136 illustrations. Octavo, cloth. \$3.50

Mr. Guttman's "Blasting" is the only work on the subject which gives full information as to the new methods adopted since the introduction of dynamite, and at the same time, the results of many years practical experience both in mining work and in the manufacture of explosives. It therefore presents in concise form all that has been proved good in the various methods of procedure.

Electric Smelting and Refining. A Practical Manual of the Extraction and Treatment of Metals by Electrical Methods. The "Elektro-Metallurgie" of Dr. W. Borchers, translated by Walter G. McMillan, F. I. C., F. C. S. With numerous illustrations and folding plates. Large octavo. \$6.50

Dr. Borchers's treatise is practical throughout. It confines itself to one branch of electro-chemistry—viz., electrolysis, a subject which is daily becoming of more and more importance to the practical metallurgist and manufacturer. In the extraction of Aluminum, the refining of copper, the treatment of gold and other metals, electrical processes are fast taking the place of the older methods.

"Dr. Borchers's well-known work must of necessity be required by every one interested in the subject. It is excellently put in English, with additional matter by Mr. McMillan."—*Nature*.

The Story of American Coals. By William Jasper Nicolls, M. Am. Sec. C. E. Buckram, gilt top, deckle edges, with complete index. \$3.50

"It is as much historical as scientific, and scientific without being at all technical. The author, Mr. Nicolls, has adopted a pleasing simple style of writing which causes the reader to be loath to lay the book down until it is finished."—*Phila. Ledger*.

Sent Post Paid to any address on receipt of Price.

We will endeavor to secure, for subscribers and customers, any other book on Mining, Metallurgy, and kindred subjects.

Address, Book Department, THE MINING AND METALLURGICAL JOURNAL, 32 Broadway, New York City.



DOUBLE CYLINDER HOISTING ENGINE

Joshua Hendy Machine Works, 38 to 44 Fremont Street San Francisco, Cal.

Manufacturers of and Dealers in

The Latest
Improved...

Quartz Milling, Pumping,
Hoisting and Smelting Plants,
Air Compressors and Rock Drills


Plans, Specifications and
Estimates of Cost Submitted
and Contracts Entered
into for Furnishing and
Erecting Mining and Milling
Plants for all conditions
of Use

"Hendy" Improved "Triple-Discharge" Two-Stamp Quartz Mills

Boilers, Engines and Pumps of all Capacities

The Jackson Hand Power Rock Drill

Handled and Operated by
One Man, will do the Work
of Two to Four Men . . .




THORNTON N. MOTLEY COMPANY (Inc.)
49 John Street, New York

We Supply Everything
for Mines and Mining

THE JACKSON DRILL & MFG. CO., 1756 Larimer St., Denver, Colo.

Write for Catalogue



MURRAY IRON WORKS COMPANY

HOISTING

SLIDE-VALVE
AND CORLISS ENGINES

We have special facilities for furnishing machinery to Mines, Mills and Smelters at short notice.


Send for
Catalogue No. 40

Burlington, Iowa

JOHN WIGMORE & SONS CO.

SELL

Goulds Pumps



117-123 S. LOS ANGELES STREET, LOS ANGELES, CAL.

The Williams Patent

Coal Crusher

A New Machine

We guarantee Greater Capacity per Horse Power than by any other means

The Hammers or Teeth are HINGED so as to strike a Heavy, and, at the same time, a Flexible Blow. They cannot break even if you drop a coupling pin into the machine.

Pat. Aug. 13, 1895

Aug. 31, 1897


Sept. 28, 1897

Oct. 26, 1897

May 24, 1898

Other patents allowed

Repairs are
Trifling . . .



Any persons manufacturing or using a Hinged Hammer Pulverizer, other than ours, are infringers of our patents, and will be promptly prosecuted

A FEW USERS

Ashland Coal & Coke Co., Ashland, W. Va.
Broth-Bowen Coal & Coke Co., Bramwell, W. Va.
Crow's Nest Coal & Coke Co., Fernie, B. C.
Elkhorn Coal & Coke Co., Mayberry, W. Va.
Goodwill Coal & Coke Co., Goodwill, W. Va.
Greenbrier Coal & Coke Co., McDowell, W. Va.
Houston Coal & Coke Co., Elkhorn, W. Va.
Indian Ridge Coal & Coke Co., Worth, W. Va.
Keystone Coal & Coke Co., Keystone, W. Va.
Lehigh-Wilkesbarre Coal & Coke Co., Ashley, Pa.
Lehigh-Wilkesbarre Coal & Coke Co., Wanamie, Pa.
Louisville Coal & Coke Co., Goodwill, W. Va.
McDowell Coal & Coke Co., McDowell, W. Va.
Norfolk Coal & Coke Co., Mayberry, W. Va.
Rifle Coal & Coke Co., Worth, W. Va.
Roanoke Coal & Coke Co., Worth, W. Va.
W. P. Reid Coal & Coke Co., Thurmond, W. Va.
Shawnee Coal & Coke Co., Eckman, W. Va.
Samokin Coal & Coke Co., Mayberry, W. Va.
Upland Coal & Coke Co., Elkhorn, W. Va.

UPLAND COAL & COKE CO.

ELKHORN, W. Va., June 20, 1900.

WILLIAMS CRUSHER CO., St. Louis,

GENTLEMEN:—Replying to your inquiry, will say that we have had your Crusher in almost constant use during the past ten months, reducing Pocahontas coal to slack for our coke ovens. It has given no trouble at all, has required no repairs whatever, will apparently crush anything crushable, as sandstone, slate, bone and sulphur band, the rock so fatal to other would-be crushers, are reduced as readily, apparently, as the coal itself.

Even car couplings, coupling pins and other stray pieces of iron and steel have no terrors for it. It cannot crush them, it is true, but it keeps overlastingly hammering at them until the machinery is stopped and they are taken out.

Thus far, we can detect no damage that they have done the Crusher. I do not know from personal experience how your machine may work on all the materials for which you recommend it, but I will say very frankly that when it comes to a simple highly efficient coal crusher that will run right along with little or no attention, that will actually crush, not merely crack the coal, you have the real thing, there are no others.

Very truly yours,

JOHN J. LINCOLN, Gen. Mgr.

The Williams Patent Crusher and Pulverizer Company

Main Office and Works: St. Louis, Mo.

West Virginia Office: F. L. Schoew, Bramwell, W. Va.; Philadelphia, J. W. Tierney, Stephen Girard Bldg.;
New York, G. W. Barton, Washington Life Bldg.